



INVITATION FOR BID (IFB)

1. The Chairman, Ministry Procurement Committee, on behalf of the Road Development Authority (RDA), invites sealed bids from eligible and qualified bidders for the project described below:-

| Contract No. | Contract Name | Engineer's Estimate w/o contingencies (Rs. Mn) | CIDA Grade | Bid Security (Rs. Mn) | Contract Period (Calendar days) |
|-----------------------------|--|--|-------------|-----------------------|---------------------------------|
| RDA/DC/UVA/FD/ GOSL/2023/02 | CONSTRUCTION OF RAJAMAWATHA EXTENSION ROAD FROM KETAWALA TO MASPANNA (FROM CH 7+560km TO CH 9+300km), INCLUDING TWO BRIDGES AT CH 07+960km AND CH 08+380km | 498.3 | C1 or above | 7.0 | 546 |

2. The work consists of construction of road and two bridges at CH:07+960 and CH: 08+380 km on Rajamawatha Extension Road from Ketawala to Maspenna in Badulla District.

The above work includes subbase, base, shoulder, surfacing, drainage, structures, incidental construction of road section and substructure, superstructure and approach roads of bridges.

3. Bidding will be conducted through the National Competitive Bidding Procedure.
4. To be eligible for contract award, the successful bidder shall be currently registered with the Construction Industry Development Authority (CIDA) in grade given in the above table in **Bridges and Highways** specialty.
5. Interested bidders may obtain further information from the following offices and inspect the bidding documents via www.rda.gov.lk from **10/04/2023**.

a. Provincial Director (Uva), Road Development Authority, No. 40, Dharmapala Mawatha, Bandarawela.
T.P : 057-2222170 Fax : 057-2222170

b. Director (Construction), Road Development Authority, 3rd Floor, "Maganeguma Mahamedura", 216, Denzil Kobbekaduwa Mawatha, Battaramulla.
T P :011-2864388 Fax : 011-2861821

6. The Pre-Bid meeting will be held at **10:00 hrs on 19/04/2023** at the office of the Provincial Director (Uva), Road Development Authority, No. 40, Dharmapala Mawatha, Bandarawela and a site visit will be arranged thereafter if necessary.

7. A complete set of Bidding Document in English language shall be purchased by the interested bidders via email on submission of a written application and valid cash deposit slip of non - refundable tender fee (contract number and name of the contractor should be indicated on the cash deposit slip) to Director Construction, RDA via email from **10/04/2023** until **02/05/2023** during **09:00 hrs to 15:00 hrs** for above contract. The email address is construction.rda@gmail.com

Non-refundable tender fee of **Rs. 69,000.00 (with VAT)** for the bidding document can be paid by depositing cash to the following bank account.

Account Name : **Director General - RDA**
Account Number : **0000001943**
Bank Name : **Bank of Ceylon - Corporate Branch**

Original/valid cash deposit slips should be submitted with the Bids at the submission of bids and it will be checked. The bids without the original/ valid cash deposit slip will be rejected.

As per the Public Contract Act No. 3 of 1987, only the Agents and Successful winners of tenders shall be registered in Department of Registrar of Companies.

8. Bid shall be accompanied by a Bid- Security for an amount given in the above table. Bid- Security shall be valid up to **25/10/2023**.
9. Bids shall be delivered in **duplicate** to the **Chairman, Ministry Procurement Committee, Ministry of Transport and Highways, Procurement Division, 7th Floor, "Maganeguma Mahamedura", Denzil Kobbekaduwa Mawatha, Battaramulla** on or before **14:00 hrs on 03/05/2023**. Late bids will be rejected. Bids will be opened soon after the closing, in the presence of the bidders' or their representatives who choose to attend.
10. Bid shall be valid up to **27/09/2023**.

**The Chairman,
Ministry Procurement Committee,
Ministry of Transport & Highways,
Procurement Division,
7th Floor, "Maganeguma Mahamedura",
Denzil Kobbekaduwa Mawatha, Battaramulla.**

DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA

MINISTRY OF TRANSPORT AND HIGHWAYS

ROAD DEVELOPMENT AUTHORITY



BIDDING DOCUMENT

FOR

**CONSTRUCTION OF RAJAMAWATHA EXTENTION ROAD FROM KETAWALA
TO MASPANNA (FROM CH 7+560km TO CH 9+300 km), INCLUDING TWO BRIDGES
AT CH 7+960 km AND CH 8+380 km**

CONTRACT NO. RDA/DC/UVA/FD/GOSL/2023/02

BID SUBMITTED BY


.....

[Name of the Bidder]

CONTENTS

| | Page |
|---|-------------|
| Project Location Map | 03 |
| Volume 1 | 05 |
| Section 1 Instructions to Bidders | 07 |
| Section 3 Conditions of Contract | 08 |
| Section 5 Standard Forms - Contract | 09 |
| | |
| Volume 2 | 15 |
| Invitation for Bids | 17 |
| Section 2 Bidding Data | 18 |
| Section 4 Contract Data | 25 |
| Section 6 Specifications | 31 |
| Section 7 Form of Bid | 44 |
| Section 8 Bill of Quantities | 46 |
| Section 9 Schedules | 61 |
| Section 11 Standard Forms (Bid) | 71 |
| Section 10 Drawings | 75 |

Project Location Map



RL

Introduction

This Bidding Document has two parts, namely, Volume 1 and Volume 2.

The bidders are expected to buy the following Standard Bidding Document from the Construction Industry Development Authority (CIDA) (former ICTAD): -

STANDARD BIDDING DOCUMENT
PROCUREMENT OF WORKS
MAJOR CONTRACTS
SECOND EDITION – JANUARY 2007 with addendum issued in October 2009 by
ICTAD
ICTAD PUBLICATION NO. – ICTAD/SBD/02

This Bidding Document shall be read in conjunction with the above Standard Bidding Document.

The Address of CIDA is

Construction Industry Development Authority
'Savsiripaya' 123, Wijerama Mawatha,
Colombo-07

VOLUME 1

REFERENCE ONLY

VOLUME 1

| | | |
|----------------|----------|---------------------------|
| Section | 1 | Instruction to Bidders |
| Section | 3 | Conditions of Contract |
| Section | 5 | Standard Forms (Contract) |

REFERENCE ONLY

Section - 1

Instruction to Bidders

The text of this 'Instructions to Bidders' is found in the 'Standard Bidding Document Procurement of Works Major Contracts '

ICTAD Publication No. ICTAD/SBD/02 – Second Edition – January 2007 with **Addendum issued in October 2009 by ICTAD**

This publication is copyright and bidders, if they do not already possess a copy, may obtain it from:

Construction Industry Development Authority
'Savsiripaya'
123, Wijerama Mawatha
Colombo-07

This has to be read in conjunction with Section 2 - 'Bidding Data of this Bidding Document. Wherever the Clauses of the Section 1 - 'Instruction to Bidders' have to be modified and/or supplemented, it is done through the text in the Section -2 – 'Bidding Data'.

Section - 5

Standard Forms (Contract)

- Letter of Acceptance
- Performance Guarantee
- Form of Agreement
- Advance Payment Security
- Retention Money Guarantee

FORM OF LETTER OF ACCEPTANCE

_____ [Date]

[Contractor's Name & Address]

This is to notify you that your bid dated for the construction and remedying the defects of the **'CONSTRUCTION OF RAJAMAWATHA EXTENTION ROAD FROM KETAWALA TO MASPANNA (FROM CH 7+560km TO CH 9+300 km), INCLUDING TWO BRIDGES AT CH 7+960 km AND CH 8+380 km '** under Contract No: RDA/DC/UVA/FD/GOSL/2023/02 for the Contract Price of Rupees as corrected in accordance with Instruction to Bidders is hereby accepted.

You are hereby instructed to proceed with the execution of the said Works in accordance with the Contract Documents.

The Commencement Date shall be

The amount of Performance Security is.....

The Performance Security shall be submitted on or before

Director General
Road Development Authority

FORM OF PERFORMANCE SECURITY

(Unconditional)

.....
[Issuing Agency's Name, and Address of Issuing Branch or Office]

Beneficiary: Director General, Road Development Authority (hereinafter called and referred to as "the Employer") 1st floor, "Maganeguma Mahamedura", 216, Denzil Kobekaduwa Mawatha, Battaramulla.

Date:

PERFORMANCE GUARANTEE No.:

We have been informed that [Name of Contractor]

(hereinafter called, "the Contractor") has entered into Contract No **RDA/DC/UVA/FD/GOSL/2023/02** dated with you, for the '**CONSTRUCTION OF RAJAMAWATHA EXTENTION ROAD FROM KETAWALA TO MASPANNA (FROM CH 7+560km TO CH 9+300 km), INCLUDING TWO BRIDGES AT CH 7+960 km AND CH 8+380 km** ', (hereinafter called "the Contract").

Furthermore, we understand that, according to the Conditions of the Contract, a performance guarantee is required.

At the request of the Contractor, we [name of Agency] hereby irrevocably undertake to pay you any sum or sums not exceeding in total an amount of [amount in figures] (.....) [amount in words], upon receipt by us of your first demand in writing accompanied by a written statement stating that the Contractor is in breach of its obligation(s) under the Contract, without your needing to prove or to show grounds for your demand or the sum specified therein.

This guarantee shall expire, no later than the day of2023. [28 days beyond the time for Completion] and any demand for payment under it must be received by us at this office on or before that date.

Name, Signature and the Seal of the Agency:

Name of the Organization

Designation

Date:

Witness:

Name NIC NoSignature

.....

Name NIC NoSignature

.....

FORM OF AGREEMENT

This Agreement made on the[day] of.[Month] 2023, between the Road Development Authority established by the Road Development Authority Act No. 73 of 1981, situated at “Maganeguma Mahamedura”, 216, Denzil Kobbekaduwa mawatha, Battaramulla, (hereinafter called and referred to as “ the Employer”), of the one part, and.....[name and address of Contractor])(hereinafter called and referred to as “the Contractor”), of the other part:

Whereas the Employer desires that the Contractor execute ‘**CONSTRUCTION OF RAJAMAWATHA EXTENTION ROAD FROM KETAWALA TO MASPANNA (FROM CH 7+560km TO CH 9+300 km), INCLUDING TWO BRIDGES AT CH 7+960 km AND CH 8+380 km ’**, under Contract No: **RDA/DC/UVA/FD/GOSL/2023/02** (hereinafter called and referred to as “the Works”) and the Employer has accepted the Bid by the Contractor for the execution and completion of such Works and remedying of any defects therein.

The Employer and the Contractor agree as follows:

1. In this Agreement words and expressions shall have the same meanings as are respectively assigned to them in the Contract.
2. In consideration of the payments to be made by the Employer to the Contractor as indicated in this Agreement, the Contractor hereby covenants with the Employer to execute and complete the Works and remedy any defects therein in conformity in all respects with the provisions of the Contract.
3. The Employer hereby covenants to pay the Contractor in consideration of the execution and completion of the Works and remedying any defects therein, the Contract Price or such other sum as may become payable under the provisions of the Contract at the times and in the manner prescribed by the Contract.

In Witness whereof the parties hereto have caused this Agreement to be executed on the day and year aforementioned in accordance with laws of Sri Lanka.

| | |
|--|---|
| Name: | Chairman Road Development Authority |
| Authorised Signatory of Contractor Common Seal | Board Member, RDA On behalf of the Employer |
| In the presence of Witness: Name | Common Seal In the presence of Witness: Name |
| NIC No. Address | NIC No. Address |

FORM OF ADVANCE PAYMENT SECURITY

.....
[Name and address of Agency, and Address of Issuing Branch or Office]

Beneficiary: Director General , Road Development Authority (hereinafter called and referred to as “the Employer”) 1st floor, “Maganeguma Mahamedura”, 216, Denzil Kobekaduwa Mawatha, Battaramulla.

Date:

ADVANCE PAYMENT GUARANTEE No.:.....

We have been informed that [name of Contractor]
(hereinafter called, “the Contractor”) has entered into Contract No: **RDA/DC/UVA/FD/GOSL/2023/02** dated2023, with you, for the ‘**CONSTRUCTION OF RAJAMAWATHA EXTENTION ROAD FROM KETAWALA TO MASPANNA (FROM CH 7+560km TO CH 9+300 km), INCLUDING TWO BRIDGES AT CH 7+960 km AND CH 8+380 km**’, (hereinafter called “the Contract”).

Furthermore, we understand that, according to the Conditions of the Contract, an advance payment in the sum[amount in figures] (.....) [amount in words] is to be made against an advance payment guarantee.

At the request of the Contractor, we [name of issuing Agency] hereby irrevocably undertake to pay you any sum or sums not exceeding in total an amount of[amount in figures] (.....) [amount in words], upon receipt by us of your first demand in writing accompanied by a written statement stating that the Contractor is in breach of its obligation in repayment of the advance payment under the Contract.

The maximum amount of this guarantee shall be progressively reduced by the amount of the advance payment repaid by the Contractor.

This guarantee shall expire on[insert the date, 28 days beyond the Time for Completion]

Consequently, any demand for payment under this guarantee must be received by us at this office on or before that date.

Name, Signature and the Seal of the Agency:

Designation

Name of the Organization

Date:

Witness:

Name NIC NoSignature.....

Name NIC NoSignature

FORM OF RETENTION MONEY GUARANTEE

(Issuing Agency's Name and Address of Issuing Branch or Office)

Beneficiary: Director General, Road Development Authority, 1st Floor, Maganeguma Mahamedura",216, Denzil Kobekaduwa Mawatha, Battaramulla.

Date: -----

RETENTION MONEY GUARANTEE No.:-----

We have been informed that -----(name of Contractor) (hereinafter called "the Contractor") had entered into Contract No: **RDA/DC/UVA/FD/GOSL/2023/02** dated2023, with you, for the execution of **'CONSTRUCTION OF RAJAMAWATHA EXTENTION ROAD FROM KETAWALA TO MASPANNA (FROM CH 7+560km TO CH 9+300 km), INCLUDING TWO BRIDGES AT CH 7+960 km AND CH 8+380 km '**, (hereinafter called "the Contract")

Furthermore, we understand that, according to the Conditions of Contract, when the works have been taken over and the first half of the Retention Money has been certified for payment, payment of the second half of the Retention Money may be made against a Retention Money guarantee.

At the request of the Contractor, we -----(name of agency) hereby irrevocably undertake to pay you any sum or sums not exceeding in total an amount of ----- (amount in figures)-----
----- (amount in words) upon receipt by us of your first demand in writing accompanied by a written statement stating that the Contractor is in breach of its obligation under the Contract because the Contractor has not attended to the defects in accordance with the Contract.

The guarantee shall expire, at the latest, ----- (insert 28 days after the end of the Defects Notification Period). Consequently, any demand for payment under this guarantee must be received by us at this office on or before that date.

Name, Signature and the Seal of the Agency:

Name of the Organization

Designation

Date:

Witness:

Name NIC NoSignature

Name NIC NoSignature

VOLUME - 2

- Invitation For Bids
- Section 2 Bidding Data
- Section 4 Contract Data
- Section 6 Specifications
- Section 7 Form of Bid
- Section 8 Bill of Quantities
- Section 9 Schedules
- Section 11 Standard Forms (Bid)
- Section 10 Drawings

REFERENCE ONLY

GOVERNMENT OF THE DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF TRANSPORT AND HIGHWAYS
ROAD DEVELOPMENT AUTHORITY
INVITATION FOR BIDS

1. The Chairman, Ministry Procurement Committee, on behalf of the Road Development Authority (RDA), invites sealed bids from eligible and qualified bidders for the *project* described below:-

| Contract No. | Contract Name | Engineer's Estimate w/o contingencies (Rs. Mn) | CIDA Grade | Bid Security (Rs. Mn) | Contract Period (Calendar days) |
|----------------------------|--|--|--------------------|-----------------------|---------------------------------|
| RDA/DC/UVA/FD/GOSL/2023/02 | CONSTRUCTION OF RAJAMAWATHA EXTENSION ROAD FROM KETAWALA TO MASPANNA (FROM CH 7+560km TO CH 9+300km), INCLUDING TWO BRIDGES AT CH 07+960km AND CH 08+380km | 498.3 | C1 or above | 7.0 | 546 |

2. The work consists of construction of road and two bridges at CH:07+960 and CH: 08+380 km on Rajamawatha Extension Road from Ketawala to Maspenna in Badulla District.

The above work includes subbase, base, shoulder, surfacing, drainage, structures, incidental construction of road section and substructure, superstructure and approach roads of bridges.

3. Bidding will be conducted through the National Competitive Bidding Procedure.
4. To be eligible for contract award, the successful bidder shall be currently registered with the Construction Industry Development Authority (CIDA) in grade given in the above table in **Bridges and Highways** specialty.
5. Interested bidders may obtain further information from the following offices and inspect the bidding documents via www.rda.gov.lk from **10/04/2023**
- Provincial Director (Uva), Road Development Authority, No. 40, Dharmapala Mawatha, Bandarawela.
T P 057-2222170 & Fax: 057-2222170
 - Director (Construction), Road Development Authority, 3rd Floor, "Maganeguma Mahamedura", 216, Denzil Kobbekaduwa Mawatha, Battaramulla. T P :011-2864388 Fax: 011-2861821
6. The Pre-Bid meeting will be held at **10:00 hrs. on 19/04/2023** at the office of the **Provincial Director (Uva), Road Development Authority, No. 40, Dharmapala Mawatha, Bandarawela** and a site visit will be arranged thereafter if necessary.
7. A complete set of Bidding Document in English language shall be purchased by the interested bidders via email on submission of a written application and valid cash deposit slip of non – refundable tender fee (contract number and name of the contractor should be indicated on the cash deposit slip) to Director Construction, RDA via email from **10/04/2023** until **02/05/2023** during 09:00 hrs to 15:00 hrs for above contract. The email address is **construction.rda@gmail.com**

Non-refundable tender fee of Rs. **69, 000.00** (with VAT) for the bidding document can be paid by depositing cash to the following bank account.

Account Name : Director General – RDA
Account Number : 0000001943
Bank Name : Bank of Ceylon - Corporate Branch

Original/valid cash deposit slips should be submitted with the Bids at the submission of bids and it will be checked. The bids without the original/ valid cash deposit slip will be rejected.

As per the Public Contract Act No. 3 of 1987, only the Agents and Successful winners of tenders shall be registered in Department of Registrar of Companies.

8. Bid shall be accompanied by a Bid- Security for an amount given in the above table. Bid- Security shall be valid up to **25/10/2023**.
9. Bids shall be delivered in **duplicate** to the **Chairman, Ministry Procurement Committee, Ministry of Transport and Highways, Procurement Division, 7th Floor, "Maganeguma Mahamedura", Denzil Kobbekaduwa Mawatha, Battaramulla** on or before **14:00 hrs on 03/05/2023** Late bids will be rejected. Bids will be opened soon after the closing, in the presence of the bidders' or their representatives who choose to attend.
10. Bid shall be valid up to **27/09/2023**

**The Chairman,
Ministry Procurement Committee
Ministry of Transport & Highways,
Procurement Division
7th Floor, "Maganeguma Mahamedura", Denzil Kobbekaduwa Mawatha, Battaramulla.**

SECTION - 2

BIDDING DATA

This Section shall be read in conjunction with Section 1- 'Instruction to Bidders', and is intended to provide specific information in relation to corresponding clauses in Section 1. Wherever there is a discrepancy, the provisions of Section-2-Bidding Data shall supersede those provided in the Section 1 – Instructions to Bidders.

The Clause numbers given in this Section correspond to the Clauses with the same numbers in the Section 1 – 'Instruction to Bidders'.

Whenever a Clause number appears in this Section, it means the information in the corresponding Clause in Section 1 is supplemented and/or modified according to the information in the Clause in Section 2.

If a Clause number does not appear in this Section, it means the Clause with the corresponding number in Section 1, remains unchanged.

BIDDING DATA

**Instructions
to Bidders
Clause
Reference**

1.1

Employer's Name and Address

Employer is the Director General, Road Development Authority established by the Road Development Authority Act No. 73 of 1981.

Address of the Employer is

Director General

Road Development Authority

1st Floor, "Maganeguma Mahamedura" 216, Denzil Kobbekaduwa Mawatha, Battaramulla.

Telephone: 0112862795 Fax: 0112872272

E-mail:

Scope of Works

'CONSTRUCTION OF RAJAMAWATHA EXTENTION ROAD FROM KETAWALA TO MASPANNA (FROM CH 7+560km TO CH 9+300 km), INCLUDING TWO BRIDGES AT CH 7+960 km AND CH 8+380 km '

The work consists of construction of road section and two bridges at CH:07+960 and CH: 08+380 km on Rajamawatha Extension Road from Ketawala to Maspanna.

The road construction includes subbase, base, shoulder, surfacing, drainage, structures and incidental construction.

The two-bridge construction includes construction of substructure and superstructure (with 9.5 m and 13.5m PSC concrete beams respectively) and construction of approaches.

1.2

Time for Completion

The Time for Completion of the whole of the Works shall be **546 Days** from the Commencement Date.

2.1

Source of funds

Budget allocation under Flood damage rehabilitation for Road Development Authority. The source of funds is Government of Sri Lanka (GOSL)

3

Add a new sub-Clause 3.3

Clause 3.3

A misrepresentation or omission of facts in order to influence the procurement process shall make the Bid non-responsive and if detected after the award the bidder could be subjected to legal prosecution.

4.1

Qualification Information

The following information shall be provided in Section – 9 – Schedules;

- CIDA registration
Registration number
- Grade
- Specialty
- Expiry date
- If not VAT registered, self declaration on VAT registration
- VAT registration number
- If a Joint Venture, the agreement

- Construction Programme with critical path and cash flow forecast.
- Legal status of the bidder (sole proprietor, Partnership, Company etc.)
- Authentication signatory (written Power of Attorney)
- Total monetary value of construction work performed for each of the last five years.
- Experience in works of a similar nature and size for last ten years.
- Availability of Construction equipment.
- Availability of Staff
- Work plan and methods
- Information on current work in hand

4.2(a) The bidders shall have a valid registration in Grade **C1 or above in Bridges and Highways** Specialty, on the date of closing of bids.

4.2(b) Average annual volume of construction work performed during last five years shall be at least **Rs. 608.0 million.**

Annual Average Construction Turnover (AACT) is calculated as follows,

$$AACT = \frac{\sum ACT_n}{5} \quad \text{where, } n = 1st \dots\dots\dots 5th \text{ year (last five years)}$$

ACT_n - Annual Construction Turnover of nth year (from the audited financial report)

4.2(c) The Bidder should have experience as prime contractor in the construction of at least one work of a nature and complexity similar to the Works, the value of which should be at least **Rs. 426.0 million** during the last ten years and at least one bridge of pre-tensioning deck along with beam launching and road construction experience. (To comply with this requirement, works cited should be at least 70 percent complete).

4.2(d) Essential equipment

Proposals for the timely acquisition (own, lease, hire, etc.) of the following essential equipment shall be ,

| <u>Machinery</u> | <u>Capacity</u> |
|----------------------------|--------------------|
| 1. Dump Truck | 4-10 Ton |
| 2. Excavator | 120 Hp |
| 3. wheel Loader | 1.5 Cum or above |
| 4. Generator Set | 10-100 KVA |
| 5 Mobile Crane | 20-25 MT |
| 6. Crawler Cranes | 100-150 MT |
| 7. Backhoe Loader | 50 – 100 Hp/1.0Cum |
| 8 Breakers | |
| 9. Asphalt Pavers | 10MT |
| 10. Pneumatic tired roller | 8 – 10 Ton |
| 12. Concrete mixture | 400 ltr |
| 13. Air compressors | 250 CFM |
| 14. Cargo truck with Crane | 10 Ton |
| 15. Beam Launchers | |
| 16. Vibrating roller | 10Ton |
| 17. Motor Grader | 120-140 HP |

4.2 (e)

The Project Manager shall have following qualification & experience,

Four Years B.Sc Engineering (Civil) Degree from a University in Sri Lanka or equivalent Civil Engineering Qualification recognized by the UGC and Institution of Engineers, Sri Lanka (IESL). OR Passed Part I, II and III examinations of the Institution of Engineers, Sri Lanka (IESL) OR B.Tech Degree in Civil Engineering from the Open University of Sri Lanka. The person shall have Corporate membership (Chartered Engineer) of the Institution of Engineers, Sri Lanka (IESL) or any other recognized institution by the Institution of Engineers, Sri Lanka (IESL) with 5 years experience in post charter in Bridge and Highway Construction and shall have ability to lead and direct multi-disciplinary teams and experience in proper deployment and efficient management of human and other resources.

4.2(f) Liquid assets and / or credit facilities required

The minimum amount of liquid assets available shall be Rs **102.0 million**.

The minimum amount of liquid assets available is calculated as follows.

$$X = (A - L) - 0.1 W + C$$

Where,

X = Minimum amount of liquid assets available,

A = Current assets as given in the latest audited financial statements,

L = Current liabilities as given in the latest audited financial statements,

W = Outstanding contractual commitments as supported by an affidavit as per Form No. 07,

C = Project specific revolving line of credit given by a bank as per given Form

Note : Available Working Capital of bidder should be equal or greater than 50% of minimum amount of the Liquid Asset (i.e. Rs. 51.0 million). Line of Credit shall be provided only to satisfy the balance amount of the required amount of the Liquid Asset.

Non - Performing Contracts

4.2 (h)

| Criteria | Compliance Requirements | | | Documents | |
|---|---|-----------------------|---|----------------|------------------------------|
| Requirement | Single Entity | Joint Venture | | | Submission Requirements |
| | | All Partners Combined | Each Partner | One Partner | |
| Non-performance* in a contract has not been occurred as a result of Contractor's default | must meet requirement by itself or as partner of JV | not applicable | must meet requirement by itself or as partner of JV | not applicable | Schedule No. 09 (a) & 09 (b) |
| <p>* All RDA projects (foreign & local funded) shall be considered for assessment of Non-performing Contracts (single entity contractor / any JV / any each partner of the JV, nominated sub contractor) based on the following criteria.</p> <p>1. Any bidder who submits bid to this contract shall be disqualified for the award of the contract, if Notice to Correct (NC) has been issued as per Clause 15.1 of SBD 2 Condition of Contracts on the poor performance of the Contractor or similar notice as per the relevant Conditions of Contract (COC) and is imposed before 28 days prior to date of bid opening, unless the Engineer certifies that Contractor has corrected the contents of the Notice to Correct. This certificate shall be accompanied with the bid; or</p> <p>If any Contract has been terminated due to the Contractor's default within last five years prior to 05/04/2023, he shall be disqualified for the award of contract.</p> | | | | | |

Add a new sub clause 4.2 (i)

Pending Litigation and Arbitration

4.2 (i)

| Criteria | Compliance Requirements | | | Documents | |
|---|---|-----------------------|---|----------------|-------------------------|
| Requirement | Single Entity | Joint Venture | | | Submission Requirements |
| | | All Partners Combined | Each Partner | One Partner | |
| All pending litigation and arbitration, if any, shall be treated as resolved against the Bidder and so shall in total not represent more than fifty (50%) percent of the Bidder's net worth calculated as the difference between total assets and total liabilities. | must meet requirement by itself or as partner to past or existing Joint Venture | not applicable | must meet requirement by itself or as partner to past or existing Joint Venture | not applicable | Schedule No. 10 |

- 10.1 Clarification of Bidding Documents**
Employer's address for clarification of bidding documents is.
Director (Construction),
RDA, 3rd Floor, "Maganeguma Mahamedura", Denzil Kobbekaduwa Mawatha,
Battaramulla
Phone: 011 – 2864388
Fax No. 011 – 2861821.
- 14.3 Add following to this clause**
All taxes except VAT shall be incorporated to the rates.
- 14.4 Adjustment for change in cost**
The Contract is subjected to price adjustments.
- 16.1 Period of Bid validity:**
The Bid shall be valid up to **27/09/2023**.
- 17.1 Amount of Bid security:**
The amount of Bid Security is Sri Lanka Rs. **7.0 Mn**.
- 17.2 Validity of Bid Security**
The Bid Security shall be valid up to **25/10/2023**.
The form of Bid Security shall be strictly in the format given in the Bidding Document.
- Any unconditional guarantee issued by a bank registered bank in the Central Bank of Sri Lanka or CGF or Insurance company except ABC Insurance Company (Pvt) Ltd is acceptable.
- 18. Alternative Proposals by Bidders**
Delete entire Clause and substitute with the following:-
"Bidders are not allowed to submit alternate proposals"
- 19.1 Pre – Bid meeting**
Pre-bid meeting will be held on **19/04/2023** at Provincial Director (Uva), Road Development Authority, No. 40, Dharmapala Mawatha, Bandarawela at 10:00 hrs. The site visit shall be arranged thereafter with RDA representative, if necessary.
- 20.4 Add new Sub Clause 20.4**
All pages of the Bidding documents shall be signed by the bidder and his seal affixed.
- 21.2 Submission of Bid**
- 21.2(a)** Employer's address for the purpose of bid submission is ;
Chairman,
Ministry Procurement Committee,
Ministry of Transport and Highways,
Procurement Division
7th floor, "Maganeguma Mahamedura"
216, Denzil Kobbekaduwa Mawatha,
Battaramulla
- 21.2(b) Name and Identification number of Contract**
The name of the Contract '**CONSTRUCTION OF RAJAMAWATHA EXTENTION ROAD FROM KETAWALA TO MASPANNA (FROM CH 7+560km TO CH 9+300 km), INCLUDING TWO BRIDGES AT CH 7+960 km AND CH 8+380 km** ' Contract Number is **RDA/DC/UVA/FD/GOSL/2023/02**

22.1 Deadline for submission of Bids

The deadline for submission of bids is **14:00 hrs on 03/05/2023**.

23.1 Any bid received after the deadline for submission of bid will be returned unopened to the bidder.

25.1 Bid Opening

The Bids shall be opened immediately after the deadline for submission of Bids, mentioned in sub-clause 21.2 & 22.1

30.6 Add new sub clause 30.6

To ensure that the bids made not unrealistic, following criteria will be adopted,

a) If the bid value is 11% to 19% less than the engineer's estimate, the performance bond will be increased by 5%.

b) If the bid value is 20% to 29% less than the engineer's estimate, the performance bond will be increased by 10%.

c) If the bid value is 30% or higher percentage less than the engineer's estimate, the bid will be rejected.

Add new sub clause 30.7

30.7

Considering the role of the State Owned Enterprises (SOE) in these industries, when such SOE submits a bid for a contract then such SOE will be given 5% preference over all other contractors. This will be considered only when the Financial Evaluation and not in Technical Evaluation.

32.3 Add new sub Clause 32.3

After evaluation of Bids in accordance with the procedures described under Clauses 28, 29, 30 and 31, the Employer will inform to all the bidders in writing the selection of the successful bidder and the intention of contract award to such bidder. The unsuccessful bidders if they so wish, within one week of such notice may make representation to the Procurement Appeal Board at the address given below. Such representation shall be self-contained to enable the Appeal Board to arrive at a conclusion and a cash deposit to an amount given below shall be made. The Appeal Board may request the bidder who had made representation to submit further evidence during investigations. The cash deposit will be forfeited unless the Employer has changed the original contract award decision in favour of the bidder who has made such representation.

Address: The Secretary
Ministry of Transport & Highways,
8th floor, "Maganeguma Mahamedura",
216, Denzil Kobekaduwa Mawatha,
Battaramulla.

Cash Deposit: Rupees 25,000/=

34.0 Authority for Signing the Agreement

Add RDA Circular RDA/DPR-AD-01/06 dated 15th June 2020 regarding empowered officers for signing the contract agreement

35.1 Amount of Performance Security

The format of the security shall be strictly in accordance with the format given in Section 5.

The amount of Performance Security is 5% of the Initial Contract Price, subject to sub clause 3.1 (v) of Public Finance Circular No. 03/2020 (i) dated 11.01.2021 issued by Ministry of Finance.

The Performance Security shall be valid until 28 Days beyond the time for completion.

Any unconditional bank guarantee issued by registered bank in the Central bank of Sri Lanka or CGF is acceptable.

REFERENCE ONLY

SECTION - 4

CONTRACT DATA

This Section shall be read in conjunction with Section 3- 'Conditions of Contract', and is intended to provide specific information in relation to corresponding clauses in Section 3. Wherever there is a discrepancy, the provisions in Section 4 – Contract Data shall supersede those provided in the Section 3 – Conditions of Contract.

The Clause numbers given in this Section correspond to the Clauses with the same numbers in the Section 3 – 'Conditions of Contract'.

Whenever a Clause number appears in this Section, it means the information in the corresponding Clause in Section 3 is supplemented and/or modified according to the information in the Clause in Section 4.

If a Clause number does not appear in this Section, it means the Clause with the corresponding number in Section 3, remains unchanged.

CONTRACT DATA

| COC Clause Number/s | |
|---------------------|---|
| 1.1.2.2 | Employer's Name : Director General , Road Development Authority Employer's Address : 1 st Floor, "Maganeguna Mahamedura", 216, Denzil Kobbekaduwa Mawatha, Battaramulla |
| 1.1.2.4 | The Engineer : The Engineer will be notified later. |
| 1.1.3.3 | Time for Completion is 546 Days |
| 1.1.3.7 | Add following, The Defects Notification Period is one Year. |
| 1.3 (b) | Employer's Address Road Development Authority, 1st Floor,"Maganeguma Mahamedura", 216, Denzil Kobbekaduwa Mawatha, Battaramulla. |
| 2.1 | Engineer's Address :will be notified later |
| 3.1 | The Start Date shall be 14 Days from the receipt of the Letter of Acceptance The Engineer shall obtain the specific approval of the Employer before taking action under the following Sub – Clauses of these Conditions. |
| | <ul style="list-style-type: none"> I. Clause 13. 3 - Variation Procedure II. Clause 4.4 - Subcontractors III. Clause 5.0 - Nominated Subcontractors IV. Clause 8.4 - Extension of Time for Completion V. Clause 8.8 - Suspension of Work VI. Clause 8.11 – Prolonged Suspension VII. Clause 10 - Employer's Taking Over VIII. Clause 11.3 – Extension of Defects Notification Period IX. Clause 11.8 - Performance Certificate X. Clause 13.6 - Adjustments in Changes in Legislation XI. Clause 16.4 - Payment on Termination |
| | Notwithstanding any obligations set out elsewhere in this Contract to obtain approval from the Employer, if, in the opinion of the Engineer, an emergency occurs affecting the safety of life or of the Works or of adjoining property, he may, without relieving the Contractor of any of his duties or responsibilities under the Contract, instruct the Contractor to execute all such work or to do such things as may, in the opinion of the Engineer, be necessary to abate or reduce the risk. The Contractor shall forthwith comply, despite the absence of approval of the Employer, with any such instruction of the Engineer. The Engineer shall determine an addition to the Initial Contract Price, in respect of such instruction, in accordance with Clause 13 and shall notify the Contractor accordingly, with a copy to the Employer. |

4.2

Performance Security

Amount of Performance Security is 5% of the Initial Contract Price, subject to sub clause 3.1 (v) of Public Finance Circular No. 03/2020 (i) dated 11.01.2021 issued by Ministry of Finance.

The acceptable format of the Performance Security is given in this Bidding Document.

Any unconditional bank guarantee issued by registered bank in the Central bank of Sri Lanka or CGF is acceptable.

Change the Heading from ‘Quality Assurance’ to ‘Quality Control’

Replace the text of the Sub-Clause 4.17 with the following text:

4.17

4.17(a) Identifying Defects

The Engineer shall check the Contractor’s work and notify the Contractor of any Defects that are found and shall specify a time within which the defects are to be rectified. Such checking shall not affect the Contractor’s responsibilities. The Engineer may instruct the Contractor to search for a Defect and to uncover and test any work that the Engineer considers may have a Defect.

4.17(b) Tests

If the Engineer instructs the Contractor to carry out a test which is not specified in the Specification or Bills of Quantities in sufficient details to enable the Contractor to have priced or allowed for the same in the Bid and the test shows that the workmanship or Material is defective then the Contractor shall pay for the tests and samples.

If the test shows that the workmanship and Materials is in accordance with the Contract and if the Contractor suffers delay and /or incurs Cost from complying with these instructions or as a result of delay for which the Employer is responsible, the Contractor shall give notice to the Engineer and shall be entitled subject to Sub-Clause 19 (Contractor’s Claims) to:

- (a) an extension of time for any such delay, if completion is or will be delayed, under Sub-Clause 8.4 (Extension of Time for Completion); and
- (b) payment of any such Cost plus reasonable profit, which shall be included in the Contract Price.

After receiving this notice, the Engineer shall proceed in accordance with Sub-Clause 3.4 (Determinations) to agree or determine these matters.

The Contractor shall promptly forward to the Engineer duly certified reports of the tests. When the specified tests have been passed, the Engineer shall endorse the Contractor’s test certificate, or issue a certificate to him, to that effect. If the Engineer has not attended the tests, he shall be deemed to have accepted the readings as accurate.

4.17(c) Correction of Defects

4.17(c-1)

The Engineer shall give notice to the Contractor of any Defects before the end of the Defects Notification Period, which begins at completion, and is defined in the Contract Data.

4.17(c-2)

Every time notice of a Defect is given, the Contractor shall correct the notified Defect within the length of time specified by the Engineer’s notice.

| | <p>4.17(c-3)</p> <p>On completion of the Defects Notification Period and correction of Defects in accordance with Sub-Clause 4.17(c-2) or 4.17(d), and on certification of the final payment, the Engineer shall issue the Final Payment Certificate to the Contractor</p> | | | | | | | | |
|---|--|-----------------|-------------------|-----------|--------------------------------|---|---------------------------------------|---------------|---------------------------------------|
| <p>8.7</p> <p>12.2(b)</p> | <p>4.17(d) <u>Uncorrected Defects</u></p> <p>If the Contractor has not corrected a Defect within the time specified in the Engineer’s notice, the Engineer will assess the cost of having the Defect corrected, and the Contractor will pay this amount.</p> <p>Liquidated Damages</p> <p>The Liquidated Damages for the whole of the works shall be Rs. 304,000.00 per Day.</p> <p>The maximum amount of Liquidated Damages for the whole of the works shall be 10% (ten percent) of the Initial Contract Price.</p> <p>The method of Measurement shall be as per the Contract</p> | | | | | | | | |
| <p>13.3</p> | <p><u>Variation Procedure</u></p> <p>Replaced with</p> <p><u>Variation Exceeding 25 percent</u></p> <p>If on the issue of the Taking Over Certificate for the whole of the Works it is found that there is a reduction or increase of more than 25% in the Quantity of any unit priced items in the original Bill of Quantities for which the total cost based on the rate for that item in the Bill of Quantities is more than 5% of the “ effective Contract Price”(which for the purpose of this sub- clause shall be the contract price, excluding the provisional sums and allowances for day works, if any, and the adjustment of price under sub clauses 13.6 and 13.7 at statement at completion) then,</p> <p>a. The excess quantity of particular item shall be paid as describes in following table</p> <table border="1" data-bbox="416 1473 1137 1686"> <thead> <tr> <th>Excess quantity</th> <th>Method of payment</th> </tr> </thead> <tbody> <tr> <td>up to 25%</td> <td>Original Bill of Quantity rate</td> </tr> <tr> <td>Between more than 25% and less than 50%</td> <td>90% of Original Bill of Quantity rate</td> </tr> <tr> <td>more than 50%</td> <td>83% of Original Bill of Quantity rate</td> </tr> </tbody> </table> <p>b. Quantity reduction of particular item shall be paid as described below</p> <p>If the final quantity of work done in particular item is 75% of the original Bill of Quantities or less shall be paid at the rate shown in the Bill of Quantities. In addition a payment of 17% of the difference between 75% of the estimated amount for that item and the final amount for that item shall be made to the Contractor.</p> | Excess quantity | Method of payment | up to 25% | Original Bill of Quantity rate | Between more than 25% and less than 50% | 90% of Original Bill of Quantity rate | more than 50% | 83% of Original Bill of Quantity rate |
| Excess quantity | Method of payment | | | | | | | | |
| up to 25% | Original Bill of Quantity rate | | | | | | | | |
| Between more than 25% and less than 50% | 90% of Original Bill of Quantity rate | | | | | | | | |
| more than 50% | 83% of Original Bill of Quantity rate | | | | | | | | |

| 13.4(b) | <p>Percentage for adjustment of Provisional Sums</p> <ol style="list-style-type: none"> 1. For the works executed by Utility Authorities - 10% 2. For the works directly executed by the Contractor – 20% 3. For supplying and services-10% | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
|---------|--|---|-------|------------|------------|----|--------|-------|----|------------------|------|----|---------------------|------|----|-----------------|------|----|------|------|----|-------|------|-----|---------------|------|----|------|------|----|----------------|------|-----|------------------|------|-----|-------|------|------|---------|------|----|-----------------|------|--|--|--------------|
| 13.7 | <p>Price Adjustment The contract is subjected to price adjustment</p> <table border="1" data-bbox="320 524 1075 1323"> <thead> <tr> <th>Input</th> <th>Input Name</th> <th>Percentage</th> </tr> </thead> <tbody> <tr><td>M3</td><td>Cement</td><td>15.32</td></tr> <tr><td>L3</td><td>Unskilled Labour</td><td>9.85</td></tr> <tr><td>L2</td><td>Semi-skilled Labour</td><td>9.04</td></tr> <tr><td>P2</td><td>Heavy Equipment</td><td>8.53</td></tr> <tr><td>M8</td><td>Sand</td><td>7.57</td></tr> <tr><td>M7</td><td>Metal</td><td>7.34</td></tr> <tr><td>M13</td><td>Reinforcement</td><td>6.49</td></tr> <tr><td>P3</td><td>Fuel</td><td>6.40</td></tr> <tr><td>L1</td><td>Skilled Labour</td><td>5.96</td></tr> <tr><td>M21</td><td>Form Work Timber</td><td>5.58</td></tr> <tr><td>M45</td><td>Earth</td><td>4.23</td></tr> <tr><td>M30C</td><td>Bitumen</td><td>2.38</td></tr> <tr><td>P1</td><td>Small Equipment</td><td>1.31</td></tr> <tr><td></td><td></td><td>90.00</td></tr> </tbody> </table> <p>Non-adjustable items shall be Bill no. 01 (Preliminaries & Generals), Bill no. 05 (Day Works), and all PS & LS items.</p> | | Input | Input Name | Percentage | M3 | Cement | 15.32 | L3 | Unskilled Labour | 9.85 | L2 | Semi-skilled Labour | 9.04 | P2 | Heavy Equipment | 8.53 | M8 | Sand | 7.57 | M7 | Metal | 7.34 | M13 | Reinforcement | 6.49 | P3 | Fuel | 6.40 | L1 | Skilled Labour | 5.96 | M21 | Form Work Timber | 5.58 | M45 | Earth | 4.23 | M30C | Bitumen | 2.38 | P1 | Small Equipment | 1.31 | | | 90.00 |
| Input | Input Name | Percentage | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| M3 | Cement | 15.32 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| L3 | Unskilled Labour | 9.85 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| L2 | Semi-skilled Labour | 9.04 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| P2 | Heavy Equipment | 8.53 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| M8 | Sand | 7.57 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| M7 | Metal | 7.34 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| M13 | Reinforcement | 6.49 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| P3 | Fuel | 6.40 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| L1 | Skilled Labour | 5.96 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| M21 | Form Work Timber | 5.58 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| M45 | Earth | 4.23 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| M30C | Bitumen | 2.38 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| P1 | Small Equipment | 1.31 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | 90.00 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 14.2 | <p>Advance Payment A total Advance Payment of 20% of the Initial Contract Price net of Contingencies and Provisional Sums would be made in two equal instalments on submission of an advance payment guarantee. The second instalment would be paid only after establishing that the first instalment of the advance payment has been used exclusively for mobilization of this project and submission and approval of detailed construction programme with network analysis and resource scheduling. The advance payment guarantee shall only be from a Bank registered in the Central Bank of Sri Lanka or CGF. First part of the advance payment would only be paid after signing of a formal contract agreement.</p> | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 14.3(c) | Percentage of retention Limit of Retention Money | 10% 5% of the Initial Contract Price | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 14.5 | Minimum amount of Interim Payment Certificates | Rs 17.0 Mn. | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |

| | | |
|-----------------------|--|--|
| <p>15.2(h)</p> | <p>Add following Termination by Employer If the delay is more than the period, for which the Maximum Delay Damage is allowed to be applied, the Employer may consider this situation as Contractor’s fundamental breach of the Contract, and the Employer may consider Termination of the Contract. The Delay is determined by updating the approved program with actual progress, after saving the approved program as a Baseline.</p> | |
| <p>18.2</p> | <p>Third Party Insurance</p> | <p>This amount of third party insurance per occurrence is Rupees 5,000,000. 00</p> |

REFERENCE ONLY

SECTION - 6
SPECIFICATIONS

REFERENCE ONLY

SPECIFICATION

Standard Specifications

The Standard Specifications comprise 'Standard Specifications for Construction and Maintenance of Roads and Bridges' issued under the authority of the Director General of the Road Development Authority and published by the Institute of Construction Training and Development.

The ICTAD Publication No. of this publication is SCA/5 Second Edition –June 2009

Bidders who are not in possession of this publication can purchase it from the CIDA.

REFERENCE ONLY

PARTICULAR SPECIFICATIONS

PREAMBLE

=====

These Particular Specifications should be read in conjunction with the Standard Specifications for Construction and Maintenance of Roads and Bridges, ICTAD Publication No SCA/5Second Edition –June 2009, which are applicable in all cases not covered herein.

The Particular Specifications for some sections of the works are comprehensive and cover the full extent of the works in these sections. In other sections they apply in conjunction with the Standard Specifications. Finally in some sections not covered in the Particular Specifications, the Standard Specifications shall apply in full.

Where there is an ambiguity or discrepancy between the Particular Specifications and the Standard Specifications, the Particular Specifications shall prevail.

REFERENCE ONLY

PRELIMINARIES & GENERAL

P(001) Mobilization & Demobilization

The Contractor shall submit to the Engineer within 14 days from the date of Letter of Acceptance his mobilization and demobilization plan for equipment, plant and machinery required for the Project. Plan shall include the location of plant, machinery and equipment and mode of transport. Engineer shall approve the mobilization and demobilization plan and payment shall be based on schedule of mobilization.

Payment

Payment shall be made according to the schedule submitted by bidder and within the lump sum amount agreed in the Bill of Quantities.

| Item No | Description | Pay Unit |
|----------------|---|-----------------|
| P (001) | Allow for mobilization & demobilization | L.S. |

P(002) Provide Office for the Engineer

The Contractor shall provide furnished buildings area of 75 sqm for the use of the Engineer according to the Contract. The buildings shall be to the satisfaction of the Engineer.

The Contractor shall submit for the Engineer's approval for general layout plan of the facilities, showing their position, the access and internal roads, fences and gates and proposed waste water/sewerage disposal system before any of this work starts.

The Contractor shall be responsible for earthworks and site grading required for the site facilities and parking areas including boundary fence, gate and watchman's hut. In addition, any access to the site facilities by means of roads from a public road shall be provided and maintained by the Contractor.

The site shall be graded and properly drained so that there are no depressions where water will collect.

All wastewater shall be disposed underground and as approved by the Engineer. The Contractor shall perform percolation tests at the location of leach field, and the size of the leach field or pit will be subject to the results of these tests and the approval of the Engineer.

The septic tanks of size approved by the Engineer shall be of reinforced concrete or glass fiber equipped with proper inlet and outlet baffles and sealed access batch. The size shall be sufficient to operate at least three years without solids overflowing into the leach field. The leach field or pits shall penetrate through the catch layer if there is one. The space below the distribution pipes shall be backfilled with a pervious material and compacted prior to installing the distribution pipes.

The design of the leach field or pits shall take into consideration only the area of the side walls of the trench or pit below the level of the inlet pipes. The area of the bottom of the trench or pit may not be used for percolation calculations as it will be continuously saturated. The Contractor shall submit full details of the proposed system for the approval of the Engineer.

No permanent work shall be allowed to start on Site until the offices for the Engineer are completed and equipped as specified and fully operational.

Upon completion of the Contract, Engineer's offices shall be become property of the Contractor. The Contractor is requested to submit with his bid, Literature & Specifications of the facilities in sufficient details to enable their quality to be assessed.

Canopies shall be provided using an approved type of Construction to shade the roofs and external walls and windows of the facilities during the day.

Covered carports shall be provided at the office areas to accommodate 2 cars/cabs in each area.

Payment

Payment shall be made at the unit price as contained in the BOQ

| Item No. | Description | Pay Unit |
|----------|---|----------|
| P(002) | Provide office for the Engineer during the Construction period. | month |

P(003) Maintenance of Office for the Engineer

Description

The Contractor shall maintain in good decorative and working order all the buildings and the contents thereof supplied under the Contract. The Contractor shall be responsible for supplying all power, water and telephone services and all the facilities and shall meet all costs for these services and settlement of all bills for these services.

The Contractor shall maintain all facilities for the duration of the Contract, such maintenance shall include but not be limited to:-

keeping buildings in good repair and decorative order, and free from pests, insects etc;
cleaning offices and laboratory daily;
maintaining the grounds around buildings;
supplying kitchen-ware and crockery and cleaning materials;
supplying toilet and cleaning equipment and materials;
providing power, water, telephone services, fax and e-mail facilities;
servicing and repairing all fittings and equipment installed, eg: air-conditioners, fans, etc;

Measurement and Payment

a. Measurement

Maintenance of each facility shall be measured as the number of months during which the maintenance for each facility is satisfactorily provided. Maintenance shall not be measured during any period occurring between the expiration of the contract period and the date the works are certified as complete.

Measurement will be made for maintenance performed after the completion of the works, during the time the facilities are required by the Engineer's staff for post-construction contract completion activities.

b. Payment

Payment for maintenance for each facility shall include all labour, materials and equipment required for satisfactory maintenance of the facilities and shall include all other costs including but not limited to supply of electricity, water and telephone facilities, cleaning, guarding, disposal of rubbish, repairing equipment and all other work required to ensure the facilities and equipment provided are in good operational order.

| Pay Item Description | Pay Unit |
|--|----------|
| P (003) Maintain Office for the Engineer | Month |

P(004) Provide Furniture & Equipment for the Engineer’s Office

The Contractor shall provide & maintain the office equipment and furniture for use of Engineer. At the completion of Contract all furniture and office equipment shall become the property of the RDA

Payment

Payment shall be made from the pay item in the Bill of Quantities

| Item No | Description | Pay Unit |
|---------|--|----------|
| P (004) | Provide office furniture & Equipment for the Engineer’s office | PS |

P (005) Provide Stationary for the Engineer’s Office

The Contractor shall provide stationary for the engineer as required and duly requisition by the engineer. Stationary includes office consumable items such as paper, paper printing material and general office requisites. Payment for the stationary shall be the actual net price of stationary provided and equipment provided. Payment for invoiced cost with 10% administrative charge shall be the full payment for stationary provided and shall be made from the provisional sum item in the bill of quantities.

| Item No. | Description | Pay Unit |
|----------|--|----------|
| P (005) | Provide stationary for the Engineer’s Office | PS |

REFERENCE ONLY

1.01 LAND AVAILABLE

The land available to the Contractor free of charge shall be the land occupied by the permanent works or the existing road right of way, whichever is greater in width.

1.02 DAMAGE TO LAND AND CROPS

Where land is made available to the Contractor free of charge, the Contractor shall under no circumstances interfere with this land whether for Permanent or Temporary works until the evaluation of all compensation has taken place and permission to proceed has been received from the Engineer. Care shall be taken during the Works to ensure that no unnecessary damage is caused to the land or crops and that all reasonable precautions are taken to prevent soil erosion and mosquito breeding. On completion of the work, the land shall be left in a tidy condition as directed by the Engineer.

1.03 GRAVES, TOMBS, RELIGIOUS OR TRADITIONAL MONUMENTS

Areas which contain graves, tombs and religious or traditional monuments within the Site shall be cleared by the Contractor in accordance with the written instructions of the Engineer.

1.04 CONTRACTOR'S HOUSING, STORES AND WORKSHOP AREAS

The location and layout of housing, stores and workshop areas together with their use and detailed dimensions shall be approved by the Engineer. The Contractor shall not erect any structures on the Site without the approval of the Engineer.

On the commencement of the Contract the Contractor shall fence off all areas designated for housing, plant-yard, workshops, offices and the like. By the end of the Period of Defects Notification Period or at such earlier time as the Engineer may instruct or approve, the Contractor shall clear all structures, plant and rubble from these areas and leave them in a condition acceptable to the Engineer.

1.05 FIRST AID FACILITIES

The first aid, welfare and safety standards to be provided and observed shall be at least equal to those laid down by the Ministry of Health/Labour for Industrial sites of similar size and remoteness and approved by the Engineer.

The Contractor shall, within 24 hours of the occurrence of any accident at or about the Site or in connection with the execution of the Works, report such accident to the Engineer and to the Competent Authority where required by Law. At least one person permanently on the Site shall have been trained in first aid and the person so designated shall have been made known to the Engineer in writing and to all employees by the posting of his name and designation in a prominent position on the Site.

1.06 SECURITY SERVICES FOR ENGINEER

The Contractor shall be responsible for all matters of security concerning the vehicles and housing, offices for the Engineer. The costs in connection with this clause shall be deemed to be included in the Contractor's tendered rates.

1.07 WATER SUPPLY

The Contractor shall make his own arrangements and at his own costs for the provision from approved sources of adequate clear water for use in construction of the Works or otherwise. Quantities of water withdrawn from the approved sources shall be such that the requirements of the local population in respect of water for irrigation, drinking purposes, etc., are not interfered with. The Contractor shall have obtained permission from the appropriate Authorities in each case for the abstraction of water from any natural source, before the Engineer approves the use of such source.

1.08 SERVICES

The Contractor shall make his own arrangements for the supply of electricity for power and light and of any other services required in order to carry out the Works and he shall make his own arrangements, subject to the approval of the Engineer, for the disposal of sewage and all waste materials during the execution of the Works. All such services shall be at the Contractor's own expense.

1.09 PROTECTION OF MAINS AND SERVICES

The Contractor shall protect and support at his own costs during the construction of the Works, all pipes, mains, cables, overhead lines and other apparatus, which might be endangered by his operations.

In the event of any pipes, mains or cables being exposed at any time, the Contractor shall immediately notify the Authority or proprietor concerned and shall not cover the exposed pipe, main or cable until it has been examined and approved by the appropriate Authority or proprietor.

Before commencing any section of the Works the Contractor shall at his own expense obtain full information with regard to the position and depth of all pipes, mains and cables.

The Contractor is responsible for making arrangements with the Public Authorities and other duly constituted bodies for the phasing into his programme of works, of all the work which needs to be done by them or their contractors concurrently with the Works. If in the execution of the Works, any damage to any service or apparatus or any interruption of or delay to the provision of any service is caused, the Contractor shall bear and pay the cost reasonably incurred by the Authority or body concerned in making good such damage and shall make full compensation to the Authority or other body for any loss sustained by reason of such interruption or delay.

In the case of damage caused to water mains, pipes or fittings less than 2 inches in diameter the Contractor shall repair the damage himself at his own expense without delay. The Contractor shall be responsible for any damage caused to the permanent works or to adjacent property by water flooding due to damage caused by him to water mains, pipes or fittings.

1.10 QUARRIES AND BORROW PITS

The Contractor shall be responsible for opening up any quarry or borrow pit and shall organize his methods of operation so that only material of a type and quality approved by the Engineer shall be selected for use in the Works. The Contractor shall provide, erect, operate and maintain all plant necessary for their proper operation, together with any access roads, temporary bridges or the like necessary for the supply to the Works of the aforementioned and pay all charges incurred, including the rights for entering the land and extracting the material, or for any other compensation.

No claim shall be allowed for delays or for any other reason in this respect.

1.11 OTHER WORKS

During the course of the Contract the Employer may cause other works such as the installation or removal or resetting of services to be carried out, on through or adjacent to the Site.

The Contractor shall at all times comply with the requirements of the relevant Clauses of the Conditions of Contract in respect of these and any other Works not included in the Contract and shall allow reasonable access as approved by the Engineer on and through the Site of the Works to any other contractor or workmen who may be working on or near the Site for this reason at no extra cost.

1.12 POSSESSION OF THE SITE

Possession of the site will be in accordance with the General Conditions of Contract. Possession will be granted in accordance with the Contractor's Programme referred to in the Conditions of Contract and the Specifications and approved by the Engineer.

1.13 BOREHOLE INFORMATION

Information regarding the position and depth of boreholes and the results obtained are shown on the drawings and Contractor shall be deemed to have considered this information and checked its accuracy during the Tender Period, and to have satisfied himself of the characteristics of the materials and the suitability of the plant and the methods of working on which he has based his rates.

1.14 WEATHER CONDITIONS

The Contractor shall not be entitled to extra payment by reason of the occurrence or effect of high winds, excessive rainfall, temperature, humidity or any other meteorological phenomena.

1.15 PROGRAMME

In addition to the requirements of the Conditions of Contract the Contractor shall furnish to the Engineer within one calendar month from the commencement date a detailed programme of the order in which he proposes to carry out the Works. The programme shall include time and progress charts so that actual progress on each operation can be shown against anticipated progress. Due allowance should be made for the seasonal rains and also in accordance with the relevant clauses in this specifications.

The Contractor shall keep the progress of the Works under continuous review. When necessary the programme shall be updated at regular intervals as required by the Engineer.

1.16 CONTRACT DOCUMENTS AND DRAWINGS

The Contractor shall be issued Contract Documents and Drawings. When necessary the Contractor shall also be supplied with two copies of any further drawings, which may be issued in accordance with the Contract.

1.17 PRESERVATION OF SURVEY MARKERS

The Contractor shall locate and where possible preserve or else relocate all survey markers established for the execution of the Works. Where such survey markers will be disturbed, the Contractor shall accurately reference these to permanent concrete markers before such work is commenced.

Where it is likely that any survey marker which is the property of the Survey Department will be disturbed, the Contractor shall inform the appropriate Survey Authorities at least 14 days before the marker is endangered and ensure that the Survey Authorities take appropriate action.

1.18 DIMENSIONS AND LEVELS

The Contractor on the Site shall verify all Dimensions and levels shown on the Drawings or mentioned in documents forming part of or issued under the Contract and he shall immediately inform the Engineer of any apparent errors or discrepancies in such dimensions or levels.

1.19 NIGHT WORKING

The Contractor may be permitted to carry out work during the night and shall submit full details of the methods of working and lighting, control of traffic and any other information, which the Engineer may request. No night working shall be carried out without the Engineer's approval, and the Engineer has the right to withhold or withdraw approval if, in his opinion, such work presents undue hazard or disturbance to the public, or is in any other way unsatisfactory.

The Contractor's intentions on night working shall be made known to the Employer on the programme of Works supplied with his tender.

1.20 AMENITY AND ACCESS

The Contractor shall ensure that, in carrying out the Works, he causes no damage by plant, workmen, flooding, subsidence or otherwise to any property. He shall take all precautions to the satisfaction of the Engineer to ensure that such hazards are avoided and public amenity maintained, and he shall be responsible for any damage that may occur.

The Contractor shall be responsible for providing and maintaining access to and along the Site for his own purposes, including any temporary river or swamp crossings he may require.

1.21 WORKS DURING DEFECTS NOTIFICATION PERIOD

After the Commencement of the Defects Notification Period, which shall normally, the Contractor shall do nothing which might endanger the safety of the public and he shall complete any outstanding works and undertake the correction of all defects as instructed by the Engineer or any other duly authorized person or

Authority. Throughout the Defects Notification Period the Contractor shall notify the Engineer of the work or operations he intends to carry out and he shall obey any instructions which the Engineer may give as to the times and manner of working so that any inconvenience to the public is kept to a minimum.

1.22 CLEARING AND TRIMMING OF SITE ON COMPLETION

On completion of the Works the Contractor shall leave the Site in a tidy condition to the satisfaction of the Engineer. Particular attention shall be paid to the final levelling, grading, making good of erosion gulleys and routings, landscaping and drainage of the Site, the borrow areas and any other places adjacent to the Site interfered with by the Contractor during the Construction or the Defects Notification Period.

1.23 SPILLAGES

The Contractor shall be responsible throughout the Contract and Defects Notification Period for any spillage of fuels, bitumen, hydraulics, oils, and other lubricants or materials caused by his activities on the Works and any such spillage shall be removed and any damage repaired to the satisfaction of the Engineer at the Contractor's expense.

1.24 APPROVAL OF SUPPLIERS OF MATERIALS AND GOODS

Before entering into any agreement for the supply of any materials or goods, the Contractor shall obtain the Engineer's approval in writing of the supplier from whom he proposes to obtain such materials or goods. Should the Engineer at any time be dissatisfied with such materials or goods or with the method or operations carried out by such sub-contractor's work or place of business, the Engineer shall be empowered to cancel his previously given approval of such sub-contractor/supplier. The Contractor shall then obtain such said materials or goods from other supplier as may be approved by the Engineer and shall bear any additional cost thereof.

1.25 COPIES OF ORDERS

The Contractor and sub-contractors shall provide the Engineer with copies of all orders, which they may place for the supply of materials or goods required in connection with the Works.

1.26 SAMPLES

In addition to any special provisions herein for the sampling and testing of materials, the Contractor shall submit to the Engineer as he may require, samples of all materials and goods, which he proposes to use or employ in or for the Works. Such samples, if approved, will be retained by the Engineer, and no materials or goods of which samples have been submitted shall be used on the Permanent Works unless and until such samples have been approved in writing by the Engineer. Notwithstanding the Engineer's approval as provided for herein the Contractor shall be solely responsible for the quality of all materials and goods supplied.

The cost of supplying all such samples and of conveying the same to such place of inspection or testing as the Engineer may designate within the country of origin and of complying with the requirements of this clause shall be deemed to be included in the rates and prices in the Contract.

1.27 TEST CERTIFICATES

Should the Engineer so require, the Contractor shall obtain Certificates of Tests from the suppliers of any Goods and shall send such Certificates to the Engineer. Such Certificates shall certify that the Goods concerned have been tested in accordance with the requirements of the Specification and shall give the results of all the tests carried out. The Contractor shall provide adequate means of identifying the Goods delivered to the Site with the corresponding Certificates.

The test certificates shall not release the Contractor of any of his obligations under the Contract in connection with the specifications of the relevant Goods when incorporated to the Permanent Works, nor of the necessity for further testing as required in the Specifications or directed by the Engineer.

1.28 WORKS TO BE IN THE DRY

Unless otherwise specified all the works are to be carried out in the dry and they shall be kept free from water coming from whatsoever source to the satisfaction of the Engineer.

1.29 PAYMENT FOR COMPLYING WITH ITEMS 1.01 TO 1.28

There will be no separate payment for complying with the Items 1.01 to 1.28 of this section, and the cost of complying with all the requirements stated herein shall be deemed to be included in the Contractor's rates in the remainder Bills of the Bills of Quantities.

1.20 AS BUILT DRAWINGS

120.1 Description

The work shall consist of preparation of As Built Drawings necessary for performance of the completion of the work covered by the Contract, the Contractor shall supply them by the dates stated in the Contract Data.

The Contractor shall retain, at his sole expense, a qualified engineer for appropriate on site construction inspections to ensure that all improvements as set forth required, pursuant to RDA standards and specification, and as-built shall be provided. The contractor shall certify, in writing, to the Engineer that the improvements were done in compliance with the approved plan or agreement pursuant to RDA Standards & Specifications and as-built shall be provided.

Field managed record drawings should be provided to the Engineer with indicating additions and deletions for approval before preparation of the final as-built Drawings.

The following requirements shall be applied to each as-built drawing developed for the project and a hard copy together with an electronic CAD drawing file in digital format on CD shall submit for the Engineer.

120.2 Construction Requirement

The following items shall be required for all "As-Built Drawings.

- (a) All as-built for projects are required to be on A1 or similar size of construction drawings and shall bear the name and address, of the person who preparing the drawings and the date the as-built data is added to the original via the revision block. Electronic Auto CAD drawing files, based on the GPS coordinate, are also required (if the construction drawings are prepared based on GPS coordinates). Surveyor's/Engineer's statement (with embossed or wet seal and with an original signature on each sheet) shall verify that as-built drawings reflect the true conditions in the field.
- (b) Contractor's statement (with an original signature on each sheet) shall verify that all construction specifications and product qualities have been met or exceeded.
- (c) "AS BUILT DRAWINGS" of "RECORD DRAWING" shall be clearly labelled on each sheet.
- (d) If the details of under-ground service lines (Water, Sewerage, ducts &etc) are available needs to be included to the as-built drawings on the approval of Engineer

- (e) The location and elevation of the benchmark referenced will be shown on the drawing. If the reference benchmark is within the project, then a complete description of its location will be provided to assist in future locating.
- (f) Survey data, relative to the GPS coordinate grid, on right-of-way monuments installed or encountered within the project
- (g) Note any changes to the alignment either vertically or horizontally of curb & gutter sidewalk, pavers or any other surface improvement.

120.3 Measurement & Payments

No payment shall pay for the preparation of As built drawings. If the Contractor does not supply the As Built Drawings by the dates stated in the contract data, or they do not receive the Engineer's approval, the Engineer shall withhold the release of Final payment of the Contract.

REFERENCE ONLY

SECTION - 7

FORM OF BID

REFERENCE ONLY

FORM OF BID

‘CONSTRUCTION OF RAJAMAWATHA EXTENTION ROAD FROM KETAWALA TO MASPANNA (FROM CH 7+560km TO CH 9+300 km), INCLUDING TWO BRIDGES AT CH 7+960 km AND CH 8+380 km ’Under Contract No: RDA/DC/UVA/FD/GOSL/2023/02

To: Director General, Road Development Authority.

Gentlemen:

1. Having examined the Standard Bidding Document – Procurement of Works – Major Contracts [ICTAD/SBD/02 – Second Edition, January 2007 with **addendum issued in October 2009 by ICTAD**], Specifications, Drawings, Bills of Quantities and Addenda for the execution of the above – named Works, we, the undersigned, offer to execute and complete such Works and remedy any defect therein in conformity with the aforesaid Conditions of Contract, Specifications, Drawings, Bills of Quantities and Addenda for the sum of Sri Lankan rupees *..... (Rs.....) (the bid price shall include physical & Price Contingencies and provisional sums but excluding VAT) or such other sums as may be ascertained in accordance with the above documents.
2. We acknowledge that the Contract Data forms part of our Bid.
3. We undertake, if our Bid is accepted, to commence the Works as soon as is reasonably possible after the receipt of the Engineer’s notice to commence, and to complete the whole of the Works comprised in the Contract within the time stated in the Contract data.
4. We agree to abide by this Bid until the date specified in ITB Clause 16..... and it shall remain bidding upon us and may be accepted at any time before that date.
5. Unless and until a formal Agreement is prepared and executed this Bid, together with your written acceptance thereof, shall constitute a binding Contract between us.[#]
6. We understand that you are not bound to accept the lowest or any bid you may receive.
7. We certify / confirm that we comply with the eligibility requirements as per ITB Clause 3 of the bidding documents.

Dated thisday of 2023 in the capacity of Duly authorized to sign bids for and on behalf of

Signature

Address

Witness : 1 Name..... Signature
2 Name Signature

*** The amount inserted here should not include the VAT component**

For the joint venture bid, add following to item 5.0:

if this bid is a joint venture bid we undertake the responsibility to enter into a joint venture agreement among the joint venture partners. We are also well aware that in the event we fail to enter into a joint venture agreement the contract formed between us is null and void and our bid bond will be forfeited by you.

SECTION - 8

BILL OF QUANTITIES

REFERENCE ONLY

BILL OF QUANTITIES

PREAMBLE

1. The Bill of Quantities shall be read in conjunction with all other sections of the bidding documents.
2. General directions and descriptions of work or materials given elsewhere in the bidding Documents are not necessarily repeated in the Bills of Quantities. For the full meaning of each Item, reference should be made to the applicable passages in the bidding documents.
3. The prices and rates entered by the contractor in the Bill of Quantities shall be deemed to cover the complete and finished works in the final position as required in the bidding documents, including, inter alia, all costs and expenses which may be required in and for the construction and maintenance of the works, together with all risks, liabilities, contingencies, insurance, sampling, testing, providing all necessary assistance to the Engineer and in general all obligations imposed or implied by the contract.
4. Without affecting the generality of the foregoing provisions the prices and rates entered by the contractor in the Bills of Quantities shall also include, inter alia, all costs and expenses involved with or arising from the following:
 - i. The provision, storage, transport, handling, use, distribution and maintenance of all materials, plant, equipment, machinery and tools, including all costs, charges, dues demurrage or other outlays involved in carriage and importation.
 - ii. The provision and maintenance of all staff and labour and their payment, accommodation, transport, fares and other requirements.
 - iii. Setting out, including the location, construction and preservation of survey markers, measurement and supervision.
 - iv. The provision, storage, transport, use, handling, distribution and maintenance of all consumable stores fuel, water and electricity including the requirements of the Engineer's Representative and his staff.
 - v. The location, test proving, opening, operation, reinstatement of all quarries and borrow pits, as well as compensation and mining royalties costs associated with quarries and borrow pits or any other land the contractor may require additional to that provided free for the execution of the permanent works.
 - vi. Sampling, the transport of samples, testing, the carrying out of trial sections of earthworks, or payment and the checking of all information given by the Engineer.
 - vii. Injury caused to the Works under Construction, Plant, Materials and consumable stores by weather.
 - viii. Repairs to the Works either prior to or during the Period of maintenance.
 - ix. Maintenance work as detailed in the Specifications and the Conditions of Contract and the maintenance of public amenities.
 - x. Co-ordination with other Contractors or Authorities carrying out work either in connection with or adjacent to the Works.
 - xi. The supply of manufactures test certificates
 - xii. The protection of mains and services, and cost of repairs in case of damage caused by the Contractor.
 - xiii. Pumping and de-watering; the protection of excavation faces.

- xiv. The provision and maintenance of temporary divisions in order that through traffic flow shall remain unobstructed through the contract period and in general the provision of all temporary works required in connection with the works.
- xv. Insurance, custom duties, taxes (without VAT), levies, first aid, welfare and safety requirements and all other overheads and costs, protection of existing bridge in case of stage construction and profit.
5. A price or rate shall be entered against each Item in the Bills of Quantities whether quantities are stated or not. Item against which no price or rate is entered shall be deemed to be covered by the other prices or rates entered by the Contractor in the Bills of Quantities. The unit price or rate entered against any Item shall take precedence over any miscalculation in the total sum against that Item. Where separate items have not been provided in the Bills of Quantities for work shall be deemed to have been included in the other prices and rates.
6. The Quantities given in the Bills of quantities are estimated only and are given to provide a basis for the tender. No guarantee is given for their accuracy and payments to Contractor will be based on the prices and rates quoted in the bills applied to measured quantities for work done.
7. The items in the Bills of Quantities are the general application to the whole of the works at any location on site or any part of the works as indicated in the bid documents or instructed by the Engineer's representative.
8. Tenders which group several items together in the Bill of Quantities under one price will not be accepted.
9. Item mentioned "Provisional" in the Bill of Quantities are not to be executed unless ordered by the Engineer. They may be expended wholly or in part or not at all as directed by the Engineer.
10. The Units of measurement described in the Bills of Quantities are Metric Units. Abbreviations in the Bill of Quantities are as follows:
- | | | | | | |
|-----------------------|---|-----------------|-----------|---|-----------------|
| hrs | - | Hours | cu.deci.m | - | Cubic Decimeter |
| km | - | Kilometre | km-mth | - | KilometreMonths |
| m | - | Linear Metre | mnth | - | Month |
| m ² or sqm | - | Square Metre | ltr | - | Litre |
| m ³ or cum | - | Cubic Metre | kg | - | Kilograms |
| Nos. | - | Numbers | MT | - | Metric Tonne |
| L.S. | - | Lump Sum | Veh-wk | - | Vehicle Week |
| P.S. | - | Provisional Sum | | | |

DAY WORKS

1. The rates entered in the Schedule for Bill of Quantities shall form day works items for pricing extra work ordered to be done in accordance with the Contract.
2. The rates shall include all overheads and profit and all other costs of whatever nature necessary for and incidental to the performance of extra work whenever ordered and these rates required anywhere on the Site for the operation of plant the provision of labour or the provision of materials and shall be deemed to include inter alia:

Plant Operation, maintenance, repairs, fuel, oils grease, hydraulic fluids, taxes, duties operator's wages and overtime, travelling time, transport supervision, administration costs related to the use of such plant.

Labour Wages, overtime, bonuses, travelling time, hand tools, accommodation, fringe benefits, transport and supervision.

Materials Provision, transport, handling, wastage and storage.

In the case of Plant and labour, only time spent working shall be paid for.

For Day works required outside the Site area (which for these purposes shall mean all areas shown on the plans for permanent works and all areas of temporary works such as Contractor's and Engineer's camps, quarry, borrow pits and their access roads, diversion roads etc.), the following should be chargeable :

Plant : Actual travel time from original work site to the place of day of work (without labour charge).

Transport : Travelling time of the places of transport (lorry, low loader etc.)

Labour : Travel time for the means of transport used.

Materials : Travelling time for the means of transport used.

The rates shall apply only to such work, as the Engineer shall instruct in writing to be carried out as day works. All items should be priced.

Summary of Bill of Quantity

‘CONSTRUCTION OF RAJAMAWATHA EXTENTION ROAD FROM KETAWALA TO MASPANNA (FROM CH 7+560km TO CH 9+300 km), INCLUDING TWO BRIDGES AT CH 7+960 km AND CH 8+380 km ’

CONTRACT NO: RDA/DC/UVA/FD/GOSL/2023/02

| <i>Bill No</i> | <i>Description</i> | <i>Amounts / Rs</i> |
|----------------|---|----------------------------|
| <i>1</i> | Preliminaries and General | |
| <i>2</i> | Construction of Bridge at CH 7+960KM accross Bogahakubura Ela | |
| <i>3</i> | Construction of Bridge at CH 08+380 KM across Uma Oya at Halabe | |
| <i>4</i> | Rajamawatha Extension from Ketawala to Maspanna Road (From 7+560KM To 9+300) | |
| <i>5</i> | Day works | |
| A | Sub Total-01 | |
| B | Provisional sums | 1,920,000.00 |
| C | Sub Total -02 (A-B) Provisional sum deduct form Sub Total -01 | |
| <i>D</i> | Discount if any | Amount in words |
| | | Amount in figures |
| E | Sub Total 03 (C-D) | |
| F | Sub Total 04 (E+B) (E+ Provisional Sums) Add Provisional sums to sub total 03 | |
| <i>G</i> | Allow for Physical Contingencies 10% (F*10%) | |
| <i>H</i> | Allow for Price Contingencies 12% (F*12%) | |
| <i>I</i> | Bid Price (F+G+H) [Form of Bid price] | |
| <i>J</i> | VAT (15%*I) | |
| <i>K</i> | Bid Price with VAT (I+J) | |

Amount in words: _____

Name of Authorized Officer: _____

Signature: _____

**CONSTRUCTION OF RAJAMAWATHA EXTENSION ROAD FROM KETAWALA
TO MASPANNA (FROM CH 7+560km TO CH 9+300km), INCLUDING TWO
BRIDGES AT CH 07+960km AND CH 08+380km**

Bill No.1 Preliminaries & General

| Item No. | Pay Item No. | Description | Quantity | Unit | Rate (Rs) | Amount (Rs) |
|--------------------------------------|--------------|--|----------|-------|-----------|-------------|
| | | <u>Mobilization and De-Mobilization of Contractor</u> | | | | |
| 1.1 | | Allow for Mobilization & Demobilization | Item | L.S. | Allow | |
| | | <u>Contract Insurance and Securities</u> | | | | |
| 1.2 | 119(1) | Allow for the cost of providing Insurances. | Item | L.S. | Allow | |
| 1.3 | 119(2) | Allow for the cost of providing Securities and Bonds. | Item | L.S. | Allow | |
| | | <u>Traffic Safety & Control</u> | | | | |
| 1.4 | 103(1) | Allow for safety measures and traffic control | 18.00 | Month | | |
| | | <u>Project sign Boards</u> | | | | |
| 1.5 | 118 (1) | Making & erecting project name board 1.8 m x 2.0 m as directed by the Engineer | 2.00 | Nos | | |
| | | <u>Facilities for the Engineer and Staff</u> | | | | |
| 1.6.1 | | Office for the Engineer and Staff | 18.00 | Month | | |
| 1.6.2 | | Maintenance of office | 18.00 | Month | | |
| 1.6.3 | | Provide furniture for the office | Item | PS | Allow | 300,000.00 |
| 1.6.4 | | Provide Stationary for the Office | Item | PS | Allow | 120,000.00 |
| 1.7 | | Allow for Environmental Permission as directed by Engineer | Item | PS | Allow | 500,000.00 |
| Bill No. 1 Carried to summary | | | | | | |

BILL NO:2**CONSTRUCTION OF BRIDGE AT 7+960KM ACROSS BOGAHAKUBURA ELA ON
RAJAMAWATHA EXTENSION ROAD FROM KETAWALA TO MASPANNA****Bill No:2.1 Site Clearing & Demolishing.**

| Item No. | Pay Item No. | Description | Quantity | Unit | Rate (Rs) | Amount (Rs) |
|--|--------------|--|----------|-------|-----------|-------------|
| 2.1.1 | 201(1) | Clearing and Grubbing inclusive of backfilling holes and trenches caused by removal of stumps. | 200.00 | Sq.m. | | |
| 2.1.2 | 201(2) | Removal of trees, girth greater than or equal to 300 mm and less than 600 mm | 3.00 | No. | | |
| 2.1.3 | 201(3) | Removal of trees, girth greater than or equal to 600 mm and less than 1200 mm | 2.00 | No. | | |
| 2.1.4 | 201(4) | Removal of trees, girth greater than or equal to 1200 mm and less than 2000 mm | 1.00 | No. | | |
| 2.1.5 | 201(5) | Removal of trees, girth greater than 2000 mm. | 1.00 | No. | | |
| 2.1.6 | 201(10) | Removal of overhanging branches of girth exceeding 300 mm | 15.00 | No. | | |
| 2.1.7 | 202(1) | Dismantling the Existing brick masonry structures & culvert pipes | 18.00 | Cu.m | | |
| 2.1.8 | 202(2) | Dismantling and removal of concrete structures. | 24.00 | Cu.m | | |
| Bill No. 2.1 Carried to summary | | | | | | |

Bill No:2.2 Earth Work

| Item No. | Pay Item No. | Description | Quantity | Unit | Rate (Rs) | Amount (Rs) |
|--|--------------|---|----------|-------|-----------|-------------|
| <u>Road way Excavation and Preperation of Subgrade in Cut Areas</u> | | | | | | |
| 2.2.1 | 301 (11) | Road Way Excavation in unclassified soil. | 150.00 | Cu.m. | | |
| 2.2.2 | 304 (3) | Trimming ,leveling and compaction of original ground to 100% standard density. | 200.00 | Sq.m. | | |
| 2.2.3 | 304 (2b) | Embankment construction & back filling Abutment & wing wall using Type 1 material | 250.00 | Cu.m. | | |
| 2.2.4 | 304 (2a) | Embankment construction & back fillng Abutment & Wing wall using Type 11 material | 250.00 | Cu.m. | | |
| 2.2.5 | 409(1) | Shoulder Construction using shoulder material and compacted in position. | 20.00 | Cu.m. | | |
| Bill No. 2.2 Carried to summary | | | | | | |

| Bill No:2.3 Soil Sub Base, Base & Surfacing. | | | | | | |
|---|--------------|--|----------|-------|-----------|-------------|
| Item No. | Pay Item No. | Description | Quantity | Unit | Rate (Rs) | Amount (Rs) |
| | | <u>Sub Base</u> | | | | |
| 2.3.1 | 401 (1) | Soil sub base compacted in position using approved soil (Type 1). | 44.00 | Cu.m. | | |
| | | <u>Dense Graded Aggregate Base</u> | | | | |
| 2.3.2 | 405 (1) | Dense Grade Aggregate Base using aggregate 37.5mm | 38.50 | Cu.m. | | |
| | | <u>Prime Coat</u> | | | | |
| 2.3.3 | 501 (5) | Prime coat with emulsion CSS-1 using 1 ltr/sq.m including blinding with sand at the rate of 250 sq.m./cu.m of sand | 222.00 | Sq.m. | | |
| | | <u>Tack Coat</u> | | | | |
| 2.3.4 | 502 (2) | Applying tack coat to the surface using emulsion CSS1 at a rate of 0.5 Lt/Sq.m. | 537.00 | Sq.m. | | |
| | | <u>Asphalt Concrete Surfacing</u> | | | | |
| 2.3.5 | 506(2) | Asphalt Concrete Surfacing Wearing course 50mm | 48.00 | MT | | |
| Bill No. 2.3 Carried to summary | | | | | | |

| Bill No:2.4 Construction of Bridge. | | | | | | |
|--|--------------|--|----------|-------|-----------|-------------|
| Item No. | Pay Item No. | Description | Quantity | Unit | Rate (Rs) | Amount (Rs) |
| | | <u>2.4. CONSTRUCTION OF BRIDGE</u> | | | | |
| | | 2.4.1. FOUNDATION & SUB STRUCTURE | | | | |
| | | Abutment , Wing walls and Pier | | | | |
| | | <u>Excavation & Back filling</u> | | | | |
| 2.4.1.1 | 302 (5) | Excavation in unsuitable soil and backfilling for Pier, Abutment & Wing walls. | 362.00 | Cu.m. | | |
| 2.4.1.2 | 302 (2) | Excavation in weathered/soft/decomposed rock | 50.00 | Cu.m. | | |
| 2.4.1.3 | 302 (4) | Rock requiring blasting | 20.00 | Cu.m. | | |
| 2.4.1.4 | 302 (11) | Dewatering | Item | LS | | |
| 2.4.1.5 | 302 (10) | Construction of necessary coffer dams, cribs sheeting shoring and bracing and their subsequent removal | Item | LS | | |
| | | <u>Concrete for structure:</u> | | | | |
| 2.4.1.6 | 1001 (3) | Concrete Class C Grade 15 (40 mm) as Screed in Pier, Abutment and Wing Wall foundations. | 44.00 | Cu.m. | | |
| 2.4.1.7 | 1001(1b) | Concrete Class A Grade 25 (20 mm) as Pocket filling in Pier, Abutment and Wing Wall foundations. | 40.00 | Cu.m. | | |
| 2.4.1.8 | 1001(1b) | Concrete Class A Grade 30(20 mm) for Foundation Concrete in Abutment & Wing walls | 84.00 | Cu.m. | | |
| 2.4.1.9 | 1001 (3) | Concrete Class C Grade 15 (40 mm) as Mass Concrete in Abutment & Wing walls | 296.00 | Cu.m. | | |
| 2.4.1.10 | 1001(1b) | Concrete Class A Grade 30 (20mm) in Capping Beams, Ballest walls, Cutain walls and Pier foundation & Pier. | 107.00 | Cu.m. | | |

| Item No. | Pay Item No. | Description | Quantity | Unit | Rate (Rs) | Amount (Rs) |
|----------|--------------|---|----------|-------|-----------|-------------|
| | | <u>Form work</u> | | | | |
| 2.4.1.11 | 1008(2) | Rough finish form work for foundation of Pier, Abutments & Wing Walls | 76.00 | Sq.m. | | |
| 2.4.1.12 | 1008(1) | Smooth finish form work for pier, Abutments, Wing Walls, Capping Beams, balrest walls, Curtain walls and bearing pads. | 717.00 | Sq.m. | | |
| | | <u>Reinforcement</u> | | | | |
| 2.4.1.13 | 1002(1a) | Fabricating & laying Tor steel reinforcement for Pier, Abutment Wing walls, Capping Beams, balrest walls, Curtain walls and bearing pads. | 8.215 | MT | | |
| 2.4.1.14 | 1002(1b) | Fabricating & laying Mild steel reinforcement. | 0.657 | MT | | |
| | | <u>Weep Holes</u> | | | | |
| 2.4.1.15 | 706(1) | Forming weep holes using type 400, PVC pipes of int. dia. not less than 110 mm. | 360.00 | L.M | | |
| | | <u>Drainage & Backfilling</u> | | | | |
| 2.4.1.16 | 705(1) | Backfill using Aggregate 50-200mm for dry stone lining behind Abutment & Wing wall. | 160.00 | Cu.m. | | |
| 2.4.1.17 | 705(2) | 75mm thick, Filter medium using 37.5 mm aggregate behind Abutment & Wing wall. | 17.00 | Cu.m. | | |
| 2.4.1.18 | 705 (3) | 600x300mm Clay puddled laid behind Abutment and Wing walls | 7.00 | Sq.m. | | |

| Item No. | Pay Item No. | Description | Quantity | Unit | Rate (Rs) | Amount (Rs) |
|----------|--------------|---|----------|-------|-----------|-------------|
| | | <u>2.4.2 SUPER STRUCTURE</u> | | | | |
| | | <u>Concrete for structures</u> | | | | |
| 2.4.2.1 | 1001(1b) | Class A Concrete of Grade 25(20mm) in approach slab. | 23.00 | Cu.m. | | |
| 2.4.2.2 | 1001(1) | Class A Concrete of Grade 40(20mm) in Bridge Deck | 189.00 | Cu.m. | | |
| 2.4.2.3 | 1001(1b) | Class A Concrete of Grade 25(20mm) in Foot Walks | 25.00 | Cu.m. | | |
| | | <u>Beams</u> | | | | |
| 2.4.2.4 | 1003(1) | Supplying of 9.5 m long P.S.C. concrete beams | 38.00 | Nos. | | |
| 2.4.2.5 | 1003(2) | Launching of 9.5 m long P.S.C. concrete beams | 38.00 | Nos. | | |
| | | <u>Form work</u> | | | | |
| 2.4.2.6 | 1008(1b) | Smooth finish form work for Deck & Foot walks. | 158.00 | Sq.m. | | |
| 2.4.2.7 | 1008(1b) | Smooth finish form work for Approach Slab. | 13.00 | Sq.m. | | |
| | | <u>Reinforcements</u> | | | | |
| 2.4.2.8 | 1002(1a) | Fabricating & laying Tor steel reinforcement For Deck, Aproch Slab and Foot walk. | 5.000 | MT | | |
| 2.4.2.9 | 1002(1b) | Fabricating & laying Mild steel reinforcement | 0.400 | MT | | |
| | | <u>Railings</u> | | | | |
| 2.4.2.10 | 1018(1) | Standard precast reinforced concrete railings & uprights in class-A, grade.25(20) concrete . (Type drawing T/B/102/B of RDA) | 64.00 | L.M | | |
| 2.4.2.11 | 1019(1) | Construction of end pilasters type iv with foundation in class A concrete of grade 25(20) (Type drawing T/B/106 - Rev 1) | 4.00 | Nos. | | |
| | | <u>Concrete Kerbs</u> | | | | |
| 2.4.2.12 | 807(1a) | Standard precast bridge kerbs(new). Type drawing T/B/106 of RDA) | 64.00 | L.m | | |
| 2.4.2.13 | 807(4) | Constructing 150x50 mm thick insitu Lower kerbs in class B grade 20 (14) concrete for bridge. | 64.00 | L.m | | |

| Item No. | Pay Item No. | Description | Quantity | Unit | Rate (Rs) | Amount (Rs) |
|----------|--------------|---|----------|------|-----------|-------------|
| | | <u>Expansion joints</u> | | | | |
| 2.4.2.14 | 1009(1) | M.S. angle iron & hard rubber expansion joints (Type drawing T/B/107-Rev-1 of RDA) | 31.50 | L.m | | |
| | | <u>Bridge bearings</u> | | | | |
| 2.4.2.15 | 1010(2) | 75x12mm. Hard rubber bearing pads supplied & laid over capping beam and for approach slab | 42.00 | L.m | | |
| | | <u>Miscellaneous</u> | | | | |
| 2.4.2.16 | 1012 (1) | Supplying & fixing 200 mm long , 20mm dia.Stainless steel dowels in capping beam at fixed end. | 42.00 | Nos. | | |
| 2.4.2.17 | 1011 (1) | Supplying & fixing 200 mm long , 25mm dia.MS steel dowels in Corbel wall for Approach slab fix end. | 35.00 | Nos. | | |
| 2.4.2.18 | 1011B(1) | Supplying & fixing M.S. Dowels, spliced and dove tailed with wedge at one end,20mm dia. And 1.0 m long,1.20 m C/C Stagered on foundations | 105.00 | Nos. | | |
| 2.4.2.19 | 1020(1a) | Supplying & fixing 110mm dia. PVC pipes as rain water outlets through deck as per drawing. | 44.00 | L.m. | | |
| 2.4.2.20 | 1020(1b) | Supplying & fixing 50mm dia. PVC pipes as rain water outlets through duct as per drawing. | 20.00 | L.m. | | |
| 2.4.2.21 | 1013 (1) | Bituminous sealing material supplied and laid under beam ends to prevent grout leak to capping beam. | 31.50 | L.m | | |
| 2.4.2.22 | 1014 (1) | Bituminous sealing material supplied and laid under beam ends to prevent grout leak to approach slab. | 62.00 | L.m | | |
| 2.4.2.23 | 1403(7) | Painting with enamel Two coat to Hand rails,End pilasters of bridge and guard stones | 350.00 | Sq.m | | |
| 2.4.2.24 | 1017(1) | 100mm Thick Cover Slab (500x450x100mm sized) for Service Duct in Class B grade 25 (20) Concrete inclusive of light reinforcement. | 38.40 | Sq.m | | |
| 2.4.2.25 | 1016(1) | Forming of service duct in the deck , 340mm depth and 350mm width | 64.00 | L.m | | |
| | | | | | | |
| | | | | | | |

| Item No. | Pay Item No. | Description | Quantity | Unit | Rate (Rs) | Amount (Rs) |
|----------|--------------|--|----------|-------|-----------|-------------|
| 2.4.2.26 | 808 (5) | Casting and Fixing standard type guard stone in 225 mm thick cement concrete 1:3:6 (20 mm) | 12.00 | Nos. | | |
| 2.4.2.27 | 802(1) | Turfing on Embankment slope and in other area as necessary | 50.00 | Sq.m. | | |
| 2.4.2.28 | 804(1) | Grouted rip rap filled with 1:3 cement mortar as per drawing | 120.00 | Cu.m. | | |
| 2.4.2.29 | | Construction of 2 Nos. reinforced concrete staircase to access underneath of the bridge | Item | PS | Allow | 500,000.00 |
| | | Bill No. 2.4 Carried to summary | | | | |

BILL NO:3**CONSTRUCTION OF BRIDGE AT CH 08+380 KM ACROSS UMA OYA AT HALABE
ON RAJAMAWATHA EXTENSION ROAD FROM KETAWALA TO MASPANNA****Bill No: 3.1 Site Clearing & Demolishing.**

| Item No. | Pay Item No. | Description | Quantity | Unit | Rate (Rs) | Amount (Rs) |
|--|--------------|--|----------|-------|-----------|-------------|
| 3.1.1 | 201(1) | Clearing and Grubbing inclusive of backfilling holes and trenches caused by removal of stumps. | 360.00 | Sq.m. | | |
| 3.1.2 | 201(2) | Removal of trees, girth greater than or equal to 300 mm and less than 600 mm | 3.00 | No. | | |
| 3.1.3 | 201(3) | Removal of trees, girth greater than or equal to 600 mm and less than 1200 mm | 2.00 | No. | | |
| 3.1.4 | 201(4) | Removal of trees, girth greater than or equal to 1200 mm and less than 2000 mm | 1.00 | No. | | |
| 3.1.5 | 201(5) | Removal of trees, girth greater than 2000 mm. | 1.00 | No. | | |
| 3.1.6 | 201(10) | Removal of overhanging branches of girth exceeding 300 mm | 10.00 | No. | | |
| 3.1.7 | 202(1) | Dismantling the Existing brick masonry structures & culvert pipes | 18.00 | Cu.m | | |
| 3.1.8 | 202(2) | Dismantling and removal of concrete structures. | 30.00 | Cu.m | | |
| Bill No. 3.1 Carried to summary | | | | | | |

Bill No:3.2 Earth Work

| Item No. | Pay Item No. | Description | Quantity | Unit | Rate (Rs) | Amount (Rs) |
|--|--------------|--|----------|-------|-----------|-------------|
| <u>Road way Excavation and Preperation of Subgrade in Cut Areas</u> | | | | | | |
| 3.2.1 | 301 (11) | Road Way Excavation in unclassified soil. | 220.00 | Cu.m. | | |
| 3.2.2 | 304 (3) | Trimming ,leveling and compaction of original ground to 100% standard density. | 360.00 | Sq.m. | | |
| 3.2.3 | 304 (2b) | Embankment construction & back filling Abutment & wing wall using Type 1 material | 320.00 | Cu.m. | | |
| 3.2.4 | 304 (2a) | Embankment construction & back filling Abutment & Wing wall using Type 11 material | 320.00 | Cu.m. | | |
| 3.2.5 | 409(1) | Shoulder Construction using shoulder material and compacted in position. | 20.00 | Cu.m. | | |
| Bill No. 3.2 Carried to summary | | | | | | |

Bill No:3.3 Soil Sub Base, Base & Surfacing.

| Item No. | Pay Item No. | Description | Quantity | Unit | Rate (Rs) | Amount (Rs) |
|----------|--------------|---|----------|-------|-----------|-------------|
| | | <u>Sub Base</u> | | | | |
| 3.3.1 | 401 (1) | Soil sub base compacted in position using approved soil (Type 1). | 42.00 | Cu.m. | | |
| | | <u>Dense Graded Aggregate Base</u> | | | | |
| 3.3.2 | 405 (1) | Dense Grade Aggregate Base using aggregate 37.5mm | 35.00 | Cu.m. | | |
| | | <u>Prime Coat</u> | | | | |
| 3.3.3 | 501 (5) | Prime coat with emulsion CSS-1 using 1 ltr/sq.m including blinding with sand at the rate of 250 sq.m/cu.m of sand | 444.00 | Sq.m. | | |
| | | <u>Tack Coat</u> | | | | |
| 3.3.4 | 502 (2) | Applying tack coat to the surface using emulsion CSS1 at a rate of 0.5 Lt/Sq.m. | 1,179.00 | Sq.m. | | |
| | | <u>Asphalt Concrete Surfacing</u> | | | | |
| 3.3.5 | 506(2) | Asphalt Concrete Surfacing Wearing course 50mm | 114.00 | MT | | |
| | | Bill No. 3.3 Carried to summary | | | | |

| Bill No:3.4 Construction of Bridge. | | | | | | |
|--|--------------|--|----------|-------|-----------|-------------|
| Item No. | Pay Item No. | Description | Quantity | Unit | Rate (Rs) | Amount (Rs) |
| | | 3.4 CONSTRUCTION OF BRIDGE | | | | |
| | | 3.4.1 FOUNDATION & SUB STRUCTURE | | | | |
| | | Abutment, Wing walls and Pier | | | | |
| | | <u>Excavation & Back filling</u> | | | | |
| 3.4.1.1 | 302 (5) | Excavation in unsuitable soil and backfilling for Pier, Abutment & Wing walls. | 1,102.00 | Cu.m. | | |
| 3.4.1.2 | 302 (4) | Rock requiring blasting | 120.00 | Cu.m. | | |
| 3.4.1.3 | 302 (11) | Dewatering | Item | LS | Allow | |
| 3.4.1.4 | 302 (10) | Construction of necessary coffer dams, cribs sheeting shoring and bracing and their subsequent removal | Item | LS | Allow | |
| | | <u>Concrete for structure:</u> | | | | |
| 3.4.1.5 | 1001 (3) | Concrete Class C Grade 15 (40 mm) as Screed in Pier, Abutment and Wing Wall foundations. | 21.00 | Cu.m. | | |
| 3.4.1.6 | 1001(1b) | Concrete Class A Grade 30 (20 mm) as Pocket filling in Pier, Abutment and Wing Wall foundations. | 50.00 | Cu.m. | | |
| 3.4.1.7 | 1001(1b) | Concrete Class A Grade 30(20 mm) for Foundation Concrete in Abutment & Wing walls | 138.00 | Cu.m. | | |
| 3.4.1.8 | 1001 (3) | Concrete Class C Grade 15 (40 mm) as Mass Concrete in Abutment & Wing walls | 818.00 | Cu.m. | | |
| 3.4.1.9 | 1001(1b) | Concrete Class A Grade 30 (20mm) in Capping Beams, Ballest walls & Curtain walls. | 54.00 | Cu.m. | | |
| 3.4.1.10 | 1001(1b) | Concrete Class A Grade 30 (20mm) in Pier foundation | 128.00 | Cu.m. | | |
| 3.4.1.11 | 1001 (3) | Concrete Class C Grade 15 (40 mm) in Pier Stem | 805.00 | Cu.m. | | |

| Item No. | Pay Item No. | Description | Quantity | Unit | Rate (Rs) | Amount (Rs) |
|----------|--------------|---|----------|-------|-----------|-------------|
| | | <u>Form work</u> | | | | |
| 3.4.1.12 | 1008(2) | Rough finish form work for foundation of Pier, Abutments & Wing Walls | 151.00 | Sq.m. | | |
| 3.4.1.13 | 1008(1) | Smooth finish form work for pier, Abutments, Wing Walls, Capping Beams, ballest walls, Curtain walls, bearing pads and others. | 2,449.00 | Sq.m. | | |
| | | <u>Reinforcement</u> | | | | |
| 3.4.1.14 | 1002(1a) | Fabricating & laying Tor steel reinforcement for Pier, Abutment Wing walls, Capping Beams, ballest walls, Curtain walls, bearing pads and others. | 14.365 | MT | | |
| 3.4.1.15 | 1002(1b) | Fabricating & laying Mild steel reinforcement. | 1.149 | MT | | |
| | | <u>Weep Holes</u> | | | | |
| 3.4.1.16 | 706(1) | Forming weep holes using type 400, PVC pipes of int. dia. not less than 110 mm. | 384.00 | L.M | | |
| | | <u>Drainage & Backfilling</u> | | | | |
| 3.4.1.17 | 705(1) | Backfill using Aggregate 50-200mm for dry stone lining behind Abutment & Wing wall. | 192.00 | Cu.m. | | |
| 3.4.1.18 | 705(2) | 75mm thick, Filter medium using 37.5 mm aggregate behind Abutment & Wing wall. | 21.00 | Cu.m. | | |
| 3.4.1.19 | 705 (3) | 600x 300mm Clay puddled laid behind Abutment and Wing walls | 9.00 | Sq.m. | | |

| Item No. | Pay Item No. | Description | Quantity | Unit | Rate (Rs) | Amount (Rs) |
|----------|--------------|---|----------|-------|-----------|-------------|
| | | <u>3.4.2 SUPER STRUCTURE</u> | | | | |
| | | <u>Concrete for structures</u> | | | | |
| 3.4.2.1 | 1001(1b) | Class A concrete of grade 30(20mm) in approach slab. | 23.00 | Cu.m. | | |
| 3.4.2.2 | 1001(1) | Class A Concrete of Grade 40(20mm) in Bridge Deck | 239.00 | Cu.m. | | |
| 3.4.2.3 | 1001(1b) | Class A Concrete of Grade 30(20mm) in Foot Walks | 50.00 | Cu.m. | | |
| | | <u>Beams</u> | | | | |
| 3.4.2.4 | 1003(1) | Supplying of 13.5 m long P.S.C. concrete beams | 100.00 | Nos. | | |
| 3.4.2.5 | 1003(2) | Launching of 13.5 m long P.S.C. concrete beams | 100.00 | Nos. | | |
| | | <u>Form work</u> | | | | |
| 3.4.2.6 | 1008(1b) | Smooth finish form work for Deck & Foot walks. | 226.00 | Sq.m. | | |
| 3.4.2.7 | 1008(1b) | Smooth finish form work for Approach Slab and Others. | 13.00 | Sq.m. | | |
| | | <u>Reinforcements</u> | | | | |
| 3.4.2.8 | 1002(1a) | Fabricating & laying Tor steel reinforcement For Deck, Aproch Slab and Foot walk and Others. | 9.000 | MT | | |
| 3.4.2.9 | 1002(1b) | Fabricating & laying Mild steel reinforcement | 0.400 | MT | | |
| | | <u>Railings</u> | | | | |
| 3.4.2.10 | 1018(1) | Standard precast reinforced concrete railings & uprights in class-A, grade.25(20) concrete . (Type drawing T/B/102/B of RDA) | 144.00 | L.M | | |
| 3.4.2.11 | 1019(1) | Construction of end pilasters type iv with foundation in class A concrete of grade 25(20) (Type drawing T/B/106 - Rev 1) | 4.00 | Nos. | | |
| | | <u>Concrete Kerbs</u> | | | | |
| 3.4.2.12 | 807(1a) | Standard precast bridge kerbs(new). Type drawing T/B/106 of RDA) | 144.00 | L.m | | |
| 3.4.2.13 | 807(4) | Constructing 150x50 mm thick insitu Lower kerbs in class B grade 20 (14) concrete for bridge. | 144.00 | L.m | | |

| Item No. | Pay Item No. | Description | Quantity | Unit | Rate (Rs) | Amount (Rs) |
|----------|--------------|---|----------|------|-----------|-------------|
| | | <u>Expansion joints</u> | | | | |
| 3.4.2.14 | 1009(1) | M.S. angle iron & hard rubber expansion joints (Type drawing T/B/107 Rev-1 of RDA) | 63.00 | L.m | | |
| | | <u>Bridge bearings</u> | | | | |
| 3.4.2.15 | 1010(2) | 75x12mm. Hard rubber bearing pads supplied & laid over capping beam and for approach slab | 105.00 | L.m | | |
| | | <u>Miscellaneous</u> | | | | |
| 3.4.2.16 | 1012 (1) | Supplying & fixing 200 mm long , 20mm dia.Stainless steel dowels in capping beam at fixed end. | 95.00 | Nos. | | |
| 3.4.2.17 | 1011 (1) | Supplying & fixing 200 mm long , 25mm dia.MS steel dowels in Corbel wall for Approach slab fix end. | 35.00 | Nos. | | |
| 3.4.2.18 | 1011B(1) | Supplying & fixing M.S. Dowels, spliced and dove tailed with wedge at one end,20mm dia. and 1.0 m long,1.20 m C/C Stagered on foundations | 192.00 | Nos. | | |
| 3.4.2.19 | 1020(1a) | Supplying & fixing 110mm dia. PVC pipes as rain water outlets through deck as per drawing. | 40.00 | Nos. | | |
| 3.4.2.20 | 1020(1b) | Supplying & fixing 50mm dia. PVC pipes as rain water outlets through duct as per drawing. | 40.00 | Nos. | | |
| 3.4.2.21 | 1013 (1) | Bituminous sealing material supplied and laid under beam ends to prevent grout leak to capping beam. | 63.00 | L.m | | |
| 3.4.2.22 | 1014 (1) | Bituminous sealing material supplied and laid under beam ends to prevent grout leak to approach slab. | 62.00 | L.m | | |
| 3.4.2.23 | 1403(7) | Painting with enamel Two coat to Hand rails,End pilasters of bridge, guard stones | 425.00 | Sq.m | | |
| 3.4.2.24 | 1015(1) | Supply and placing 200mm dia Displacers of polythene tubes filled with light materials. | 1,400.00 | L.m | | |
| 3.4.2.25 | 1017(1) | 100mm Thick Cover Slab (500x450x100mm sized) for Service Duct in Class B grade 25 (20) Concrete inclusive of light reinforcement. | 84.00 | Sq.m | | |
| 3.4.2.26 | 1016(1) | Forming of service duct in the deck , 230mm depth and 500mm width | 140.00 | L.m | | |

| Item No. | Pay Item No. | Description | Quantity | Unit | Rate (Rs) | Amount (Rs) |
|----------|--------------|--|----------|-------|-----------|-------------|
| 3.4.2.27 | 808 (5) | Casting and Fixing standard type guard stone in 225 mm thick cement concrete 1:3:6 (20 mm) | 12.00 | Nos. | | |
| 3.4.2.28 | 802(1) | Turfing on Embankment slope and in other area as necessary | 50.00 | Sq.m. | | |
| 3.4.2.29 | 804(1) | Grouted rip rap filled with 1:3 cement mortar as per drawing | 120.00 | Cu.m. | | |
| 3.4.2.30 | | Construction of 2 Nos. reinforced concrete staircase to access underneath of the bridge | Item | PS | Allow | 500,000.00 |
| | | Bill No. 3.4 Carried to summary | | | | |

BILL NO:4**CONSTRUCTION OF RAJAMAWATHA EXTENSION ROAD FROM KETAWALA TO MASPANNA (FROM CH 7+560km TO CH 9+300km)****BILL NO : 4.1 SITE CLEARANCE**

| Item No. | Pay Item No | Description | Quantity | Unit | Rate (Rs.) | Amount (Rs.) |
|---|--------------------|--|-----------------|-------------|-------------------|---------------------|
| 4.1.1 | | CLEARING AND GRUBBING | | | | |
| 4.1.1.1 | 201(1) | Clearing and Grubbing inclusive of backfilling holes and trenches caused by removal of stumps. | 11,700.00 | Sq.m. | | |
| 4.1.1.2 | 201(2) | Removal of trees, girth greater than or equal to 300 and less than 600 mm | 25 | No. | | |
| 4.1.1.3 | 201(3) | Removal of trees, girth greater than or equal to 600 and less than 1200 mm | 13 | No. | | |
| 4.1.1.4 | 201(4) | Removal of trees, girth greater than or equal to 1200 and less than 2000 mm | 11 | No. | | |
| 4.1.1.5 | 201(10) | Removal of overhanging branches of girth exceeding 300 mm | 50 | No. | | |
| 4.1.2 | | REMOVAL OF STRUCTURES AND OBSTRUCTION | | | | |
| 4.1.2.1 | 202(2) | Dismantle & remove concrete structures | 25.00 | Cu.m | | |
| SITE CLEARING - TOTAL CARRIED TO GRAND SUMMARY | | | | | | |

BILL NO:4**CONSTRUCTION OF RAJAMAWATHA EXTENSION ROAD FROM KETAWALA TO MASPANNA (FROM CH 7+560km TO CH 9+300km)****BILL NO : 4.2 EARTH WORKS**

| Item No. | Pay Item No | Description | Quantity | Unit | Rate (Rs.) | Amount (Rs.) |
|--|--------------------|--|-----------------|-------------|-------------------|---------------------|
| 4.2.1 | | ROADWAY EXCAVATION | | | | |
| 4.2.1.1 | 301(1) | Roadway Excavation, soil suitable for construction works. | 1,460.00 | Cu.m. | | |
| 4.2.1.2 | 301(11) | Roadway Excavation, unsuitable soil for construction works | 2,929.92 | Cu.m. | | |
| 4.2.1.3 | 301(7) | Excavation in weathered/decomposed rock | 884.80 | Cu.m. | | |
| 4.2.1.4 | 301(8) | Roadway Excavation, in hard rock(not chemical blasting) | 308.00 | Cu.m. | | |
| 4.2.1.5 | 301(14) | Roadway excavation in marshy materials/ soil | 972.00 | Cu.m. | | |
| 4.2.2 | | EMBANKMENT CONSTRUCTION | | | | |
| 4.2.2.1 | 304(1)a | Embankment construction using material (Type II) from roadway excavation compacted in position | 1,222.00 | Cu.m. | | |
| 4.2.2.2 | 304(2)b | Embankment construction using borrow material (type 1) and compacted in position | 868.00 | Cu.m. | | |
| 4.2.2.3 | 304(2)a | Embankment construction using borrow material (type II) and compacted in position | 250.00 | Cu.m. | | |
| 4.2.2.4 | 304(3) | Trimming leveling and compaction of original ground | 2,080.00 | Sq.m. | | |
| 4.2.3 | | SOFT GROUND IMPROVEMENT | | | | |
| 4.2.3.1 | 304(6) | Ground improvement Compacted 150mm - 225mm rubble with 40mm metal | 1,296.00 | Cu.m. | | |
| 4.2.3.2 | 307(9) | Geo -textile | 1,296.00 | Sq.m. | | |
| EARTHWORKS - TOTAL CARRIED TO SUMMARY | | | | | | |

BILL NO:4**CONSTRUCTION OF RAJAMAWATHA EXTENSION ROAD FROM KETAWALA
TO MASPANNA (FROM CH 7+560km TO CH 9+300km)****BILL NO : 4.3 SUB - BASES, BASES AND SHOULDERS**

| Item No. | Pay Item No | Description | Quantity | Unit | Rate (Rs.) | Amount (Rs.) |
|---|--------------------|--|-----------------|-------------|-------------------|---------------------|
| 4.3.1 | | SUB BASE | | | | |
| 4.3.1.1 | 401(1) | Provide and place Sub base as compacted in position Type I | 2,973.80 | Cu.m. | | |
| 4.3.1.2 | 401(1) | Provide and place Sub base (Capping Layer) as compacted in position Type II | 2,699.41 | Cu.m. | | |
| 4.3.2 | | DENSE GRADED AGGREGATE BASE | | | | |
| 4.3.2.1 | 405(1) | Provide and place 37.5 mm dense graded aggregate base as compacted in position | 2,592.00 | Cu.m. | | |
| 4.3.3 | | SHOULDERS | | | | |
| 4.3.3.1 | 409(1) | Earthen shoulder as compacted in position | 340.00 | Cu.m. | | |
| SUB - BASES, BASES AND SHOULDERS TOTAL CARRIED TO MAIN SUMMARY | | | | | | |

BILL NO:4**CONSTRUCTION OF RAJAMAWATHA EXTENSION ROAD FROM KETAWALA
TO MASPANNA (FROM CH 7+560km TO CH 9+300km)****BILL NO : 4.4 SURFACINGS**

| Item No. | Pay Item No | Description | Quantity | Unit | Rate (Rs.) | Amount (Rs.) |
|---|--------------------|---|-----------------|-------------|-------------------|---------------------|
| 4.4.1 | | PRIME COAT | | | | |
| 4.4.1.1 | 501(5) | Bituminous Prime coat using MC 30 at 1 ltr/sq.m) | 12,960.00 | Sq.m. | | |
| 4.4.2 | | TACK COAT | | | | |
| 4.4.2.1 | 502(2) | Tack coat using emulsion CSS1 at rate of 0.5 Lt/Sq.m. | 12,960.00 | Sq.m. | | |
| 4.4.3 | | ASPHALT CONCRETING SURFACING | | | | |
| 4.4.3.1 | 506(1) | Asphalt concrete surfacing Wearing Course 50mm thick | 12,960.00 | Sq.m. | | |
| SURFACINGS TOTAL CARRIED TO MAIN SUMMARY | | | | | | |

BILL NO:4**CONSTRUCTION OF RAJAMAWATHA EXTENSION ROAD FROM KETAWALA TO
MASPANNA (FROM CH 7+560km TO CH 9+300km)****BILL NO :4.5 DRAINAGE**

| Item No. | Pay Item No | Description | Quantity | Unit | Rate (Rs.) | Amount (Rs.) |
|---|--------------------|---|-----------------|-------------|-------------------|---------------------|
| ROADSIDE AND LEAD AWAY SURFACE DRAINS | | | | | | |
| 4.5.1 | | EXCAVATION AND BACKFILL | | | | |
| 4.5.1.1 | 301A(5) | Excavation for lining of drains in unsuitable soil | 132.00 | Cu.m. | | |
| 4.5.2 | | CONCRETING | | | | |
| 4.5.2.1 | 701 (2) | Lining of drains with in-situ concrete (Class B Grade 25/19) | 342.00 | Cu.m. | | |
| 4.5.2.2 | 1001 (3) | Class C concrete Grade 15 (37.5 mm) as screed for the foundation | 75.00 | Cu.m. | | |
| 4.5.3 | | PLACING COVER SLAB | | | | |
| 4.5.3.1 | 701 (6)b | 100 mm thick ,Class B Grade25(20) Precast concrete cover slab including reinforcement & formwork | 28.00 | Sq.m. | | |
| 4.5.4 | | REINFORCEMENT | | | | |
| 4.5.4.1 | 1002(1) a | Steel Reinforcement (Tor Steel) | 9.00 | Tonnes | | |
| 4.5.5 | | FORM WORK | | | | |
| 4.5.5.1 | 1008(1) | Formwork, Smooth finish | 382.00 | Sq.m. | | |
| 4.5.5.2 | 1008(2) | Formwork, Rough finish | 1,476.00 | Sq.m. | | |
| 4.5.6 | | WEEP HOLES | | | | |
| 4.5.6.1 | 706(1) | Forming weep holes in Line drains walls using P.V.C. pipes of int. dia. not grater than 50 mm complete with dripledge and surround finished smooth. | 100.00 | L.m. | | |
| DRAINAGE CONSTRUCTIONS TOTAL CARRIED TO MAIN SUMMARY | | | | | | |

BILL NO:4**CONSTRUCTION OF RAJAMAWATHA EXTENSION ROAD FROM KETAWALA TO
MASPANNA (FROM CH 7+560km TO CH 9+300km)****BILL NO : 4.6 STRUCTURES CONSTRUCTION**

| Item No. | Pay Item No | Description | Quantity | Unit | Rate (Rs.) | Amount (Rs.) |
|-----------------|--------------------|--|-----------------|-------------|-------------------|---------------------|
| | | STRUCTURES CONSTRUCTION | | | | |
| 4.6.1 | | EXCAVATION AND BACKFILL FOR STRUCTURES | | | | |
| 4.6.1.1 | 302 (5) | Excavation in unsuitable soil and backfilling for Structure | 158.00 | Cu.m. | | |
| 4.6.1.2 | 301 A (5) | Channel excavation, unsuitable soil | 155.00 | Cu.m. | | |
| 4.6.2 | | CONCRETING | | | | |
| 4.6.2.1 | 1001 (3) | Class C Concrete Grade 15 (37.5 mm) as screed for the foundation | 56.00 | Cu.m. | | |
| 4.6.2.2 | 1001(1) | Class A Concrete Grade 30(20) in Box structure | 50.00 | Cu.m. | | |
| 4.6.2.3 | 1001(1b) | Concrete Class A Grade 25(20 mm) Base Concrete for retaining wall | 158.00 | Cu.m. | | |
| 4.6.2.4 | 1001 (3) | Concrete Class C Grade 15 (40 mm) as Mass Concrete in retaining wall | 640.00 | Cu.m. | | |

| Item No. | Pay Item No | Description | Quantity | Unit | Rate (Rs.) | Amount (Rs.) |
|---|-------------|--|----------|-------|------------|--------------|
| 4.6.3 | | REINFORCEMENT | | | | |
| 4.6.3.1 | 1002(1) a | Steel Reinforcement (Tor Steel) | 8.00 | MT | | |
| 4.6.4 | | FORM WORK | | | | |
| 4.6.4.1 | 1008(1) | Formwork, Smooth finish | 160.00 | Sq.m. | | |
| 4.6.4.2 | 1008(2) | Formwork, Rough finish | 940.00 | Sq.m. | | |
| 4.6.5 | | WEEP HOLES | | | | |
| 4.6.5.1 | 706(1) | Forming weep holes using type 400, PVC pipes of int. dia. not less than 110 mm. | 100.00 | L.m. | | |
| 4.6.6 | | GABION STRUCTURE | | | | |
| 4.6.6.1 | 805(1) | Supply and placing PVC coated Gabbions boxes including rubble filling | 819.00 | Cu.m. | | |
| 4.6.6.2 | 307(9) | Geo Textile Layer | 954.00 | Sq.m. | | |
| 4.6.6.3 | 304(6) | Compacted rubble base 150mm-225mm rubble with 40mm metal at bottom of gabion walls | 286.00 | Cu.m. | | |
| 4.6.7 | | RETAINING WALL STRUCTURE | | | | |
| 4.6.7.1 | 705(1) | Backfill using Aggregate 50-200mm for dry stone lining behind retaining wall | 373.00 | Cu.m. | | |
| 4.6.7.2 | 705(2) | 75mm thick, Filter medium using 37.5 mm aggregate behind retaining wall | 55.00 | Cu.m. | | |
| 4.6.7.3 | 705 (3) | Clay puddled laid behind retaining wall | 35.00 | Cu.m. | | |
| STRUCTURES CONSTRUCTIONS TOTAL CARRIED TO MAIN SUMMARY | | | | | | |

BILL NO:4

**CONSTRUCTION OF RAJAMAWATHA EXTENSION ROAD FROM KETAWALA
TO MASPANNA (FROM CH 7+560km TO CH 9+300km)**

BILL NO :4.7 'INCIDENTAL CONSTRUCTIONS

| Item No. | Pay Item No | Description | Quantity | Unit | Rate (Rs.) | Amount (Rs.) |
|---|--------------------|---|-----------------|-------------|-------------------|---------------------|
| 4.7.1 | | TOP SOILLING AND GRASSING | | | | |
| 4.7.1.1 | 802(1) | Turfing on Embankment slope and in other area as necessary | 2,700.00 | Sq.m. | | |
| 4.7.2 | | ROAD MARKING PAINT (3 mm thick) | | | | |
| 4.7.2.1 | 810(1) a | Road line marking 100mm width, using thermoplastic material (White, Yellow) | 406.00 | Sq.m. | | |
| 4.7.3 | | ROAD SIGNS | | | | |
| 4.7.3.1 | 811(1) | Reflective road signs single pole, sign area up to 0.5 m ² | 30.00 | No. | | |
| 4.7.3.2 | 811(2) | Reflective road signs double pole, sign area up to 2.0 m ² | 8.00 | No. | | |
| INCIDENTAL CONSTRUCTIONS TOTAL CARRIED TO MAIN SUMMARY | | | | | | |

BILL NO:5

CONSTRUCTION OF RAJAMAWATHA EXTENSION ROAD FROM
KETAWALA TO MASPANNA (FROM CH 7+560km TO CH 9+300km),
INCLUDING TWO BRIDGES AT CH 07+960km AND CH 08+380km

BILL NO:5 SCHEDULE OF DAY WORK RATES**5.1 / LABOUR DAY WORKS**

All Quantities are Provisional

| Item No. | Description | Unit | Quantity | Rate (Rs.) | Amount (Rs) |
|--|---------------------------------|------|----------|------------|-------------|
| 1 | Surveyor | Hrs | 60 | | |
| 2 | Survey Assistant (Skilled) | Hrs | 60 | | |
| 3 | Laboratory Technician (Skilled) | Hrs | 60 | | |
| 4 | Cad Operator | Hrs | 60 | | |
| 5 | Draughtman | Hrs | 60 | | |
| 6 | Operator, Light Equipment | Hrs | 70 | | |
| 7 | Driver, Heavy Duty Vehicles | Hrs | 70 | | |
| 8 | Driver, Light Duty Vehicles | Hrs | 70 | | |
| 9 | Mechanic | Hrs | 40 | | |
| 10 | Welder | Hrs | 40 | | |
| 11 | Electrician | Hrs | 40 | | |
| 12 | Mason | Hrs | 45 | | |
| 13 | Semi- skilled Labour | Hrs | 45 | | |
| 14 | Unskilled Labour | Hrs | 60 | | |
| Labour Day Works Carried to summary | | | | | |

BILL NO:5**CONSTRUCTION OF RAJAMAWATHA EXTENSION ROAD FROM KETAWALA TO MASPANNA (FROM CH 7+560km TO CH 9+300km), INCLUDING TWO BRIDGES AT CH 07+960km AND CH 08+380km****BILL NO:5 SCHEDULE OF DAY WORK RATES****5.2 / MATERIAL DAY WORKS****All Quantities are Provisional**

| Item No. | Description | Unit | Quantity | Rate (Rs.) | Amount (Rs) |
|-----------------|--|-------------|-----------------|-------------------|--------------------|
| 1 | Aggregate base, dense graded (37.5 mm) | cu.m | 8 | | |
| 2 | Aggregate, 12 mm | cu.m | 3 | | |
| 3 | Aggregate, 19 mm | cu.m | 2 | | |
| 4 | Aggregate, 37.5 mm | cu.m | 3 | | |
| 5 | Asphalt concrete, cold mix | mt | 2 | | |
| 6 | Asphalt concrete, hot mix (Surfacing Material) | mt | 2 | | |
| 7 | Bitumen emulsions, (CRS 1, CRS 2, CSS 1) | ltr | 35 | | |
| 8 | Bitumen prime coat, cutback MC 30 | ltr | 35 | | |
| 9 | Cement, ordinary Portland | nr | 15 | | |
| 10 | Concrete pipe, reinforced 600 mm diameter, 2.4m length | nr | 1 | | |
| 11 | Concrete, Grade 15/20 | cu.m | 2 | | |
| 12 | Concrete, Grade 20/20 | cu.m | 2 | | |
| 13 | Concrete, Grade 25/20 | cu.m | 2 | | |
| 14 | Paint, emulsion | ltr | 4 | | |
| 15 | Paint, enamel | ltr | 4 | | |
| 16 | Lime | kg | 20 | | |
| 17 | Reinforcement, high-yield steel, Grade 460/425 | kg | 30 | | |
| 18 | Reinforcement, mild steel, Grade 250 | kg | 30 | | |
| 19 | Rubble, 150 - 225 mm | cu.m | 2 | | |
| 20 | River Sand | cu.m | 4 | | |
| 21 | Auto diesel | ltr | 50 | | |
| 22 | Petrol | ltr | 45 | | |
| 23 | kerosene Oil | ltr | 10 | | |

Material Day works Carried to Summary :

BILL NO:5

CONSTRUCTION OF RAJAMAWATHA EXTENSION ROAD FROM KETAWALA TO MASPANNA (FROM CH 7+560km TO CH 9+300km), INCLUDING TWO BRIDGES AT CH 07+960km AND CH 08+380km

BILL NO:5 SCHEDULE OF DAY WORK RATES**5.3 / EQUIPMENT DAY WORKS**

All Quantities are Provisional

| Item No. | Description | Unit | Quantity | Rate (Rs.) | Amount (Rs) |
|---|---|------|----------|------------|-------------|
| 1 | Lorry, 5 to 10 tonnes | Km | 100 | | |
| 2 | Water Bowser, up to 6,000 litres with Spray Bar | hr | 6 | | |
| 3 | Farm Tractor & Broom over 2m width | hr | 6 | | |
| 4 | Backhoe, wheeled, 4 WD | hr | 7 | | |
| 5 | Motor grader, up to 100 HP (65 HP) | hr | 6 | | |
| 6 | Hand roller, vibratory, 1/2 - 1 tonne | hr | 15 | | |
| 7 | Plate compactor, vibratory, over 90 kg | hr | 10 | | |
| 8 | Rammer, mechanical, over 60 kg | hr | 10 | | |
| 9 | Water pump with hoses, clear water 4 inch | hr | 6 | | |
| 10 | Concrete mixer, 200 ltr (10/7) | hr | 6 | | |
| 11 | Welding set, electric, 300 - 400 amp | hr | 6 | | |
| 12 | Porker Vibrator, petrol driven | hr | 10 | | |
| Equipment Day works carried to Summary | | | | | |

SECTION 9
SCHEDULES

REFERENCE ONLY

Schedule 1- General Information

For Joint Venture partners, each partner shall furnish information separately

| ITB Clause Reference | Description | Information To be filled by Bidder | Remarks |
|--|--|---|---|
| 3.1 | CIDA Registration | | Provide certified copies and label as attachment to Clause 3.1 |
| | Registration Number | | |
| | Grade | | |
| | Specialty | | |
| | Expiry Date | | |
| | Number | | |
| | Expiry Date | | |
| 4.1(a) | Legal Status | | Provide certified copies of registration |
| | Written power of attorney to the signatory to the bid (bids signed by other than the authorized person, shall be rejected) | Provide original or certified copy of the power of attorney attested by a Notary and label as attachment to Clause 4.1(a) | |
| | If a Joint Venture, names and addresses of Joint Venture partners | 1..... | Provide draft copy of Joint Venture agreement |
| | | 2..... | |
| | | 3..... | |
| | If a Joint Venture, name of the Lead Partner | | |
| For Joint Ventures, each JV partner shall furnish legal status separately | | | |
| | Name (lead partner) | | Provide certified copies and label as attachment to Clause 4.1(a) |
| | Legal status | | |
| | Place of registration | | |
| | Principal place of business | | |
| | Written power of attorney of the signatory to the Bid | Provide original or certified copy of the power of attorney attested by a Notary and label as attachment to Clause 5.1 | |
| | VAT Registration No. | | |
| | Name (Partner 2) | | Provide certified copies and label as attachment to Clause 4.1(a) |
| | Legal status | | |
| | Place of registration | | |
| | Principal place of business | | |
| | Written power of attorney of the signatory to the Bid | Provide original or certified copy of the power of attorney attested by a Notary and label as attachment to Clause 5.1 | |

| | | |
|--|---|--|
| | VAT Registration No. | |
| | Name (Partner 3) | Provide certified copies and label as attachment to Clause 4.1(a) |
| | Legal status | |
| | Place of registration | |
| | Principal place of business | |
| | Written power of attorney of the signatory to the Bid | Provide original or certified copy of the power of attorney attested by a Notary and label as attachment to Clause 5.1 |
| | VAT Registration No. | |

| Schedule 2 – Annual Turnover Information | | |
|---|-----------------|--|
| For Joint Ventures each partner shall submit the information separately | | |
| Year | Turnover | Remarks |
| 1 | | Attach audited reports and label as attachment to Clause 4.2 |
| 2 | | |
| 3 | | |
| 4 | | |
| 5 | | |

| Schedule 3 – Adequacy of Working Capital | | |
|---|---------------|--|
| Source of Credit Line | Amount | Remarks |
| | | Provide documentary evidence and label as attachment to Clause 4.2 |
| | | |
| | | |
| Total | | |

| Schedule 4 - Financial Data (As per Latest Audited Financial Statement) | | 2021/2022 or latest |
|--|---------------------------------------|---------------------|
| 1 | Current Assets | |
| 2 | Current Liabilities | |
| 3 | Working Capital(1-2) | |
| 4 | Works in hand | |
| 5 | Line of credit** | |
| 6 | Available Liquid Asset {3-(0.1)x4+5}* | |

* This amount shall be not less than the amount given in clause 4.2 of ITB.

** Line of credit if provided shall strictly be as per Form No. 07 provided.

*** *Bidder available working capital should be equal to the 50% of minimum amount of liquid assets.(i.e Rs 51.0 Mn) Line of credit shall be provided only to satisfy balance amount of liquid assets*

| Schedule 5 – Construction Experience in last five years | | | | |
|--|----------|----------------------|--------|--------------------------------|
| For JVs each JV partner shall furnish information separately | | | | |
| Year | Employer | Description of Works | Amount | Contractors Responsibility (%) |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

| Schedule 6 – Major Items of Construction Equipment Proposed | | |
|--|----------|--------------------|
| Type | Capacity | Own, Lease or hire |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| Schedule 7 – Construction Management Staff | | |
|---|----------|------|
| A: Key Professional | | |
| Name | Position | Task |
| | | |
| | | |
| | | |
| B: Support Staff | | |
| Name | Position | Task |
| | | |
| | | |
| | | |

REFERENCE ONLY

Schedule 8 – Time Schedule for Key Staff

| Months (in the form of a Bar Chart) | | | | | | | | | | | | | Number of Months | | |
|-------------------------------------|----------|------------|---|---|---|---|---|---|---|---|---|----|------------------|----|----|
| Name | Position | Activities | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | | 11 | 12 |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |

Full Time:- _____ Part Time:-.....

Schedule No. 09 (a)

Non-Performance Contracts – Notice to Correct Issued

[The following table shall be filled in for the bidder and for each partner of a Joint Venture]

Date: _____
 Contract No.: _____
 Bidder’s Legal Name: _____
 Page _____ of _____

1. History of Non Performing Contracts – Notice to Correct Issued

| Non-Performing Contracts | | | |
|---|---------------------------------------|--|-----------------------------|
| <p>Choose one of the following</p> <p><input type="checkbox"/> Notice to Correct on the poor performance or similar notice as per the relevant COC, which is enforced prior to 05/04/2023 had not been issued as specified in Section II, Bidding Data, sub clause 4.2 (h)</p> <p><input type="checkbox"/> Notice to Correct on the poor performance or similar notice as per the relevant COC, which is enforced prior to 05/04/2023 has been issued as specified in Section II, Bidding Data, sub clause 4.2 (h)</p> | | | |
| Year | Non Performed Portion of Contract | Contract Identification | Total Contract Amount (LKR) |
| <i>[insert year]</i> | <i>[insert amount and percentage]</i> | Contract Identification: <i>[indicate complete contract name, number, and any other identification]</i> Name of Employer: <i>[insert full name]</i> Address of Employer: <i>[insert street/city/country]</i> Reason(s) for Notice to Correct: <i>[indicate main reason(s), attach copy of Notice to Correct]</i> Whether Remedies taken: (Yes/No) (If yes, attach Engineer’s certificate) Current Status of Contract: <i>(indicate completed/ongoing/referred to dispute resolution mechanism etc)</i> | <i>[insert amount]</i> |

.....
 Signature of the Bidder

The foregoing non performing contracts listed in schedule no. 09 (a) having been duly read over and explained by me to the Affirmant and he having understood the contents of same, signed before me at
[Place], on this 2023 *[date]*

.....
 Attorney at Law

Note – if does not provide all non performing contracts shall be treated as non - responsive according to the clause 3.3 of ITB

Schedule No. 09 (b)
Non-Performance Contracts – Terminated

[The following table shall be filled in for the bidder and for each partner of a Joint Venture]

Date: _____
 Contract No.: _____
 Bidder's Legal Name: _____
 Bidder's Party Legal Name: _____

1. History of Non Performing Contracts – Terminated Contracts

| Non-Performing Contracts | | | |
|--|--|---|-----------------------------|
| <p>Choose one of the following</p> <p><input type="checkbox"/> Termination of contracts due to the Contractor's default did not occur within last five (5) years prior to 05/04/2023 specified in Section II, Bidding Data, sub clause 4.2 (h)</p> <p><input type="checkbox"/> Termination of Contracts due to the Contractor's default occurred within last five (5) years prior to 05/04/2023 specified in Section II, Bidding Data, sub clause 4.2 (h)</p> | | | |
| Year | Non Performed Portion of Contract (Rs) | Contract Identification | Total Contract Amount (LKR) |
| <i>[insert year]</i> | <i>[insert amount and percentage]</i> | Contract Identification: <i>[indicate complete contract name, number, and any other identification]</i> Name of Employer: <i>[insert full name]</i> Address of Employer: <i>[insert street/city/country]</i> Reason(s) for non-performance/termination: <i>[indicate main reason(s), attach relevant details]</i> Current Status of Contract: <i>(indicate completed/ongoing/ referred to dispute resolution)</i> | <i>[insert amount]</i> |

.....
 Signature of the Bidder

The foregoing non performing contracts listed in schedule no. 09 (b) having been duly read over and explained by me to the Affirmant and he having understood the contents of same, signed before me at
[Place], on this 2023 *[date]*

.....
 Attorney at Law

Note – if does not provide all non performing contracts shall be treated as non - responsive according to the clause 3.3 of ITB

**Schedule No. 10
Pending Litigation and Arbitration**

Each Bidder must fill out this form if so required under Criterion 4.2 (i) of Section 2, Bidding Data to describe any pending litigation or arbitration formally commenced against it.

In case of a Joint Venture, each Joint Venture Partner must fill out this form separately and provide the Joint Venture Partner's name below:

Joint Venture Partner: _____

| Pending Litigation and Arbitration | | | | |
|--|-------------------|------------------------------------|---|-----------------------|
| Choose one of the following | | | | |
| <input type="checkbox"/> No Pending Litigation and Arbitration in accordance with section II, Bidding Data, sub clause 4.2 (i) | | | | |
| <input type="checkbox"/> Below is a description of all pending litigation and arbitration in accordance with section II, Bidding Data, sub clause 4.2 (i) | | | | |
| Year of Dispute | Amount of Dispute | Outcome as percentage of Net worth | Contract Identification | Total Contract Amount |
| | | | Contract Identification (<i>insert contract name, number and any other identification</i>) Name of Employer (<i>insert full name</i>) Address of Employer (<i>insert street, city, town</i>) Matter in dispute (<i>indicate main issues in dispute</i>) Status of dispute (<i>indicate if it is being treated by the adjudicator, under arbitration or being dealt with by the judiciary</i>) | |

.....
Signature of the Bidder

The foregoing details in the schedule no. 10 having been duly read over and explained by me to the Affirmant and he having understood the contents of same, signed before me at [Place], on this 2023 [date]

.....
Attorney at Law

Note – if does not provide all pending litigation arbitration shall be treated as non responsive according to the clause 3.3 of ITB

Schedule 11 – work Programme

(1st, 2nd etc. are months from the Start Date)

Construction Activity1st2nd3rd4th5th6th7th8th9th10th11th12th

SECTION – 11

STANDARD FORMS (BID)

FORM NO. 06: Form of Bid Security

FORM NO. 07: Form for the Affidavit for the Current Contractual Commitments

FORM NO. 08: For Letter from the Bank for Granting of A Revolving Line of Credit

REFERENCE ONLY

FORM OF BID SECURITY

[this Guarantee form shall be filled in accordance with the instructions indicated in brackets]

.....[insert issuing agency's name, and address of issuing branch or office]

Beneficiary: Director General, Road Development Authority, "MagaNeguma Mahamedura" 216, Denzil Kobbekaduwa mawatha, Battaramulla, Sri Lanka.

Date:[insert (by issuing agency) date]

BID GUARANTEE No.:[insert (by issuing agency) number]

We have been informed thatinsert (by issuing agency) name of the Bidder] (hereinafter called "the Bidder") has submitted to you its bid dated [insert (by issuing agency) date] (hereinafter called "the Bid") for the execution of '**CONSTRUCTION OF RAJAMAWATHA EXTENTION ROAD FROM KETAWALA TO MASPANNA (FROM CH 7+560km TO CH 9+300 km), INCLUDING TWO BRIDGES AT CH 7+960 km AND CH 8+380 km** ' under Contract No: **RDA/DC/UVA/FD/GOSL/2023/02**

Furthermore, we understand that, according to your conditions, Bids must be supported by a Bid Guarantee.

At the request of the Bidder, we[insert name of issuing agency] hereby irrevocably undertake to pay you any sum or sums not exceeding in total an amount of[insert amount in figures][insert amount in words] upon receipt by us of your first demand in writing accompanied by a written statement stating that Bidder is in breach of its obligation(s) under the bid conditions, because the Bidder:

- i. has withdrawn its Bid during the period of bid validity specified; or
- ii. does not accept the correction of errors in accordance with the Instruction to Bidders (hereinafter "the ITB") of the IFB or
- iii. having been notified of the acceptance of its Bid by the Employer during the period of bid validity,
 - (i) fails or refuses to execute the Contract Form, if required, or
 - (ii) fails or refuses to furnish the Performance Security, in accordance with the ITB.

This Guarantee shall expire:

- (a) if the Bidder is the successful bidder, upon our receipt of copies of the Contract signed by the Bidder and of the Performance Security issued to you by the Bidder; or
- (b) if the Bidder is not successful bidder, upon the earlier of the successful bidder furnishing the performance security, otherwise it will remain in force up to(insert date)

Consequently, any demand for payment under this Guarantee must be received by us at the office on or before that date.

Signature and the Seal of the Guarantor:

Name of the Organization

Date:

Witness:

Note: Any bid security which has deviated from this bid Security format shall be considered as non responsive

FORM FOR THE AFFIDAVIT FOR THE CURRENT CONTRACTUAL COMMITMENTS

Director General,
Road Development Authority

In accordance with the Clause 4.2 of the Instructions to Bidders, I (We) declare that the outstanding Contract Commitments of (Name of the Bidder (s)) is as follows. I (We) further declare that all the outstanding contract commitments are listed below.

| Specialty | Name of the Contract | Name of the Client | Initial Contract Amount (Rs.) | Outstanding Work (Rs.) |
|--------------|----------------------|--------------------|-------------------------------|------------------------|
| Highways* | | | | |
| | | | | |
| | | | | |
| Bridges* | | | | |
| | | | | |
| | | | | |
| Buildings* | | | | |
| | | | | |
| | | | | |
| Irrigation* | | | | |
| | | | | |
| | | | | |
| # | | | | |
| | | | | |
| | | | | |
| Total | | | | |

.....

Signature of the Bidder

The foregoing Affidavit having been duly read over and explained by me to the Affirmant and he having understood the contents of same, signed before me at [Place], on this 2023 [date]

.....

Justice of The Peace

* Add additional rows to include all the current projects if needed

Add additional speciality to include all the current projects

Note – if does not provide all contract commitment shall be treated as non responsive according to the clause 3.3 of ITB

**FOR LETTER FROM THE BANK FOR GRANTING
OF A REVOLVING LINE OF CREDIT**

FROM:

.....

.....

.....

TO : Director General,
Road Development Authority (RDA)
“MagaNeguma Mahamedura ”
216, Denzil Kobbekaduwa mawatha,
Battaramulla
Sri Lanka

SUB : Letter from the Bank for providing a line of credit in favour
of (1) in case of award to them of works for the
Contract of execute ‘**CONSTRUCTION OF RAJAMAWATHA
EXTENTION ROAD FROM KETAWALA TO MASPANNA
(FROM CH 7+560km TO CH 9+300 km), INCLUDING TWO
BRIDGES AT CH 7+960 km AND CH 8+380 km**’, under contract No:
RDA/DC/UVA/FD/GOSL/2023/02

Dear Sir,

We (2)bankers of (3)hereby agree to grant
revolving line of credit for an amount of Sri Lanka Rupees for the purpose of the
execution of the Civil Work Contracts under the Contract of execute ‘**CONSTRUCTION OF
RAJAMAWATHA EXTENTION ROAD FROM KETAWALA TO MASPANNA
(FROM CH 7+560km TO CH 9+300 km), INCLUDING TWO BRIDGES AT CH
7+960 km AND CH 8+380 km**’Contract No: **RDA/DC/UVA/FD/GOSL/2023/02** revolving line of
credit will be maintained until the works are taken over by the RDA.

Signature and the Seal of the Guarantor:

Name of the Organization

Date:

Witness:

Notes

(1) Name of Beneficiary / Bidder

(2) Name of Bank

(3) Name of Beneficiary / Bidder

(4) **No conditional line of credit will be accepted and any letter of line of credit, which has deviated from the specimen format, shall be treated as non – responsive.**

SECTION – 10

DRAWINGS

REFERENCE ONLY



**GOVERNMENT OF DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS**



ROAD DEVELOPMENT AUTHORITY


**CONSTRUCTION OF BRIDGE ACROSS BOGAHAKUBURA ELA ON
HALIELA KETAWALA TO KANDY RAJA MAWATHA.**

DETAILED DESIGN DRAWINGS

MARCH 2023

**Design Office (Central Province)
Road Development Authority
06B, Samagi Niwasa, Gannoruwa Road
Peradeniya.**

| LEGEND | |
|--------|----------------------|
| | CENTER LINE |
| | EDGE OF CARRIAGEWAY |
| | EDGE OF SHOULDER |
| | FINISHED GROUND LINE |
| | EXISTING GROUND LINE |
| | FLOW DIRECTION |
| | CONTROL POINTS |



Center Line & TBM Co-ordinates

| Station | Northing | Easting |
|----------|------------|------------|
| 0+000.00 | 915.6450 | 1,001.5680 |
| 0+010.00 | 925.5718 | 1,000.3605 |
| 0+020.00 | 935.5169 | 999.3460 |
| 0+030.00 | 945.4968 | 999.7629 |
| 0+040.00 | 955.2718 | 1,001.8175 |
| 0+050.00 | 964.6306 | 1,005.3171 |
| 0+060.00 | 973.3220 | 1,010.2447 |
| 0+070.00 | 981.7779 | 1,015.5831 |
| 0+080.00 | 990.8741 | 1,019.2631 |
| 0+090.00 | 999.3554 | 1,014.6844 |
| 0+100.00 | 1,005.5719 | 1,006.8515 |
| 0+110.00 | 1,011.7863 | 999.0168 |
| 0+120.00 | 1,014.1913 | 989.5831 |
| 0+130.00 | 1,011.7768 | 979.8809 |
| 0+140.00 | 1,009.3016 | 970.1921 |
| 0+150.00 | 1,006.8264 | 960.5032 |
| 0+160.00 | 1,005.3895 | 950.6368 |
| 0+165.42 | 1,005.5440 | 945.2230 |

| | Northing | Easting |
|-------|-----------|----------|
| TBM 1 | 1000.000 | 1000.000 |
| TBM 2 | 21009.167 | 983.430 |
| TBM 3 | 31016.776 | 1021.031 |
| TBM 4 | 41000.293 | 1012.796 |
| TBM 5 | 51006.018 | 938.992 |
| TBM 6 | 61007.740 | 942.502 |
| TBM 7 | 71018.864 | 973.522 |
| TBM 8 | 81008.847 | 1032.035 |
| TBM 9 | 9963.129 | 996.443 |

PLAN

SCALE 1:500

CONSTRUCTION OF BRIDGE ACROSS BOGAHAKUBURA ELA ON HALIELA KETAWALA TO KANDY RAJA MAWATHA

LAYOUT PLAN SCALE -


| REV | DESCRIPTION | BY | DATE |
|-----|--------------|-----|------------|
| 00 | TENDER ISSUE | MDA | 16-08-2021 |
| | | | |
| | | | |
| | | | |
| | | | |

DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS


DESIGN OFFICE (C.P.),
ROAD DEVELOPMENT AUTHORITY
06B, SAMAGI NIWASA, GANNORUWA RD, PERADENIYA
TEL : 812388997 FAX : 0812388997 email : docpkandy@gmail.com

| | | |
|---|--|---|
| SURVEYED & PLOTTED : | DESIGNED : ATHULA LIYANAGE <i>A</i> | DRAWN : H.A.D. PADMIKA <i>D</i> |
| A.C.E. (DESIGN) : SUDEERA KUMARA ARACHCHI <i>A</i> | A.D.D. (DESIGN) : L.V.S. WEERAHOON <i>A</i> | CHECKED : SUDEERA KUMARA ARACHCHI <i>A</i> |
| DATE : 16-08-2021 | | DRG No. : DD/D/CP/UVA/B/1265/1(11) |

| LEGEND | |
|--------|----------------------|
| | CENTER LINE |
| | EDGE OF CARRIAGEWAY |
| | EDGE OF SHOULDER |
| | FINISHED GROUND LINE |
| | EXISTING GROUND LINE |
| | FLOW DIRECTION |
| | CONTROL POINTS |



PLAN
SCALE 1:500



| CHAINAGE | Ch0+030 | Ch0+040 | Ch0+050 | Ch0+060 | Ch0+070 | Ch0+080 | Ch0+090 | Ch0+100 | Ch0+110 | Ch0+120 | Ch0+130 | Ch0+140 | Ch0+150 | Ch0+160 |
|-----------------------|---------------------------------|---------|---------------------------------|---------|---------------------------------|---------|---------|---------------------------------|------------------------|---------------------------------|----------|---------|---------|---------|
| FINISHED GROUND LEVEL | 103.629 | 102.892 | 102.174 | 101.691 | 101.503 | 101.500 | 101.500 | 101.500 | 101.500 | 101.597 | 102.281 | 103.521 | 104.829 | 106.137 |
| EXISTING GROUND LEVEL | 103.635 | 102.852 | 103.712 | 101.822 | 100.638 | 100.373 | 97.565 | 95.876 | 98.163 | 102.154 | 103.013 | 103.275 | 104.779 | 106.209 |
| HORIZONTAL GEOMETRY | R=60.45 0+015.16 0+042.43 | | R=58.42 0+043.83 0+057.44 | | R=10.50 0+073.86 0+089.22 | | | R=12.50 0+109.73 0+121.25 | | R=35.97 0+151.29 0+161.53 | | | | |
| VERTICAL GEOMETRY | G=-7.37% | | V.C.L.=25.00 K=3.39 | | | G=0.00% | | | V.C.L.=20.00 K=1.53 | | G=13.08% | | | |

ELEVATION
SCALE 1:500

CONSTRUCTION OF BRIDGE ACROSS BOGAHAKUBURA ELA ON HALIELA KETAWALA TO KANDY RAJA MAWATHA

PLAN AND PROFILE

SCALE -

| REV | DESCRIPTION | BY | DATE |
|-----|--------------|-----|------------|
| 00 | TENDER ISSUE | RDA | 16-08-2021 |



DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS

SURVEYED & PLOTTED :

DESIGNED :
ATHULA LIYANAGE

DRAWN :
H.A.D. PADMIKA

A.C.E. (DESIGN) :
SUDEERA KUMARA ARACHCHI


A.D.D. (DESIGN) :
L.V.S. WEERAKOON

CHECKED :
SUDEERA KUMARA ARACHCHI

DATE : 16-08-2021
DRG.No. : DD/D/CP/UVA/B/1265/2(11)




DESIGN OFFICE (C.P.),
ROAD DEVELOPMENT AUTHORITY
06B, SAMAGI NIWASA, GANNORUWA RD, PERADENIYA
TEL : 81238897 FAX : 081238897 email : docpkandy@gmail.com



ELEVATION
SCALE - 1 : 150

SECTIONAL ELEVATION A - A
SCALE - 1 : 150



PLAN
SCALE - 1 : 150

- NOTE:**
- ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE STATED.
 - DIMENSIONS SHALL NOT BE OBTAIN BY SCALEING.
 - ALL WORKMANSHIP AND MATERIALS ARE TO BE ACCORDANCE WITH THE REQUIREMENT OF THE SPECIFICATION AND BY LAWS OF THE AUTHORITY.
 - WEEP HOLES TO BE PROVIDED AT 1.2 m C/C STAGGERED USING 110 mm DIA.TYPE 600 PVC PIPES.
 - ADDITIONAL WEEP HOLES ARE TO BE PROVIDED IF NECESSARY TO SUIT SITE CONDITION.
 - A CLAY PUDDLE OF 300 X 600 TO BE PROVIDED THROUGH OUT THE LENGTH OF THE ABUTMENTS AND WING WALLS TO DIVERT THE WATER COLLECTING BEHIND.
 - ALL BAR MARKED "T" SHALL BE HIGH YIELD DEFORMED BARS OF YIELD STRENGTH NOT LESS THAN 460 N/mm² AND ALL MARKED "R" SHALL BE HOT ROLLED MILD STEEL PLAIN BARS OF YIELD STRENGTH NOT LESS THAN 250 N/mm².
 - BARS OF CUT LENGTH LARGER THAN THE SUPPLIED LENGTH TO BE LAPPED WITH LENGTH OF 50 Ø, WHERE Ø IS THE DIAMETER AND LAPPING SHOULD BE STAGGERED.
 - CLEAR CONCRETE COVER FOR REINFORCEMENT SHOULD BE 50 mm UNLESS OTHERWISE SPECIFIED.
 - REINFORCEMENT BARS SHALL BE BENT ACCORDANCE WITH STANDARD SPECIFICATIONS.
 - DOWEL TO BE PROVIDED ONLY IF REQUIRE AS PER SITE CONDITION AND SUBJECTED TO ENGINEER APPROVAL
 - SCREED CONCRETE IS USED ONLY IN ABSENT OF ROCK SURFACE.
 - ALLOWABLE BEARING STRENGTH UNDER THE FOUNDATION SHOULD NOT BE LESS THAN 250kN/m².

GRADES OF CONCRETE

| ABUTMENTS & WING WALLS | MASS | RC/PIER |
|------------------------|---------------|--------------|
| 1. SCREED | -GRADE 15(40) | GRADE 15(40) |
| 2. BASE | -GRADE 30(20) | GRADE 30(20) |
| 3. STEM | -GRADE 15(40) | GRADE 30(20) |
| 4. POCKET FILL | -GRADE 30(20) | GRADE 30(20) |
| OTHER | | |
| 1. DECK | -GRADE 40(20) | |
| 2. FOOT WALK | -GRADE 30(20) | |
| 3. APPROACH SLAB | -GRADE 30(20) | |

CONSTRUCTION OF BRIDGE ACROSS BOGAHAKUBURA ELA ON HALIELA KETAWALA TO KANDY RAJA MAWATHA

PLAN AND ELEVATION


SCALE -

| REV | DESCRIPTION | BY | DATE |
|-----|--------------|-----|------------|
| 00 | TENDER ISSUE | RDA | 16-08-2021 |

DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS

| | | | |
|--|---|-------------------------------------|---|
| SURVEYED & PLOTTED : | DESIGNED : ATHULA LIYANAGE <i>A</i> | DRAWN : H.A.D. PADMIKA <i>du</i> | CHECKED : SUDEERA KUMARA ARACHCHI <i>A</i> |
| A.C.E. (DESIGN): SUDEERA KUMARA ARACHCHI <i>A</i> | A.D.D. (DESIGN): L.V.S. WEERAKOON <i>A</i> | | DATE : 16-08-2021 |
| | | | DRG.No. : DD/D/CP/UVA/B/1265/3(11) |

DESIGN OFFICE (C.P.),
ROAD DEVELOPMENT AUTHORITY
06B, SAMAGI NIWASA, GANNORUWA RD, PERADENIYA
TEL : 812388997 FAX : 0812388997 email : docpkandy@gmail.com



| POINT | EAST (X) | NORTH(Y) |
|-------|-----------|-----------|
| A1 | 1014.5306 | 999.4775 |
| A1-1 | 1017.2808 | 1004.2779 |
| A1-2 | 1013.8804 | 999.9934 |
| A1-3 | 1010.4725 | 995.6994 |
| A1-4 | 1011.1478 | 989.8294 |
| A1-5 | 1014.2275 | 990.1838 |
| A1-6 | 1013.7636 | 994.2161 |
| A1-7 | 1016.5362 | 997.7095 |
| A1-8 | 1019.4727 | 1001.4096 |
| A1-9 | 1023.5051 | 1001.8736 |
| A1-10 | 1023.1507 | 1004.9532 |

| POINT | EAST (X) | NORTH(Y) |
|-------|-----------|-----------|
| P | 1007.2499 | 1005.2557 |
| P-1 | 1009.6907 | 1010.1811 |
| P-2 | 1006.3491 | 1005.9706 |
| P-3 | 1003.0075 | 1001.7602 |
| P-4 | 1004.8091 | 1000.3304 |
| P-5 | 1008.1507 | 1004.5408 |
| P-6 | 1011.4922 | 1008.7513 |


| POINT | EAST (X) | NORTH(Y) |
|-------|-----------|-----------|
| A2 | 999.9888 | 1011.0185 |
| A2-1 | 1004.0392 | 1014.7870 |
| A2-2 | 1000.6389 | 1010.5025 |
| A2-3 | 997.2310 | 1006.2085 |
| A2-4 | 991.3610 | 1005.5331 |
| A2-5 | 991.0067 | 1008.6128 |
| A2-6 | 995.0390 | 1009.0768 |
| A2-7 | 997.8254 | 1012.5877 |
| A2-8 | 1000.7481 | 1016.2703 |
| A2-9 | 1000.2842 | 1020.3026 |
| A2-10 | 1003.3639 | 1020.6569 |


CONSTRUCTION OF BRIDGE ACROSS BOGAHAKUBURA ELA ON HALIELA KETAWALA TO KANDY RAJA MAWATHA

DETAIL OF SETTING OUT


SCALE -

| REV | DESCRIPTION | BY | DATE |
|-----|--------------|-----|------------|
| 00 | TENDER ISSUE | IDA | 16-08-2021 |
| | | | |
| | | | |
| | | | |


| | | | |
|--|--|--|--|
|  <p>DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA MINISTRY OF HIGHWAYS</p> | |  <p>DESIGN OFFICE (C.P.), ROAD DEVELOPMENT AUTHORITY 06B, SAMAGI NIWASA GANNORUWA RD, PERADENIYA TEL : 812388997 FAX : 0812388997 email : docpkandy@gmail.com</p> | |
| SURVEYED & PLOTTED : | | DESIGNED : ATHULA LIYANAGE | |
| A.C.E. (DESIGN) : SUDEERA KUMARA ARACHCHI | | DRAWN : H.A.D. PADMIKA | |
| A.D.D. (DESIGN) : L.V.S. WEERAKOON | | CHECKED : SUDEERA KUMARA ARACHCHI | |
| | | DATE : 16-08-2021 DRG.No. : DD/D/CP/UVA/B/1265/4(11) | |



RB
RIGHT BANK



M.S Dowels 20mm Ø 1000mm long,
1200mm C/C Staggered



LB
LEFT BANK

DETAIL OF DOWEL ARRANGEMENT
SCALE 1:100

CONSTRUCTION OF BRIDGE ACROSS BOGAHAKUBURA ELA
ON HALIELA KETAWALA TO KANDY RAJA MAWATHA

| REV | DESCRIPTION | BY | DATE |
|-----|--------------|-----|------------|
| 00 | TENDER ISSUE | RDA | 16-08-2021 |
| | | | |
| | | | |
| | | | |
| | | | |



DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS



DESIGN OFFICE (C.P.),
ROAD DEVELOPMENT AUTHORITY
06B, SAMAGI NIWASA, GANNORUWA RD, PERADENIYA
TEL : 812388997 FAX : 0812388997 email : docpkandy@gmail.com

SURVEYED & PLOTTED :

DESIGNED :
ATHULA LIYANAGE

DRAWN :
H.A.D. PADMIKA

CHECKED :
SUDEERA KUMARA ARACHCHI


A.C.E. (DESIGN):
SUDEERA KUMARA ARACHCHI

A.D.D. (DESIGN):
L.V.S. WEERAKOON

DATE : 16-08-2021
DRG.No. : DD/D/CP/UVA/B/1265/5(11)

DETAIL OF DOWEL ARRANGEMENT



SCALE -




ABUTMENT & WING WALL PLAN
SCALE - 1 : 100

**CONSTRUCTION OF BRIDGE ACROSS BOGAHAKUBURA ELA
ON HALIELA KETAWALA TO KANDY RAJA MAWATHA**


| REV | DESCRIPTION | BY | DATE |
|-----|--------------|-----|------------|
| 00 | TENDER ISSUE | RDA | 16-08-2021 |
| | | | |
| | | | |
| | | | |

| | | |
|---|---|--|
|  DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA MINISTRY OF HIGHWAYS | |  DESIGN OFFICE (C.P.), ROAD DEVELOPMENT AUTHORITY 06B, SAMAGI NIWASA, GANNORUWA RD, PERADENIYA TEL : 812388997 FAX : 0812388997 email : docpkandy@gmail.com |
| SURVEYED & PLOTTED : A.C.E. (DESIGN) : SUDEERA KUMARA ARACHCHI | DESIGNED : ATHULA LIYANAGE A.D.D. (DESIGN) : L.V.S. WEERAKOON | DRAWN : H.A.D. PADMIKA |
| CHECKED : SUDEERA KUMARA ARACHCHI | | DATE : 16-08-2021 DRG.No. : DD/D/CPI/UVA/B/1265/6(11) |


DETAIL OF ABUTMENT AND WING WALL PLAN SCALE -




**SECTION OF C-C
(KOBAGATIYA END)**
SCALE 1:75




**SECTION OF D-D
(KOBAGATIYA END)**
SCALE 1:75




DETAILS OF CAPPING BEAM
SCALE- 1:25



**SECTION OF D-D
(DALUKKELLA END)**
SCALE 1:75



**SECTION OF C-C
(DALUKKELLA END)**
SCALE 1:75





DETAILS OF CURTAIN WALL
SCALE- 1:25


CONSTRUCTION OF BRIDGE ACROSS BOGAHAKUBURA ELA ON HALIELA KETAWALA TO KANDY RAJA MAWATHA

DETAIL OF SECTION


SCALE -

| REV | DESCRIPTION | BY | DATE |
|-----|--------------|-----|------------|
| 00 | TENDER ISSUE | IDA | 16-08-2021 |
| | | | |
| | | | |


| | | |
|---|---|--|
|  DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA MINISTRY OF HIGHWAYS | |  DESIGN OFFICE (C.P.), ROAD DEVELOPMENT AUTHORITY 06B, SAMAGI NIWASA, GANNORUWA RD, PERADENIYA TEL: 812388997 FAX: 0812388997 email: docpkandy@gmail.com |
| SURVEYED & PLOTTED : A.C.E. (DESIGN): SUDEERA KUMARA ARACHCHI | DESIGNED : ATHULA LIYANAGE A.D.D. (DESIGN): L.V.S. WEERAKOON | |
| | | CHECKED : SUDEERA KUMARA ARACHCHI |
| | | DATE : 16-08-2021 DRG.No. : DD/D/CPI/UVA/B/1265/7(11) |




R/F DETAIL OF BASE
SCALE - 1:100



R/F DETAILS OF CAPPING BEAM
SCALE 1:25



DETAIL OF BEARING SEAT
SCALE - 1:10






R/F DETAILS OF CURTAIN WALL
SCALE- 1:20

CONSTRUCTION OF BRIDGE ACROSS BOGAHAKUBURA ELA ON HALIELA KETAWALA TO KANDY RAJA MAWATHA


R/F DETAIL OF BASE AND CAPPING BEAM, CURTAIN WALL, BEARING SEAT SCALE -

| REV | DESCRIPTION | BY | DATE |
|-----|--------------|-----|------------|
| 00 | TENDER ISSUE | RDA | 16-08-2021 |
| | | | |
| | | | |
| | | | |


| | | | |
|---|-----------------------------------|--|--------------------------------------|
|  DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA MINISTRY OF HIGHWAYS | |  DESIGN OFFICE (C.P.), ROAD DEVELOPMENT AUTHORITY 06B, SAMAGI NIWASA GANNORUWA RD, PERADENIYA TEL : 812388997 FAX : 0812388997 email : docpkandy@gmail.com | |
| SURVEYED & PLOTTED : A.C.E. (DESIGN): SUDEERA KUMARA ARACHCHI | DESIGNED : ATHULA LIYANAGE | DRAWN : H.A.D. PADMIKA | CHECKED : SUDEERA KUMARA ARACHCHI |
| A.C.E. (DESIGN): SUDEERA KUMARA ARACHCHI | A.D.D. (DESIGN): L.V.S. WEERAKOON | DATE: 16-08-2021 | DRG.No. : DD/D/CP/UVA/B/1265/8(11) |




SECTION G - G
SCALE - 1 : 75



ELEVATION
SCALE - 1 : 75



DETAILS OF PIER CAPPING
SCALE 1:20



PLAN
SCALE - 1 : 75

CONSTRUCTION OF BRIDGE ACROSS BOGAHAKUBURA ELA ON HALIELA KETAWALA TO KANDY RAJA MAWATHA

DETAIL OF PIER

SCALE -

| REV | DESCRIPTION | BY | DATE |
|-----|--------------|-----|------------|
| 00 | TENDER ISSUE | RDA | 16-08-2021 |
| | | | |
| | | | |
| | | | |



DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS



DESIGN OFFICE (C.P.),
ROAD DEVELOPMENT AUTHORITY
06B, SAMAGI NIWASA GANNORUWA RD, PERADENIYA
TEL : 812388997 FAX : 0812388997 email : docpkandy@gmail.com

SURVEYED & PLOTTED :

DESIGNED :
ATHULA LIYANAGE

DRAWN :
H.A.D. PADMIKA


CHECKED :
SUDEERA KUMARA ARACHCHI

A.C.E. (DESIGN) :
SUDEERA KUMARA ARACHCHI


A.D.D. (DESIGN) :
L.V.S. WEERAKOON

DATE : 16-08-2021


DRG.No. : DD/D/CP/UVA/B/1265/9(11)




DETAIL OF CURTAIN WALL
SCALE 1:50




SECTION P - P
SCALE - 1 : 50




R/F DETAIL OF PIER BEARING SEAT
SCALE - 1 : 20




SECTION N - N
SCALE - 1 : 75



R/F DETAIL OF PIER WALL
SCALE - 1 : 75



R/F DETAIL OF PIER BASE
SCALE - 1 : 75



SECTION OF K - K
SCALE 1:75

CONSTRUCTION OF BRIDGE ACROSS BOGAHAKUBURA ELA
ON HALIELA KETAWALA TO KANDY RAJA MAWATHA

R/F DETAIL OF PIER

SCALE

| REV | DESCRIPTION | BY | DATE |
|-----|--------------|-----|------------|
| 00 | TENDER ISSUE | RDA | 16-08-2021 |
| | | | |
| | | | |
| | | | |



DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS



DESIGN OFFICE (C.P.),
ROAD DEVELOPMENT AUTHORITY
06B, SAMAGI NIWASA, GANNORUWA RD, PERADENIYA
TEL : 812388997 FAX : 0812388997 email : docpkandy@gmail.com

SURVEYED & PLOTTED :

DESIGNED :
ATHULA LIYANAGE

DRAWN :
H.A.D. PADMIKA


CHECKED :
SUDEERA KUMARA ARACHCHI

A.C.E. (DESIGN) :
SUDEERA KUMARA ARACHCHI

A.D.D. (DESIGN) :
L.V.S. WEERA KOON

DATE : 16-08-2021

DRG.No. : DD/D/CP/UVA/B/1265/10(11)




GENERAL DETAILS.

REINFORCEMENT DETAILS.

CROSS SECTION OF 9 500 LONG DECK

1:30



PLAN DETAILS OF RAIN WATER CATCH PIT



SCALE 1:20

**CONSTRUCTION OF BRIDGE ACROSS BOGAHAKUBURA ELA
ON HALIELA KETAWALA TO KANDY RAJA MAWATHA**

DETAIL OF DECK

SCALE -

| REV | DESCRIPTION | BY | DATE |
|-----|--------------|----|------------|
| 00 | TENDER ISSUE | RD | 16-08-2021 |
| | | | |
| | | | |
| | | | |

| | | | |
|---|--|---|--------------------------------------|
|  DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA MINISTRY OF HIGHWAYS | |  DESIGN OFFICE (C.F.), ROAD DEVELOPMENT AUTHORITY 06B, SAMAGI NIWASA, GANNORUWA RD, PERADENIYA TEL : 812388997 FAX : 0812388997 email : docpkandy@gmail.com | |
| SURVEYED & PLOTTED : | | DESIGNED : ATHULA LIYANAGE | DRAWN : H.A.D. PADMIKA |
| A.C.E. (DESIGN) : SUDEERA KUMARA ARACHCHI | | A.D.D. (DESIGN) : L.V.S. WEERAKOON | CHECKED : SUDEERA KUMARA ARACHCHI |
| | | DATE : 16-08-2021 | |
| DRG.No. : DD/D/CP/UVA/B/1265/11(11) | | | |



**GOVERNMENT OF DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS**



ROAD DEVELOPMENT AUTHORITY

**ROAD – RAJAMAWATHA EXTENSION FROM KETAWALA TO MASPANNA ROAD,
LOCATION BRIDGE AT CH 08+380 Km**

DETAILED DESIGN DRAWINGS

MARCH 2023



**Design Office (Central Province)
Road Development Authority
06B, Samagi Niwasa, Gannoruwa Road
Peradeniya.**

| LEGEND | |
|--------|--|
| | CENTER LINE |
| | EDGE OF CARRIAGEWAY |
| | EXISTING GROUND PROFILE |
| | FLOW DIRECTION |
| | CONTROL POINTS |
| | CONTROL POINTS AND CENTER LINE COORDINATES |

TBM & Setting Out Co-ordinates

| TBM No. | Northing(m) | Easting(m) | Elevation(m) |
|---------|-------------|-------------|--------------|
| A1 | 4199898.540 | 6222857.995 | 544.016 |
| P1 | 4199885.250 | 6222855.461 | 544.016 |
| P2 | 4199871.972 | 6222852.842 | 544.016 |
| P3 | 4199858.695 | 6222850.266 | 544.016 |
| P4 | 4199845.417 | 6222847.691 | 544.016 |
| A2 | 4199832.126 | 6222845.113 | 544.016 |

| GPS No. | Northing(m) | Easting(m) | Elevation(m) |
|---------|-------------|------------|--------------|
| GPS10 | 500537.705 | 521675.481 | 472.341 |
| GPS11 | 500567.983 | 521637.493 | 472.521 |
| GPS12 | 500567.184 | 521599.942 | 472.319 |



| CHAINAGE | 8+320 | 8+330 | 8+340 | 8+350 | 8+360 | 8+370 | 8+380 | 8+390 | 8+400 | 8+410 | 8+420 | 8+430 | 8+440 | 8+450 |
|-----------------------|------------------------------|---------|------------------------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|
| FINISHED GROUND LEVEL | 547.636 | 546.657 | 545.669 | 544.906 | 544.369 | 544.075 | 544.016 | 544.016 | 544.016 | 544.016 | 544.016 | 544.016 | 544.016 | 544.016 |
| EXISTING GROUND LEVEL | 548.795 | 548.562 | 547.490 | 546.151 | 544.519 | 542.528 | 539.527 | 537.620 | 537.448 | 537.070 | 537.024 | 537.942 | 539.919 | 537.843 |
| HORIZONTAL GEOMETRY | R=18.00 8+353.84-8+377.41 | | | | | | | | | | | | | |
| VERTICAL GEOMETRY | G=-9.79% | | V.C.L.=40.00 K=4.08 | | | | | G=0.00% | | | | | | |

LONGITUDINAL SECTION

SCALE : HORIZONTAL 1: 500
VERTICAL 1: 100

ROAD-RAJAMAWATHA EXTENSION FROM KETAWALA TO MASPANNA ROAD, LOCATION BRIDGE AT CH 08+380 km

PLAN AND PROFILE

SCALE - 1:50

| REV | DESCRIPTION | BY | DATE |
|-----|--------------|-----|------------|
| 00 | TENDER ISSUE | RDA | 13.03.2023 |



DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS



DESIGN OFFICE (C.P.),
ROAD DEVELOPMENT AUTHORITY
06B, SAMAGI NIWASA, GANNORUWA RD, PERADENIYA
TEL : 0812388997 FAX : 0812388997 email : docp@rda.gov.lk

SURVEYED & PLOTTED :

DESIGNED :
K.P.R.H.RUPASINGHE

DRAWN :
JAGATH C RAJAPAKSE


CHECKED :
L.G.A. LIYANAGE

C.E. (DESIGN):
S. KUMARA ARACHCHI


A.D.D. (DESIGN):
L.V.S. WEERAKOON

DATE : 20-11-2014

DRG.No. : DD/D/CP/UVA/B/1262/01-11



BRIDGE ELEVATION
SCALE - 1:250



BRIDGE PLAN
SCALE - 1:250

ROAD-RAJAMAWATHA EXTENSION FROM KETAWALA TO MASPANNA ROAD, LOCATION BRIDGE AT CH 08+380 km

PLAN AND ELEVATION SCALE - 1:50

| REV | DESCRIPTION | BY | DATE |
|-----|--------------|-----|------------|
| 00 | TENDER ISSUE | RDA | 13 03 2023 |
| | | | |
| | | | |
| | | | |


DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS

SURVEYED & PLOTTED :
DESIGNED : K.P.R.H.RUPASINGHE
DRAWN : JAGATH C RAJAPAKSE


C.E. (DESIGN) : S. KUMARA ARACHCHI
A.D.D. (DESIGN) : L.V.S.WEERAKOON

DESIGN OFFICE (C.P.),
ROAD DEVELOPMENT AUTHORITY
06B, SAMAGI NIWASA, GANNORUWA RD, PERADENIYA
TEL : 0812388997 FAX : 0812388997 email : docp@rda.gov.lk

CHECKED : L.G.A. LIYANAGE
DATE : 20-11-2014
DRG.No. : DD/D/CP/UVA/B/1262/02-11



PIER ELEVATION
SCALE - 1:100



ABUTMENT ELEVATION
SCALE - 1:100
WEEP HOLES 1100 PVC WITH 1:10 SLOPE

ROAD-RAJAMAWATHA EXTENSION FROM KETAWALA TO MASPANNA ROAD, LOCATION BRIDGE AT CH 08+380 km

ABUTMENT AND PIER ELEVATION

SCALE - 1:50

| REV | DESCRIPTION | BY | DATE |
|-----|--------------|-----|------------|
| 00 | TENDER ISSUE | RDA | 13 03 2023 |
| | | | |
| | | | |
| | | | |
| | | | |



DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS



DESIGN OFFICE (C.P.),
ROAD DEVELOPMENT AUTHORITY
06B, SAMAGI NIWASA, GANNORUWA RD, PERADENIYA
TEL : 0812388997 FAX : 0812388997 email : docp@rda.gov.lk

SURVEYED & PLOTTED :

DESIGNED :
K.P.R.H.RUPASINGHE









DRAWN :
JAGATH C RAJAPAKSE *F. Ranga*

CHECKED :
L.G. A. LIYANAGE *A*

C.E (DESIGN) :
S. KUMARA ARACHCHI *A*

A.D.D (DESIGN)
L.V.S.WEERAKOON *A*

DATE : 20-11-2014
DRG.No. : DD/DJ/CP/UVA/B/1262/03-11



ROAD-RAJAMAWATHA EXTENSION FROM KETAWALA TO MASPANNA ROAD, LOCATION BRIDGE AT CH 08+380 km

DETAILS OF ABUTMENT, WINGWALL AND CAPPING BEAM

SCALE - 1:50

| REV | DESCRIPTION | BY | DATE |
|-----|--------------|-----|------------|
| 00 | TENDER ISSUE | RDA | 13.03.2023 |
| | | | |
| | | | |
| | | | |
| | | | |



DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS



DESIGN OFFICE (C.P.),
ROAD DEVELOPMENT AUTHORITY
06B, SAMAGI NIWASA, GANNORUWA RD, PERADENYA
TEL : 0812388997 FAX : 0812388997 email : docp@rda.gov.lk

SURVEYED & PLOTTED :

DESIGNED :
K.P.R.H.RUPASINGHE










DRAWN :
JAGATH C RAJAPAKSE

CHECKED :
L.G.A. LIYANAGE

C.E. (DESIGN) :
S. KUMARA ARACHCHI

A.D.D. (DESIGN) :
L.V.S. WEERAKOON

DATE : 20-11-2014
DRG.No. : DD/DI/CP/UVA/B/1262/04-11



ROAD-RAJAMAWATHA EXTENSION FROM KETAWALA TO MASPANNA ROAD, LOCATION BRIDGE AT CH 08+380 km

DETAILS OF PIER AND CAPPING BEAM

SCALE - 1:50

| REV | DESCRIPTION | BY | DATE |
|-----|--------------|-----|------------|
| 00 | TENDER ISSUE | HDA | 13.03.2022 |



DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS



DESIGN OFFICE (C.P.),
ROAD DEVELOPMENT AUTHORITY
06B, SAMAGI NIWASA, GANNORUWA RD, PERADENYA
TEL : 0812388997 FAX : 0812388997 email : docp@rda.gov.lk

SURVEYED & PLOTTED :

DESIGNED :
K.P.R.H.RUPASINGHE


DRAWN :
JAGATH C RAJAPAKSE

CHECKED :
L.G.A. LIYANAGE


C.E. (DESIGN) :
S. KUMARA ARACHCHI

A.D.D. (DESIGN) :
L.V.S. WEERAKOON


DATE : 20-11-2014
DRG.No. : DD/D/CP/UVA/B/1262/05-11




SECTION OF DECK
SCALE - 1:40



DETAILS OF EXPANSION JOINT
SCALE - 1:2.5



DETAILS OF RAIN WATER CATCH PIT
SCALE - 1:20



SECTION B-B
SCALE - 1:20

ROAD-RAJAMAWATHA EXTENSION FROM KETAWALA TO MASPANNA ROAD, LOCATION BRIDGE AT CH 08+380 km

DETAILS OF DECK SCALE - 1:50

| REV | DESCRIPTION | BY | DATE |
|-----|--------------|-----|------------|
| 00 | TENDER ISSUE | RDG | 13.03.2023 |
| | | | |
| | | | |
| | | | |




DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS




DESIGN OFFICE (C.P.),
ROAD DEVELOPMENT AUTHORITY
06B, SAMAGI NIWASA, GANNORUWA RD, PERADENIYA
TEL : 0812388997 FAX : 0812388997 email : docp@rda.gov.lk

| | | | |
|--|--|--|---------------------------------------|
| SURVEYED & PLOTTED : | DESIGNED : K.P.R.H. RUPASINGHE <i>brt</i> | DRAWN : JAGATH C. RAJAPAKSE <i>Jm</i> | CHECKED : L.G.A. LIYANAGE <i>A</i> |
| C.E. (DESIGN) : S. KUMARA ARACHCHI <i>A</i> | A.D.D. (DESIGN) : L.V.S. WEERAKOON <i>A</i> | DATE : 20-11-2014 | DRG.No. : DD/D/CP/UVA/B/1262/06-11 |



DETAILS OF ABUTMENT AND PIER FOUNDATION

SCALE - 1:150



R/F DETAILS OF ABUTMENT AND PIER FOUNDATION

SCALE - 1:150

ROAD-RAJAMAWATHA EXTENSION FROM KETAWALA TO MASPANNA ROAD, LOCATION BRIDGE AT CH 08+380 km

DETAILS OF ABUTMENT AND PIER FOUNDATION SCALE - 1:50

| REV | DESCRIPTION | BY | DATE |
|-----|--------------|-----|------------|
| 00 | TENDER ISSUE | RDA | 13 03 2023 |
| | | | |
| | | | |
| | | | |
| | | | |


DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS

SURVEYED & PLOTTED :
DESIGNED : K.P.R.H RUPASINGHE
DRAWN : JAGATH C RAJAPAKSE

C.E. (DESIGN) : S. KUMARA ARACHCHI
A.D.D. (DESIGN) : L.V.S. WEERAKOON

DESIGN OFFICE (C.P.),
ROAD DEVELOPMENT AUTHORITY
06B, SAMAGI NIWASA, GANNORUWA RD, PERADENIYA
TEL : 0812388997 FAX : 0812388997 email : docp@rda.gov.lk

CHECKED : L.G. A. LIYANAGE
DATE : 20-11-2014
DRG.No. : DD/D/CP/UVA/B/1262/07-11



ROAD-RAJAMAWATHA EXTENSION FROM KETAWALA TO MASPANNA ROAD, LOCATION BRIDGE AT CH 08+380 km

DOWEL PLAN

SCALE - 1:50

| REV | DESCRIPTION | BY | DATE |
|-----|--------------|-----|------------|
| 00 | TENDER ISSUE | NDA | 13 03 2023 |
| | | | |
| | | | |
| | | | |



DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS

SURVEYED & PLOTTED :

DESIGNED :
K.P.R.H.RUPASINGHE

DRAWN :
JAGATH C RAJAPAKSE

CHECKED :
L.G. A. LIYANAGE


C.E. (DESIGN) :
S. KUMARA ARACHCHI

A.D.D.(DESIGN)
L.V.S.WEERAKOON


DATE : 20-11-2014
DRG.No. : DD/D/CP/JUVA/B/1262/08-11



DESIGN OFFICE (C.P.),
ROAD DEVELOPMENT AUTHORITY
06B,SAMAGI NIWASA,GANNORUWA RD,PERADENIYA
TEL : 0812388997 FAX : 0812388997 email : docp@rda.gov.lk




DETAILS OF APPROACH SLAB
SCALE - 1:100




R/F DETAILS OF APPROACH SLAB
SCALE - 1:100

NOTE

1. DIMENSIONS SHALL NOT BE OBTAINED BY SCALING.
2. ALL WORKMANSHIP AND MATERIALS ARE TO BE ACCORDING WITH REQUIREMENTS OF THE SPECIFICATION AND BY LOWS OF THE AUTHORITY.
3. ALL DIMENSIONS ARE IN MILLIMETERS
4. ALL BARS MARKED 'R' SHALL BE HOT ROLLED MILD STEEL PLAIN BARS.
5. ALL BARS MARKED 'T' SHALL BE TOR STEEL.
6. CLEAR COVER TO REINFORCEMENT 40mm UNLESS OTHERWISE STATED.
7. CONCRETE GRADE 25(20)
8. SUITABLE TYPE OF APPROACH SLAB SHOULD BE SELECTED TO SUIT THE BACK FILLING WIDTH BEHIND THE ABUTMENT.
9. FOR INSITU CONSTRUCTION USE CONTINUOUS MESHES OF REINFORCEMENT FOR THE ENTIRE WIDTH OF CARRIAGEWAY.



DETAILS OF ABUTMEN CAPPING
SCALE - 1:25



SECTION 5-5
SCALE - 1:25

**ROAD-RAJAMAWATHA EXTENSION FROM KETAWALA TO MASPANNA ROAD,
LOCATION BRIDGE AT CH 08+380 km**

| REV | DESCRIPTION | BY | DATE |
|-----|--------------|-----|------------|
| 00 | TENDER ISSUE | HDA | 13 03 2023 |



DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS



DESIGN OFFICE (C.P.),
ROAD DEVELOPMENT AUTHORITY
06B, SAMAGI NIWASA, GANNORUWA RD, PERADENIYA
TEL : 0812388997 FAX : 0812388997 email : doep@rdia.gov.lk

APPROACH SLAB

SCALE - 1:50

SURVEYED & PLOTTED :

DESIGNED :
K.P.R.H.RUPASINGHE

DRAWN :
JAGATH C RAJAPAKSE

CHECKED :
L.G.A. LIYANAGE

C.E. (DESIGN) :
S. KUMARA ARACHCHI

A.D.D. (DESIGN)
L.V.S.WEERAKOON

DATE : 20-11-2014

DRG.No. : DD/D/CP/UVA/B/1262/09-11

| LOCATION | BAR MARK | BAR TYPE | DIA (mm) | NO.OF BARS | CUT LENGTH (mm) | SHAPE |
|----------------------|------------------|----------|----------|------------|-----------------|-------|
| Abutment & wing wall | 01 | T | 16 | 44 | 5600 | |
| | 02 | T | 16 | 25 | 14400 | |
| | 02A | T | 16 | 25 | 12065 | |
| | 03 | T | 16 | 84 | 5475 | |
| | 03A | T | 16 | 20 | 5830 | |
| 04 | T | 16 | 96 | 9830 | | |
| 04A | T | 16 | 24 | 7195 | | |
| Pier | 05 | T | 16 | 324 | 3850 | |
| | 06 | T | 16 | 72 | 14900 | |
| | 07 | T | 10 | 388 | 3200 | |
| | 08 | T | 10 | 24 | 28280 | |
| | 08a | T | 10 | 04 | 27660 | |
| | 09 | T | 10 | 368 | 3950 | |
| | 10 | T | 10 | 36 | 27020 | |
| | 10a | T | 10 | 04 | 25760 | |
| | 11 | T | 10 | 366 | 3100 | |
| | 12 | T | 10 | 24 | 23600 | |
| | 13 | T | 10 | 32 | 1600 | |
| | 14 | T | 10 | 32 | 2680 | |
| | 15 | T | 10 | 12 | 24500 | |
| | 15a | T | 10 | 12 | 1675 | |
| | Abutment capping | 16 | R | 16 | 20 | |
| 17 | | R | 10 | 100 | 2150 | |
| 18 | | R | 10 | 100 | 2400 | |
| 19 | | R | 10 | 10 | 10950 | |
| 20 | | R | 10 | 10 | 10950 | |
| 21 | | R | 10 | 20 | 2510 | |
| 22 | | T | 10 | 40 | 675 | |
| 23 | | R | 10 | 96 | 1565 | |
| 24 | | R | 10 | 12 | 10500 | |
| 25 | | R | 06 | 420 | 680 | |
| Pier capping | 26 | R | 06 | 08 | 10500 | |
| | 27 | R | 16 | 48 | 10950 | |
| | 28 | R | 10 | 200 | 2400 | |
| | 29 | R | 10 | 40 | 2510 | |
| | 30 | T | 10 | 80 | 800 | |
| | 31 | R | 06 | 840 | 680 | |
| | 32 | R | 06 | 16 | 10500 | |
| Deck | 33 | T | 10 | 450 | 10580 | |
| | 34 | T | 10 | 180 | 13400 | |
| | 35 | R | 10 | 30 | 13400 | |
| | 36 | R | 10 | 600 | 600 | |
| | 37 | R | 10 | 600 | 1450 | |
| | 38 | R | 10 | 50 | 13400 | |
| Approach slab | 39 | T | 10 | 284 | 3600 | |
| | 40 | T | 10 | 96 | 10500 | |

NOTES

CONCRETE
Use following concrete grades for structures or part of a structure as indicated below in accordance with specifications.

ABUTMENT & wingwall - KETAWALA END

a. Screed Conc. = GR. 15 (40)
b. Foundation = GR. 30 (20)
c. Stem = GR. 15 (40)
d. Capping = GR. 30 (20)

PIER

a. Screed Conc. = GR. 15 (40)
b. Foundation = GR. 30 (20)
c. Stem = GR. 15 (40)
d. Capping = GR. 30 (20)

ABUTMENT & Wingwall - MASPANNA END

a. Screed Conc. = GR. 15 (40)
b. Foundation = GR. 30 (20)
c. Stem = GR. 15 (40)
d. Capping = GR. 30 (20)

REINFORCEMENT

a. All bar marked "Y" shall be high yield deformed bars of yield strength not less than 460 N/mm² and all marked "R" shall not be rolled mild steel plain bars of yield strength not less than 250 N/mm²

b. Bars of cut length larger than the supplied length to be lapped with length of 50 Ø, where Ø is the diameter and lapping should be staggered with length of 50 Ø, where Ø is the diameter

c. Reinforcement bars shall be bent accordance with standard specifications.

d. Clear concrete cover for reinforcement
Capping beam - 75 mm
Abutment foundation - 75 mm

SPECIAL NOTES

All the constructions shall be in accordance with

a. Standards specification for construction & maintenance of Road & Bridges. Second Edition June 2009 ICTAD

b. Specification for Building Works (Volume I) - ICTAD

c. Specification for Building Works (Volume II) - ICTAD

ROAD-RAJAMAWATHA EXTENSION FROM KETAWALA TO MASPANNA ROAD, LOCATION BRIDGE AT CH 08+380 km

DETAILS OF BAR SCHEDULE

SCALE - 1:50

| REV | DESCRIPTION | BY | DATE |
|-----|--------------|-----|------------|
| 00 | TENDER ISSUE | RDA | 13.03.2023 |

DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS


SURVEYED & PLOTTED :
DESIGNED : K.P.R.H.RUPASINGHE
DRAWN : JAGATH C RAJAPAKSE
CHECKED : L.G.A. LIYANAGE

C.E. (DESIGN) : S. KUMARA ARACHCHI
A.D.D. (DESIGN) : L.V.S. WEERAKOON

DATE : 20-11-2014
DRG.No. : DD/D/CP/UVJ/B/1262/10-11

DESIGN OFFICE (C.P.),
ROAD DEVELOPMENT AUTHORITY
06B, SAMAGI NIWASA, GANNORUWA RD, PERADENIYA
TEL : 0812388997 FAX : 0812388997 email : docp@rda.gov.lk


| DESCRIPTION OF GPS CONTROL POINT | | | | Point No: GPS 10 | |
|----------------------------------|---------------------|-------------|--------------------|------------------|--|
| PROVINCE | Uva | DISTRICT | Badulla | | |
| D.S.DIVISION | Uva Paranagama | STATION | Dalukella | | |
| PREPARED BY: | | CHECKED BY: | | | |
| NAME | J.M.K.R. Jayasekara | NAME | P.L.Y. Seneviratne | | |
| DESIGNATION | Govt. Surveyor | DESIGNATION | Supdt. of Surveys | | |
| DATE | 2014.07.25 | DATE | 2014.07. | | |



Remarks :

| MONUMENT TYPE: A6 | | | GEODETIC ID: 71C20072 | | |
|--------------------|----------------|------------------------|---|-------------|--------------------|
| WGS 84 COORDINATES | | | NATIONAL GRID COORDINATES | | |
| LATITUDE | LONGITUDE | ELLIPSOIDAL HEIGHT (m) | NORTHING (m) | EASTING (m) | EVEREST HEIGHT (m) |
| 7 00 21.42563 | 80 58 11.72049 | 472.341 | 500573.705 | 521675.481 | - |
| REQUISITION NO: | | MISSION | PROJECT | | |
| ISM/2014/BD/51 | | TGPS | Kandy-Badulla Rajamawatha(MAGA Engineering) | | |


| DESCRIPTION OF GPS CONTROL POINT | | | | Point No: GPS 11 | |
|----------------------------------|---------------------|-------------|--------------------|------------------|--|
| PROVINCE | Uva | DISTRICT | Badulla | | |
| D.S.DIVISION | Uva Paranagama | STATION | Dalukella | | |
| PREPARED BY: | | CHECKED BY: | | | |
| NAME | J.M.K.R. Jayasekara | NAME | P.L.Y. Seneviratne | | |
| DESIGNATION | Govt. Surveyor | DESIGNATION | Supdt. of Surveys | | |
| DATE | 2014.07.25 | DATE | 2014.07. | | |



Remarks :

| MONUMENT TYPE: A6 | | | GEODETIC ID: 71C20073 | | |
|--------------------|----------------|------------------------|---|-------------|--------------------|
| WGS 84 COORDINATES | | | NATIONAL GRID COORDINATES | | |
| LATITUDE | LONGITUDE | ELLIPSOIDAL HEIGHT (m) | NORTHING (m) | EASTING (m) | EVEREST HEIGHT (m) |
| 7 00 21.23985 | 80 58 10.48263 | 472.521 | 500567.983 | 521637.493 | - |
| REQUISITION NO: | | MISSION | PROJECT | | |
| ISM/2014/BD/51 | | TGPS | Kandy-Badulla Rajamawatha(MAGA Engineering) | | |

| DESCRIPTION OF GPS CONTROL POINT | | | | Point No: GPS 12 | |
|----------------------------------|---------------------|-------------|--------------------|------------------|--|
| PROVINCE | Uva | DISTRICT | Badulla | | |
| D.S.DIVISION | Uva Paranagama | STATION | Dalukella | | |
| PREPARED BY: | | CHECKED BY: | | | |
| NAME | J.M.K.R. Jayasekara | NAME | P.L.Y. Seneviratne | | |
| DESIGNATION | Govt. Surveyor | DESIGNATION | Supdt. of Surveys | | |
| DATE | 2014.07.25 | DATE | 2014.07. | | |



Remarks :

| MONUMENT TYPE: A6 | | | GEODETIC ID: 71C20074 | | |
|--------------------|----------------|------------------------|---|-------------|--------------------|
| WGS 84 COORDINATES | | | NATIONAL GRID COORDINATES | | |
| LATITUDE | LONGITUDE | ELLIPSOIDAL HEIGHT (m) | NORTHING (m) | EASTING (m) | EVEREST HEIGHT (m) |
| 7 00 21.21434 | 80 58 09.25906 | 472.319 | 500567.184 | 521599.942 | - |
| REQUISITION NO: | | MISSION | PROJECT | | |
| ISM/2014/BD/51 | | TGPS | Kandy-Badulla Rajamawatha(MAGA Engineering) | | |

ROAD-RAJAMAWATHA EXTENSION FROM KETAWALA TO MASPANNA ROAD, LOCATION BRIDGE AT CH 08+380 km

GPS CONTROL POINT

SCALE - 1:50

| REV | DESCRIPTION | BY | DATE |
|-----|--------------|-----|------------|
| 00 | TENDER ISSUE | RDA | 13.03.2023 |



DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS

SURVEYED & PLOTTED :

DESIGNED :
K.P.R.H.RUPASINGHE

DRAWN :
JAGATH C RAJAPAKSE

CHECKED :
L.G.A. LIYANAGE

C.E. (DESIGN):
S. KUMARA ARACHCHI

A.D.D. (DESIGN):
L.V.S. WEERAKOON

DATE : 20-11-2014

DRG.No. : DD/D/CP/UVA/B/1262/11-11



**GOVERNMENT OF DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS AND TRANSPORT**



ROAD DEVELOPMENT AUTHORITY

**CONSTRUCTION OF RAJA MAWATHA EXTENSION ROAD FROM KETAWALA TO MASPANNA
(CH 07+560– CH 09+300)**

**DETAILED ENGINEERING DESIGNS
GEOMETRIC DESIGN DRAWINGS**

MARCH 2023

**Design Office (Central Province)
Road Development Authority
6B, Gannoruwa,
Peradeniya**

CONTENTS

: GEOMETRIC DESIGN DRAWINGS

- 1.1 General Details
- 1.2 Plan & Profile
- 1.3 Typical road cross sections
- 1.4 Pavement design thicknesses
- 1.5 Structures

***CONSTRUCTION OF RAJA MAWATHA EXTENTION ROAD FROM
KETAWALA TO MASPANNA (CH 7+560- CH9+300km)
: GEOMETRIC DESIGN DRAWINGS,
1.1 - GENERAL DETAILS***

LEGEND

| Existing ground features | |
|--------------------------|--|
| | North Direction |
| | Edge of existing road |
| CUL | Culvert / Bridge No. |
| | Stream/River etc. |
| | Tree |
| | Railway Track |
| RW | Retaining Wall |
| ● KMP (No.) | Kilometer post No. |
| | RDA Boundary stone |
| ● SB/DB/NB | Sign Board/Direction Board/Named Board |
| ● AdB | Advertising Board |

| | |
|-----|-------------------------------|
| CP | Concrete post |
| MHS | Manhole Sewer |
| MHD | Manhole Dialog |
| GL | Gully |
| V | Valve |
| ECB | Electric Cable Box |
| TSP | Traffic Signal Post |
| FB | Flower Bed |
| WM | Water Main Marker |
| GS | Gurd stone |
| M | Memorial |
| BL | Building Lavatory |
| | Exiting Sluice Valve |
| | Sluice Valve/Section Valve |
| | Road |
| | Proposed 225mm dia. pipe line |
| | Flow Meters |
| | Existing Pipe line |

| | |
|----|------------|
| DF | Dry Fence |
| GR | Guard rail |

| Buildings , Houses, shops etc. | |
|--------------------------------|-----------------------------|
| P | Permanent Building |
| Ty | Temporary Building |
| TRS | Tiled Roofed Shop |
| TRG | Tiled Roofed Garage |
| ARH | Asbestos Roofed House |
| ARS | Asbestos Roofed Shop |
| TinRH | Tin Roofed House |
| TinRS | Tin Roofed Shop |
| TH | Temporary Hut |
| C/rldg | Concrete Roofed Building |
| BS | Bus Shelter |
| BUC | Building Under Construction |
| ● G ● | Gate |

| Proposed ground features | |
|--------------------------|--|
| | Center Line |
| | Edge of carriageway |
| | Edge of shoulder |
| | Acquisition boundary |
| | Finished ground profile |
| | Existing ground profile |
| | Shoulder edge Profile |
| | Drain invert Profile |
| | Flow direction |
| | Embankment |
| | Bench Mark /Control Point/GPS Point (No) |
| | Temporary bench mark (No) |
| | Traverse line |

| Utility etc. | |
|--------------|------------------------------|
| | Lamp Post |
| | Electric Post |
| | Electric Post (High Tension) |
| | Transmission Tower |
| TF | Transformer (Electrical) |
| MHE | Man hole (Electrical) |
| | Telephone Post |
| CB | Telephone Booth |
| MHT | Man hole (Telecom) |
| TCB | Telephone cable box |
| ● PB | Post Box |
| WPL | Water Pipe line |
| ECB | Electric cable box |
| WTH | Water tank (Over head) |
| WTP | Water Tap |
| MHW | Man hole (Water) |
| MH | Man hole |
| ○ TUW | Tube Well |
| | Fire Hydrant |

| Boundaries, Fences etc. | |
|-------------------------|--------------------------------|
| U | Undefined |
| IF | Iron Fence |
| WFC | Wire on concrete post |
| WFI | Wire on iron post |
| CFC | Chain link fence concrete post |
| CFI | Chain link fence iron post |
| W | Boundary Wall |
| WF | Wire fence |
| TB | Bank Top |
| BB | Bank Bottom |
| ABF | Asbestos Fence |
| WMF | Wire Mesh Fence |
| ZF | Zinc Fence |

| Design notations and abbreviations Vertical Geometry | |
|---|---|
| G | Gradient |
| △ IP | Point of intersection of gradient |
| V.C.L. | Vertical Curve length |
| K | Curve coefficient |
| PT | Point |
| STA: | Station |
| ELEV: | Elevation |
| BVCS: | Vertical Tangent-Curve Intersect Station |
| BVCE: | Vertical Tangent-Curve Intersect Elevation |
| EVCS: | Vertical Curve-Tangent Intersect Station |
| EVCE: | Vertical Curve-Tangent Intersect Elevation |
| VCCS: | Vertical Compound Curve Intersect Station |
| VCCE: | Vertical Compound Curve Intersect Elevation |

| Design notations and abbreviations Horizontal Geometry | |
|---|---|
| CH | CHAINAGE |
| PC | Tangent - curve intersect |
| PCC | Curve - curve intersect |
| PT | Curve - tangent intersect |
| R | Radius of curvature |
| Off: | Offset |
| l & r | Difference in levels between left or right edge of carriageway & centerline |

| DRAIN | |
|-------|--------------------|
| | Existing Drain |
| CDn | Covered Drain |
| SDn | Shoe Drain |
| MDn | Masonry Drain |
| EDn | Earth Drain |
| Udn | Under Ground Drain |

CONSTRUCTION OF RAJA MAWATHA EXTENSION ROAD FROM KETAWALA TO MASPANNA. (FROM CH7+560 TO 9+300 km)

LEGEND

SCALE - N.T.S


| REV | DESCRIPTION | BY | DATE |
|-----|-------------|----|------------|
| | | | 28-11-2011 |

| | | | | | | | |
|--|--|--|--|---------------------------------|--|--|--|
| | | DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA MINISTRY OF HIGHWAYS | | | | DESIGN OFFICE (C.P.), ROAD DEVELOPMENT AUTHORITY 6B, GANNORUWA, PERADENIYA. TEL : 0812388997 FAX : 0812388997 email : docpkandy@gmail.com | |
| SURVEYED & PLOTTED : ***** | | DESIGNED : | | DRAWN : | | CHECKED : | |
| C.E (DESIGN): K.A.S.B.KUMARA ARACHCHI | | | | D.D (DESIGN) L.V.S.WEERAKOON | | | |
| | | | | | | DATE : 23-03-2023 DRG.No. : DD/D/UVAH/1267/1.1/01(01) | |

*CONSTRUCTION OF RAJA MAWATHA EXTENTION ROAD FROM
KETAWALA TO MASPANNA (CH 7+560- CH9+300km)*

: GEOMETRIC DESIGN DRAWINGS,

1.2 - PLAN, SETTING OUT DATA & PROFILE



PLAN
SCALE 1: 1000

| Station | Northing(m) | Easting(m) |
|----------|-------------|------------|
| 7+500.00 | 499720.745 | 523497.459 |
| 7+505.00 | 499723.409 | 523493.232 |
| 7+510.00 | 499725.539 | 523488.711 |
| 7+515.00 | 499727.103 | 523483.966 |
| 7+520.00 | 499728.079 | 523479.065 |
| 7+525.00 | 499728.453 | 523474.082 |
| 7+530.00 | 499728.792 | 523469.095 |
| 7+535.00 | 499729.545 | 523464.153 |
| 7+540.00 | 499730.707 | 523459.292 |
| 7+545.00 | 499732.270 | 523454.544 |
| 7+550.00 | 499734.222 | 523449.942 |
| 7+555.00 | 499736.551 | 523445.519 |
| 7+560.00 | 499739.239 | 523441.305 |
| 7+565.00 | 499742.270 | 523437.330 |
| 7+570.00 | 499745.620 | 523433.621 |
| 7+575.00 | 499749.146 | 523430.076 |
| 7+580.00 | 499752.606 | 523426.467 |
| 7+585.00 | 499755.995 | 523422.790 |
| 7+590.00 | 499759.309 | 523419.046 |
| 7+595.00 | 499762.549 | 523415.238 |
| 7+600.00 | 499765.712 | 523411.366 |
| 7+605.00 | 499768.808 | 523407.440 |
| 7+610.00 | 499772.036 | 523403.623 |
| 7+615.00 | 499775.472 | 523399.991 |
| 7+620.00 | 499779.104 | 523396.555 |
| 7+625.00 | 499782.921 | 523393.327 |
| 7+630.00 | 499786.912 | 523390.315 |
| 7+635.00 | 499790.956 | 523387.375 |
| 7+640.00 | 499794.936 | 523384.349 |
| 7+645.00 | 499798.849 | 523381.237 |
| 7+650.00 | 499802.695 | 523378.042 |
| 7+655.00 | 499806.471 | 523374.765 |
| 7+660.00 | 499810.176 | 523371.407 |
| 7+665.00 | 499813.807 | 523367.970 |
| 7+670.00 | 499817.363 | 523364.456 |
| 7+675.00 | 499820.843 | 523360.865 |
| 7+680.00 | 499824.245 | 523357.201 |
| 7+685.00 | 499827.567 | 523353.464 |
| 7+690.00 | 499830.807 | 523349.657 |
| 7+695.00 | 499834.045 | 523345.846 |
| 7+700.00 | 499837.406 | 523342.145 |
| 7+705.00 | 499840.888 | 523338.557 |
| 7+710.00 | 499844.488 | 523335.087 |
| 7+715.00 | 499848.201 | 523331.740 |
| 7+720.00 | 499852.024 | 523328.518 |
| 7+725.00 | 499855.953 | 523325.425 |
| 7+730.00 | 499859.982 | 523322.464 |
| 7+735.00 | 499864.108 | 523319.640 |
| 7+740.00 | 499868.093 | 523316.637 |
| 7+745.00 | 499871.201 | 523312.738 |
| 7+750.00 | 499873.187 | 523308.165 |
| 7+755.00 | 499873.915 | 523303.233 |
| 7+760.00 | 499873.466 | 523298.260 |
| 7+765.00 | 499873.944 | 523293.306 |
| 7+770.00 | 499876.017 | 523288.782 |
| 7+775.00 | 499879.457 | 523285.185 |
| 7+780.00 | 499883.884 | 523282.911 |
| 7+785.00 | 499888.773 | 523281.890 |
| 7+790.00 | 499893.461 | 523280.180 |
| 7+795.00 | 499897.670 | 523277.499 |



SETTING OUT DATA OF C/L


CONSTRUCTION OF RAJA MAWATHA EXTENTION ROAD FROM KETAWALA TO MASPENNA SECTION FROM CH (7+500 - 9+300)Km

PLAN AND SETTING OUT DATA - CH(7+500-7+800)Km

SCALE -1:1000

| REV | DESCRIPTION | BY | DATE |
|-----|-------------|----|------|
| | | | |
| | | | |
| | | | |
| | | | |

| | | | |
|---|--|---|---------------------------------------|
|  DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA MINISTRY OF HIGHWAYS & TRANSPORT | |  DESIGN OFFICE (C.P.), ROAD DEVELOPMENT AUTHORITY 6B, GANNORUWA, PERADENIYA. TEL : 0812388997 FAX : 0812388997 email : docpkandy@gmail.com | |
| SURVEYED & PLOTTED : | | DESIGNED : K A S B. KUMARA ARACHCHI | DRAWN : B.K. RANASINGHE |
| C.E. (DESIGN) : K.A.S.B. KUMARA ARACHCHI | | D.D(DESIGN) L.V.S WEERAKOON | CHECKED : R.I.P. SOMARATHNA |
| DATE : 2023-03-23 | | | DRG.No. : DD/D/UA/H/1267/1.2/1/01(06) |



PLAN
SCALE 1: 1000

| Station | Northing(m) | Easting(m) |
|----------|-------------|------------|
| 7+800.00 | 499901.201 | 523273.973 |
| 7+805.00 | 499903.959 | 523269.808 |
| 7+810.00 | 499906.781 | 523265.683 |
| 7+815.00 | 499909.938 | 523261.807 |
| 7+820.00 | 499913.406 | 523258.207 |
| 7+825.00 | 499917.161 | 523254.908 |
| 7+830.00 | 499921.179 | 523251.934 |
| 7+835.00 | 499925.429 | 523249.304 |
| 7+840.00 | 499929.884 | 523247.037 |
| 7+845.00 | 499934.513 | 523245.149 |
| 7+850.00 | 499939.229 | 523243.488 |
| 7+855.00 | 499943.946 | 523241.829 |
| 7+860.00 | 499948.662 | 523240.170 |
| 7+865.00 | 499953.379 | 523238.511 |
| 7+870.00 | 499958.096 | 523236.852 |
| 7+875.00 | 499962.813 | 523235.193 |
| 7+880.00 | 499967.564 | 523233.638 |
| 7+885.00 | 499972.411 | 523232.418 |
| 7+890.00 | 499977.334 | 523231.547 |
| 7+895.00 | 499982.306 | 523231.029 |
| 7+900.00 | 499987.302 | 523230.868 |
| 7+905.00 | 499992.297 | 523231.063 |
| 7+910.00 | 499997.266 | 523231.615 |
| 7+915.00 | 500002.182 | 523232.519 |
| 7+920.00 | 500007.022 | 523233.772 |
| 7+925.00 | 500011.759 | 523235.368 |
| 7+930.00 | 500016.374 | 523237.290 |
| 7+935.00 | 500021.269 | 523238.042 |
| 7+940.00 | 500025.965 | 523236.485 |
| 7+945.00 | 500029.498 | 523232.972 |
| 7+950.00 | 500032.612 | 523229.060 |
| 7+955.00 | 500035.726 | 523225.148 |
| 7+960.00 | 500038.841 | 523221.237 |
| 7+965.00 | 500041.921 | 523217.299 |
| 7+970.00 | 500043.928 | 523212.749 |
| 7+975.00 | 500044.219 | 523207.784 |
| 7+980.00 | 500042.992 | 523202.944 |
| 7+985.00 | 500041.576 | 523198.149 |
| 7+990.00 | 500040.160 | 523193.353 |
| 7+995.00 | 500038.744 | 523188.558 |
| 8+000.00 | 500037.328 | 523183.763 |
| 8+005.00 | 500035.912 | 523178.967 |
| 8+010.00 | 500034.496 | 523174.172 |
| 8+015.00 | 500033.080 | 523169.377 |
| 8+020.00 | 500031.664 | 523164.582 |
| 8+025.00 | 500030.242 | 523159.788 |
| 8+030.00 | 500028.854 | 523155.047 |
| 8+035.00 | 500026.831 | 523150.392 |
| 8+040.00 | 500024.778 | 523145.834 |
| 8+045.00 | 500022.500 | 523141.384 |
| 8+050.00 | 500020.010 | 523137.048 |
| 8+055.00 | 500017.464 | 523132.744 |
| 8+060.00 | 500014.919 | 523128.441 |
| 8+065.00 | 500012.373 | 523124.137 |
| 8+070.00 | 500009.828 | 523119.834 |
| 8+075.00 | 500007.196 | 523115.584 |
| 8+080.00 | 500004.102 | 523111.660 |
| 8+085.00 | 500000.543 | 523108.153 |
| 8+090.00 | 499996.575 | 523105.117 |
| 8+095.00 | 499992.259 | 523102.599 |



SETTING OUT DATA OF C/L


CONSTRUCTION OF RAJA MAWATHA EXTENTION ROAD FROM
KETAWALA TO MASPENNA
SECTION FROM CH (7+500 - 9+300)Km

PLAN AND SETTING OUT DATA - CH(7+800-8+100)Km

SCALE -1:1000

| REV | DESCRIPTION | BY | DATE |
|-----|-------------|----|------|
| | | | |
| | | | |
| | | | |

| | | | | |
|--|--|---|--|--|
|  DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA MINISTRY OF HIGHWAYS & TRANSPORT | |  | | DESIGN OFFICE (C.P.), ROAD DEVELOPMENT AUTHORITY 6B, GANNORUWA, PERADENIYA. TEL : 0812388997 FAX : 0812388997 email : docpkandy@gmail.com |
| SURVEYED & PLOTTED : | | DESIGNED : K.A.S.B. KUMARA ARACHCHI | | DRAWN : B.K. RANASINGHE |
| C.E. (DESIGN): K.A.S.B. KUMARA ARACHCHI | | D.D.(DESIGN) L.V.S WEERAKOON | | CHECKED : R.I.P. SOMARATHNA |
| DATE : 2023-03-23 | | | | DRG.No. : DD/DI/UA/H/1267/1 2/1/02(06) |



PLAN
SCALE 1:1000

| Station | Eastings(m) | Northing(m) |
|----------|-------------|-------------|
| 8+100.00 | 523100.639 | 499987.663 |
| 8+105.00 | 523099.265 | 499982.858 |
| 8+110.00 | 523098.147 | 499977.985 |
| 8+115.00 | 523097.028 | 499973.112 |
| 8+120.00 | 523095.910 | 499968.238 |
| 8+125.00 | 523094.730 | 499963.380 |
| 8+130.00 | 523093.190 | 499958.625 |
| 8+135.00 | 523091.259 | 499954.014 |
| 8+140.00 | 523088.951 | 499949.580 |
| 8+145.00 | 523086.282 | 499945.354 |
| 8+150.00 | 523083.270 | 499941.365 |
| 8+155.00 | 523079.937 | 499937.640 |
| 8+160.00 | 523076.306 | 499934.205 |
| 8+165.00 | 523072.401 | 499931.084 |
| 8+170.00 | 523068.250 | 499928.300 |
| 8+175.00 | 523063.881 | 499925.870 |
| 8+180.00 | 523059.326 | 499923.813 |
| 8+185.00 | 523054.615 | 499922.142 |
| 8+190.00 | 523049.781 | 499920.869 |
| 8+195.00 | 523044.858 | 499920.003 |
| 8+200.00 | 523039.892 | 499919.421 |
| 8+205.00 | 523034.925 | 499918.849 |
| 8+210.00 | 523029.958 | 499918.277 |
| 8+215.00 | 523024.991 | 499917.705 |
| 8+220.00 | 523020.023 | 499917.134 |
| 8+225.00 | 523015.052 | 499916.596 |
| 8+230.00 | 523010.077 | 499916.100 |
| 8+235.00 | 523005.098 | 499915.644 |
| 8+240.00 | 523000.115 | 499915.230 |
| 8+245.00 | 522995.129 | 499914.858 |
| 8+250.00 | 522990.140 | 499914.528 |
| 8+255.00 | 522985.148 | 499914.238 |
| 8+260.00 | 522980.154 | 499913.991 |
| 8+265.00 | 522975.159 | 499913.785 |
| 8+270.00 | 522970.161 | 499913.634 |
| 8+275.00 | 522965.161 | 499913.599 |
| 8+280.00 | 522960.162 | 499913.690 |
| 8+285.00 | 522955.167 | 499913.905 |
| 8+290.00 | 522950.179 | 499914.245 |
| 8+295.00 | 522945.200 | 499914.710 |
| 8+300.00 | 522940.231 | 499915.260 |
| 8+305.00 | 522935.251 | 499915.711 |
| 8+310.00 | 522930.262 | 499916.036 |
| 8+315.00 | 522925.266 | 499916.237 |
| 8+320.00 | 522920.267 | 499916.312 |
| 8+325.00 | 522915.267 | 499916.263 |
| 8+330.00 | 522910.270 | 499916.089 |
| 8+335.00 | 522905.279 | 499915.790 |
| 8+340.00 | 522900.292 | 499915.441 |
| 8+345.00 | 522895.304 | 499915.092 |
| 8+350.00 | 522890.316 | 499914.742 |
| 8+355.00 | 522885.328 | 499914.393 |
| 8+360.00 | 522880.340 | 499914.044 |
| 8+365.00 | 522875.353 | 499913.694 |
| 8+370.00 | 522870.436 | 499912.867 |
| 8+375.00 | 522865.928 | 499910.741 |
| 8+380.00 | 522862.176 | 499907.460 |
| 8+385.00 | 522859.468 | 499903.277 |
| 8+390.00 | 522858.000 | 499898.512 |
| 8+395.00 | 522857.048 | 499893.604 |

SETTING OUT DATA OF C/L

CONSTRUCTION OF RAJA MAWATHA EXTENTION ROAD FROM
KETAWALA TO MASPENNA
SECTION FROM CH (7+500 - 9+300)Km

PLAN AND SETTING OUT DATA - CH(8+100-8+400)Km

SCALE -1:1000

| REV | DESCRIPTION | BY | DATE |
|-----|-------------|----|------|
| | | | |
| | | | |
| | | | |
| | | | |



DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS & TRANSPORT

SURVEYED & PLOTTED :

DESIGNED :
K.A.S.B. KUMARA ARACHCHI

DRAWN :
B.K. RANASINGHE


C.E. (DESIGN) :
K.A.S.B. KUMARA ARACHCHI

D.D.(DESIGN)
L.V.S.WEERAKOON

DESIGN OFFICE (C.P.),
ROAD DEVELOPMENT AUTHORITY
6B, GANNORUWA, PERADENIYA.
TEL : 0812388997 FAX : 0812388997 email : docpkandy@gmail.com

CHECKED :
R.I.P. SOMARATHNA

DATE : 2023-03-23
DRG.No. : DD/DI/UVA/H/1267/1 2/1/03(06)



PLAN
SCALE 1: 1000

| Station | Northing(m) | Easting(m) |
|----------|-------------|------------|
| 8+400.00 | 499888.695 | 522856.096 |
| 8+405.00 | 499883.787 | 522855.144 |
| 8+410.00 | 499878.878 | 522854.192 |
| 8+415.00 | 499873.970 | 522853.239 |
| 8+420.00 | 499869.061 | 522852.287 |
| 8+425.00 | 499864.153 | 522851.335 |
| 8+430.00 | 499859.244 | 522850.383 |
| 8+435.00 | 499854.336 | 522849.431 |
| 8+440.00 | 499849.427 | 522848.479 |
| 8+445.00 | 499844.519 | 522847.527 |
| 8+450.00 | 499839.610 | 522846.575 |
| 8+455.00 | 499834.702 | 522845.622 |
| 8+460.00 | 499829.818 | 522844.561 |
| 8+465.00 | 499825.206 | 522842.653 |
| 8+470.00 | 499821.089 | 522839.832 |
| 8+475.00 | 499817.844 | 522836.221 |
| 8+480.00 | 499815.020 | 522831.975 |
| 8+485.00 | 499813.332 | 522827.279 |
| 8+490.00 | 499812.651 | 522822.334 |
| 8+495.00 | 499813.008 | 522817.356 |
| 8+500.00 | 499814.386 | 522812.559 |
| 8+505.00 | 499816.704 | 522808.137 |
| 8+510.00 | 499819.295 | 522803.860 |
| 8+515.00 | 499821.886 | 522799.584 |
| 8+520.00 | 499824.476 | 522795.308 |
| 8+525.00 | 499827.067 | 522791.031 |
| 8+530.00 | 499829.647 | 522786.748 |
| 8+535.00 | 499832.177 | 522782.436 |
| 8+540.00 | 499834.653 | 522778.092 |
| 8+545.00 | 499837.074 | 522773.717 |
| 8+550.00 | 499839.441 | 522769.313 |
| 8+555.00 | 499841.752 | 522764.879 |
| 8+560.00 | 499844.007 | 522760.416 |
| 8+565.00 | 499846.207 | 522755.926 |
| 8+570.00 | 499848.350 | 522751.409 |
| 8+575.00 | 499850.437 | 522746.865 |
| 8+580.00 | 499852.467 | 522742.296 |
| 8+585.00 | 499854.439 | 522737.701 |
| 8+590.00 | 499856.470 | 522733.133 |
| 8+595.00 | 499858.820 | 522728.721 |
| 8+600.00 | 499861.488 | 522724.494 |
| 8+605.00 | 499864.460 | 522720.474 |
| 8+610.00 | 499867.719 | 522716.684 |
| 8+615.00 | 499871.247 | 522713.143 |
| 8+620.00 | 499875.026 | 522709.871 |
| 8+625.00 | 499878.862 | 522706.664 |
| 8+630.00 | 499882.514 | 522703.250 |
| 8+635.00 | 499885.971 | 522699.638 |
| 8+640.00 | 499889.222 | 522695.840 |
| 8+645.00 | 499892.257 | 522691.868 |
| 8+650.00 | 499895.157 | 522687.794 |
| 8+655.00 | 499898.186 | 522683.818 |
| 8+660.00 | 499901.533 | 522680.106 |
| 8+665.00 | 499905.177 | 522676.685 |
| 8+670.00 | 499909.087 | 522673.570 |
| 8+675.00 | 499913.074 | 522670.552 |
| 8+680.00 | 499917.060 | 522667.534 |
| 8+685.00 | 499921.047 | 522664.516 |
| 8+690.00 | 499925.033 | 522661.498 |
| 8+695.00 | 499929.073 | 522658.553 |

SETTING OUT DATA OF C/L

CONSTRUCTION OF RAJA MAWATHA EXTENTION ROAD FROM KETAWALA TO MASPENNA SECTION FROM CH (7+500 - 9+300)Km

PLAN AND SETTING OUT DATA - CH(8+400-8+700)Km

SCALE -1:1000

| REV | DESCRIPTION | BY | DATE |
|-----|-------------|----|------|
| | | | |
| | | | |
| | | | |
| | | | |



DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS & TRANSPORT

SURVEYED & PLOTTED :

DESIGNED :
K.A.S.B. KUMARA ARACHCHI

DRAWN :
B.K. RANASINGHE

C.E. (DESIGN):
K.A.S.B. KUMARA ARACHCHI


D.D(DESIGN)
L.V.S.WEERAKOON

CHECKED :
R.I.P. SOMARATHNA

DATE : 2023-03-23

DRG.No. : DD/D/UVA/H/1267/1.2/1/04(06)

DESIGN OFFICE (C.P.),
ROAD DEVELOPMENT AUTHORITY
6B, GANNORUWA, PERADENIYA
TEL : 0812388997 FAX : 0812388997 email : docpkandy@gmail.com



PLAN
SCALE 1: 1000

| Station | Northing(m) | Easting(m) |
|----------|-------------|------------|
| 8+700.00 | 499933.331 | 522655.935 |
| 8+705.00 | 499937.792 | 522653.680 |
| 8+710.00 | 499942.425 | 522651.804 |
| 8+715.00 | 499947.198 | 522650.320 |
| 8+720.00 | 499952.078 | 522649.239 |
| 8+725.00 | 499957.032 | 522648.568 |
| 8+730.00 | 499962.024 | 522648.311 |
| 8+735.00 | 499967.023 | 522648.387 |
| 8+740.00 | 499972.022 | 522648.490 |
| 8+745.00 | 499977.021 | 522648.593 |
| 8+750.00 | 499982.020 | 522648.697 |
| 8+755.00 | 499987.019 | 522648.800 |
| 8+760.00 | 499992.017 | 522648.903 |
| 8+765.00 | 499997.016 | 522649.007 |
| 8+770.00 | 500002.015 | 522649.110 |
| 8+775.00 | 500007.015 | 522649.142 |
| 8+780.00 | 500012.012 | 522648.970 |
| 8+785.00 | 500016.997 | 522648.592 |
| 8+790.00 | 500021.963 | 522648.009 |
| 8+795.00 | 500026.928 | 522647.433 |
| 8+800.00 | 500031.923 | 522647.233 |
| 8+805.00 | 500036.918 | 522647.418 |
| 8+810.00 | 500041.885 | 522647.985 |
| 8+815.00 | 500046.793 | 522648.933 |
| 8+820.00 | 500051.628 | 522650.207 |
| 8+825.00 | 500056.451 | 522651.524 |
| 8+830.00 | 500061.274 | 522652.841 |
| 8+835.00 | 500066.098 | 522654.158 |
| 8+840.00 | 500070.913 | 522655.503 |
| 8+845.00 | 500075.569 | 522657.315 |
| 8+850.00 | 500079.948 | 522659.722 |
| 8+855.00 | 500083.972 | 522662.983 |
| 8+860.00 | 500087.574 | 522666.146 |
| 8+865.00 | 500090.690 | 522670.052 |
| 8+870.00 | 500093.267 | 522674.332 |
| 8+875.00 | 500095.627 | 522678.740 |
| 8+880.00 | 500098.075 | 522683.100 |
| 8+885.00 | 500100.609 | 522687.410 |
| 8+890.00 | 500103.229 | 522691.668 |
| 8+895.00 | 500105.884 | 522695.905 |
| 8+900.00 | 500108.538 | 522700.143 |
| 8+905.00 | 500111.193 | 522704.380 |
| 8+910.00 | 500113.847 | 522708.617 |
| 8+915.00 | 500116.502 | 522712.854 |
| 8+920.00 | 500119.156 | 522717.091 |
| 8+925.00 | 500121.811 | 522721.328 |
| 8+930.00 | 500124.478 | 522725.557 |
| 8+935.00 | 500127.287 | 522729.693 |
| 8+940.00 | 500130.265 | 522733.709 |
| 8+945.00 | 500133.408 | 522737.597 |
| 8+950.00 | 500136.711 | 522741.351 |
| 8+955.00 | 500140.167 | 522744.964 |
| 8+960.00 | 500143.770 | 522748.430 |
| 8+965.00 | 500147.515 | 522751.743 |
| 8+970.00 | 500151.394 | 522754.897 |
| 8+975.00 | 500155.189 | 522758.150 |
| 8+980.00 | 500158.700 | 522761.708 |
| 8+985.00 | 500161.903 | 522765.545 |
| 8+990.00 | 500164.775 | 522769.636 |
| 8+995.00 | 500167.412 | 522773.884 |
| 9+000.00 | 500170.132 | 522778.079 |

SETTING OUT DATA OF C/L

CONSTRUCTION OF RAJA MAWATHA EXTENTION ROAD FROM
KETAWALA TO MASPENNA
SECTION FROM CH (7+500 - 9+300)Km

PLAN AND SETTING OUT DATA - CH(8+700-9+000)Km

SCALE -1:1000

| REV | DESCRIPTION | BY | DATE |
|-----|-------------|----|------|
| | | | |
| | | | |
| | | | |

DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS & TRANSPORT

SURVEYED & PLOTTED :
DESIGNED :
DRAWN :
CHECKED :

C.E. (DESIGN):
K.A.S.B. KUMARA ARACHCHI


D.D(DESIGN):
L.V.S WEERAKOON

B.K. RANASINGHE

DESIGN OFFICE (C.P.),
ROAD DEVELOPMENT AUTHORITY
6B, GANNORUWA, PERADENIYA.
TEL : 0812388997 FAX : 0812388997 email : docpkandy@gmail.com

R.I.P. SOMARATHNA

DATE : 2023-03-23
DRG.No. : DD/DJ/UVVA/H/1267/1, 2/1/05(06)



PLAN
SCALE 1: 1000

| Station | Northing(m) | Easting(m) |
|----------|-------------|------------|
| 9+000.00 | 500170.132 | 522778.079 |
| 9+005.00 | 500172.957 | 522782.204 |
| 9+010.00 | 500175.885 | 522786.258 |
| 9+015.00 | 500178.912 | 522790.237 |
| 9+020.00 | 500182.000 | 522794.169 |
| 9+025.00 | 500185.089 | 522798.101 |
| 9+030.00 | 500188.178 | 522802.033 |
| 9+035.00 | 500191.267 | 522805.965 |
| 9+040.00 | 500194.355 | 522809.897 |
| 9+045.00 | 500197.444 | 522813.829 |
| 9+050.00 | 500200.533 | 522817.760 |
| 9+055.00 | 500203.622 | 522821.692 |
| 9+060.00 | 500206.710 | 522825.624 |
| 9+065.00 | 500209.799 | 522829.556 |
| 9+070.00 | 500212.957 | 522833.431 |
| 9+075.00 | 500216.562 | 522836.890 |
| 9+080.00 | 500220.611 | 522839.817 |
| 9+085.00 | 500225.026 | 522842.155 |
| 9+090.00 | 500229.722 | 522843.859 |
| 9+095.00 | 500234.607 | 522844.913 |
| 9+100.00 | 500239.534 | 522845.759 |
| 9+105.00 | 500244.465 | 522846.590 |
| 9+110.00 | 500249.436 | 522847.116 |
| 9+115.00 | 500254.431 | 522847.162 |
| 9+120.00 | 500259.318 | 522846.162 |
| 9+125.00 | 500263.831 | 522844.037 |
| 9+130.00 | 500267.716 | 522840.908 |
| 9+135.00 | 500270.910 | 522837.065 |
| 9+140.00 | 500274.021 | 522833.151 |
| 9+145.00 | 500277.132 | 522829.236 |
| 9+150.00 | 500280.243 | 522825.322 |
| 9+155.00 | 500283.354 | 522821.408 |
| 9+160.00 | 500286.466 | 522817.494 |
| 9+165.00 | 500289.585 | 522813.586 |
| 9+170.00 | 500292.862 | 522809.810 |
| 9+175.00 | 500296.343 | 522806.222 |
| 9+180.00 | 500300.018 | 522802.833 |
| 9+185.00 | 500303.873 | 522799.650 |
| 9+190.00 | 500307.786 | 522796.537 |
| 9+195.00 | 500311.699 | 522793.424 |
| 9+200.00 | 500315.612 | 522790.311 |
| 9+205.00 | 500319.525 | 522787.198 |
| 9+210.00 | 500323.437 | 522784.086 |
| 9+215.00 | 500327.312 | 522780.925 |
| 9+220.00 | 500331.055 | 522777.611 |
| 9+225.00 | 500334.656 | 522774.143 |
| 9+230.00 | 500338.137 | 522770.554 |
| 9+235.00 | 500341.715 | 522767.062 |
| 9+240.00 | 500345.436 | 522763.723 |
| 9+245.00 | 500349.293 | 522760.541 |
| 9+250.00 | 500353.275 | 522757.518 |
| 9+255.00 | 500357.295 | 522754.545 |
| 9+260.00 | 500361.315 | 522751.571 |
| 9+265.00 | 500365.335 | 522748.598 |
| 9+270.00 | 500369.354 | 522745.624 |
| 9+275.00 | 500373.374 | 522742.651 |
| 9+280.00 | 500377.450 | 522739.756 |
| 9+285.00 | 500381.621 | 522736.998 |
| 9+290.00 | 500385.881 | 522734.381 |
| 9+295.00 | 500390.224 | 522731.904 |
| 9+300.00 | 500394.523 | 522729.351 |

SETTING OUT DATA OF C/L

CONSTRUCTION OF RAJA MAWATHA EXTENTION ROAD FROM
KETAWALA TO MASPENNA
SECTION FROM CH (7+500 - 9+300)Km

PLAN AND SETTING OUT DATA - CH(9+000-9+300)Km SCALE - 1:1000

| REV | DESCRIPTION | BY | DATE |
|-----|-------------|----|------|
| | | | |
| | | | |
| | | | |
| | | | |


DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS & TRANSPORT

SURVEYED & PLOTTED :
DESIGNED : K.A.S.B. KUMARA ARACHCHI
DRAWN : B.K. RANASINGHE

C.E. (DESIGN): K.A.S.B. KUMARA ARACHCHI
D.D(DESIGN): L.V.S. WEERAKOON

DESIGN OFFICE (C.P.),
ROAD DEVELOPMENT AUTHORITY
6B GANNORUWA, PERADENIYA.
TEL : 0812388997 FAX : 0812388997 email : docpkandy@gmail.com

CHECKED : R.I.P. SOMARATHNA
DATE : 2023-03-23
DRG No. : DD/D/UYA/H/1267/1 2/1/06(06)



| CHAINAGE | 7+500 | 7+510 | 7+520 | 7+530 | 7+540 | 7+550 | 7+560 | 7+570 | 7+580 | 7+590 | 7+600 | 7+610 | 7+620 | 7+630 | 7+640 | 7+650 | 7+660 | 7+670 | 7+680 | 7+690 | 7+700 | 7+710 | 7+720 | 7+730 | 7+740 | 7+750 | 7+760 | 7+770 | 7+780 | 7+790 | 7+800 |
|-----------------------|------------------------------|---------|------------------------------|---------|------------------|-------------------------------|------------------------|---------|------------------------------|----------|----------------|-------------------------------|----------------|----------|-------------------------------|------------------------|----------------|------------------------------|----------------|------------------------------|----------------|------------------------------|----------------|------------------------------|----------------|----------|----------------|---------|---------|---------|---------|
| FINISHED GROUND LEVEL | 571.000 | 571.000 | 571.001 | 571.006 | 571.017 | 571.033 | 570.969 | 570.889 | 570.804 | 569.804 | 568.804 | 567.731 | 566.883 | 565.979 | 565.076 | 564.341 | 563.783 | 563.431 | 563.255 | 563.235 | 563.184 | 563.084 | 562.937 | 562.722 | 562.487 | 562.270 | 562.107 | 562.000 | 561.950 | 561.940 | 561.932 |
| EXISTING GROUND LEVEL | 567.659 | 570.178 | 570.855 | 572.289 | 573.479 | 574.989 | 575.553 | 575.120 | 575.206 | 576.423 | 575.826 | 577.560 | 578.889 | 579.142 | 578.084 | 575.455 | 578.023 | 578.535 | 577.561 | 578.657 | 574.719 | 572.741 | 572.089 | 571.520 | 571.231 | 572.587 | 571.684 | 571.808 | 571.202 | 569.848 | 569.183 |
| HORIZONTAL GEOMETRY | R=41.00 7+437.20-7+524.69 | | R=60.00 7+524.69-7+570.87 | | | R=252.00 7+570.87-7+603.74 | | | R=90.00 7+603.74-7+630.06 | | | R=232.00 7+630.06-7+690.66 | | | R=150.00 7+690.66-7+736.36 | | | R=19.00 7+736.36-7+758.51 | | R=15.00 7+758.51-7+782.58 | | R=23.00 7+782.58-7+805.95 | | R=85.00 7+805.95-7+845.45 | | | | | | | |
| VERTICAL GEOMETRY | G=0.00% | | V.C.L.=30.00 K=177.22 | | G=0.17% | | V.C.L.=50.00 K=6.89 | | | G=-7.08% | | V.C.L.=40.00 K=17.85 | | G=-9.32% | | V.C.L.=50.00 K=5.37 | | G=-0.01% | | V.C.L.=40.00 K=17.17 | | G=-2.34% | | V.C.L.=40.00 K=17.71 | | G=-0.08% | | | | | |
| SUPERELEVATION | +4.0% -4.0% | | +5.0% -5.0% | | +5.33% -5.33% | | +2.5% -2.5% | | +2.5% -2.5% | | +2.5% -2.5% | | +2.5% -2.5% | | +2.5% -2.5% | | +2.5% -2.5% | | +2.5% -2.5% | | +2.5% -2.5% | | +2.5% -2.5% | | +2.5% -2.5% | | +2.5% -2.5% | | | | |

LONGITUDINAL SECTION
 SCALE : HORIZONTAL 1: 1000
 VERTICAL 1: 200

CONSTRUCTION OF RAJA MAWATHA EXTENTION ROAD FROM KETAWALA TO MASPENNA SECTION FROM CH (7+500 - 9+300)Km

PROFILE - CH(7+500-7+800)Km SCALE -1:1000

| REV | DESCRIPTION | BY | DATE |
|-----|-------------|----|------|
| | | | |
| | | | |
| | | | |
| | | | |

DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
 MINISTRY OF HIGHWAYS & TRANSPORT

SURVEYED & PLOTTED :
 K.A.S.B. KUMARA ARACHCHI

DESIGNED :
 K.A.S.B. KUMARA ARACHCHI

DRAWN :
 B.K. RANASINGHE

C.E (DESIGN):
 K.A.S.B. KUMARA ARACHCHI


D.D(DESIGN):
 L.V.S. WEERAKOON

DESIGN OFFICE (C.P.),
 ROAD DEVELOPMENT AUTHORITY
 6B, GANNORUWA, PERADENIYA.
 TEL : 0812388997 FAX : 0812388997 email : docpkandy@gmail.com

CHECKED :
 R.I.P. SOMARATHNA

DATE : 2023-03-23

DRG.No. : DD/D/UVA/H/1267/1 2/2/01(06)



| CHAINAGE | 7+800 | 7+810 | 7+820 | 7+830 | 7+840 | 7+850 | 7+860 | 7+870 | 7+880 | 7+890 | 7+900 | 7+910 | 7+920 | 7+930 | 7+940 | 7+950 | 7+960 | 7+970 | 7+980 | 7+990 | 8+000 | 8+010 | 8+020 | 8+030 | 8+040 | 8+050 | 8+060 | 8+070 | 8+080 | 8+090 | 8+100 | |
|-----------------------|------------------------------|---------|------------------------------|---------|---------|---------|------------------------------|---------|------------------------|---------|--------------------|---------|------------------------------|---------|------------------------------|---------|-------------------------------|---------|---------|---------|------------------------------|---------|------------------------|---------|---------|---------|---------|---------|---------|---------|---------|---------|
| FINISHED GROUND LEVEL | 561.836 | 561.832 | 561.924 | 561.916 | 561.899 | 561.849 | 561.709 | 561.480 | 561.161 | 560.795 | 560.429 | 560.089 | 559.801 | 559.656 | 559.627 | 559.627 | 559.627 | 559.783 | 560.378 | 561.411 | 562.734 | 564.062 | 565.391 | 566.719 | 567.883 | 568.753 | 569.047 | 568.844 | 568.231 | 567.554 | 566.753 | 566.298 |
| EXISTING GROUND LEVEL | 569.163 | 570.222 | 568.097 | 566.973 | 566.758 | 565.586 | 564.547 | 565.150 | 562.293 | 561.662 | 560.967 | 561.342 | 561.287 | 561.216 | 558.613 | 556.127 | 557.619 | 560.984 | 563.863 | 565.379 | 567.098 | 568.961 | 570.639 | 572.000 | 573.123 | 573.779 | 573.034 | 571.896 | 571.181 | 570.651 | 569.002 | 568.298 |
| HORIZONTAL GEOMETRY | R=23.00 7+802.58-7+833.36 | | R=60.00 7+803.36-7+845.45 | | | | R=70.00 7+875.09-7+929.62 | | | | | | R=10.50 7+929.62-7+943.53 | | R=14.00 7+953.90-7+977.54 | | R=100.00 8+023.89-8+048.60 | | | | R=40.00 8+072.16-8+104.60 | | | | | | | | | | | |
| VERTICAL GEOMETRY | G=-0.08% | | V.C.L.=40.00 K=11.18 | | | | G=-3.66% | | V.C.L.=30.00 K=8.20 | | G=0.00% | | V.C.L.=30.00 K=2.26 | | G=13.28% | | V.C.L.=40.00 K=2.01 | | | | G=6.57% | | V.C.L.=30.00 K=7.09 | | | | | | | | | |
| SUPERELEVATION | r=+2.5% r=-2.5% | | r=+2.5% r=-2.5% | | | | r=+2.5% r=-2.5% | | r=+2.5% r=-2.5% | | r=+2.5% r=-2.5% | | r=+2.5% r=-2.5% | | r=+2.5% r=-2.5% | | r=+4.0% r=-4.0% | | | | r=+4.0% r=-4.0% | | | | | | | | | | | |

LONGITUDINAL SECTION

SCALE: HORIZONTAL 1:1000
VERTICAL 1:200

CONSTRUCTION OF RAJA MAWATHA EXTENTION ROAD FROM KETAWALA TO MASPENNA SECTION FROM CH (7+500 - 9+300)Km

PROFILE - CH(7+800-8+100)Km

SCALE -1:1000

| REV | DESCRIPTION | BY | DATE |
|-----|-------------|----|------|
| | | | |
| | | | |
| | | | |
| | | | |



DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS & TRANSPORT



DESIGN OFFICE (C.P.),
ROAD DEVELOPMENT AUTHORITY
6B, GANNORUWA, PERADENIYA,
TEL : 0812388997 FAX : 0812388997 email : docpkandy@gmail.com

SURVEYED & PLOTTED :

DESIGNED :
K.A.S.B. KUMARA ARACHCHI


DRAWN :
B.K. RANASINGHE

CHECKED :
R.I.P. SOMARATHNA

C.E. (DESIGN) :
K.A.S.B. KUMARA ARACHCHI

D.D.(DESIGN)
L.V.S. WEERAKOON

DATE : 2023-03-23
DRG.No. : DD/D/UVA/H/1267/1 2/2/02(06)



| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
|-----------------------|------------------------------|---------|------------------------------|---------|-------------------------|---------|-----------|---------|------------------------|---------|----------|---------|-------------------------|---------|----------|---------|-------------------------------|---------|----------|---------|-------------------------------|---------|----------|---------|-------------------------------|---------|------------------------|---------|------------------------------|---------|---------|---------|---------|---------|
| CHAINAGE | 8+100 | 8+110 | 8+120 | 8+130 | 8+140 | 8+150 | 8+160 | 8+170 | 8+180 | 8+190 | 8+200 | 8+210 | 8+220 | 8+230 | 8+240 | 8+250 | 8+260 | 8+270 | 8+280 | 8+290 | 8+300 | 8+310 | 8+320 | 8+330 | 8+340 | 8+350 | 8+360 | 8+370 | 8+380 | 8+390 | 8+400 | | | |
| FINISHED GROUND LEVEL | 567.171 | 566.753 | 565.810 | 564.746 | 563.887 | 562.802 | 561.554 | 560.521 | 559.532 | 558.655 | 557.880 | 557.238 | 556.656 | 556.060 | 555.448 | 554.814 | 554.111 | 553.327 | 552.461 | 551.521 | 550.561 | 549.592 | 548.615 | 547.638 | 546.657 | 545.689 | 544.806 | 543.889 | 542.882 | 541.818 | 540.795 | 539.810 | 538.810 | 537.810 |
| EXISTING GROUND LEVEL | 568.002 | 568.062 | 568.372 | 568.649 | 568.478 | 568.401 | 568.818 | 569.082 | 569.338 | 569.157 | 568.888 | 568.788 | 568.283 | 568.073 | 568.373 | 568.803 | 569.038 | 569.320 | 569.607 | 569.723 | 569.817 | 569.025 | 568.420 | 568.041 | 567.487 | 566.772 | 566.708 | 566.883 | 567.882 | 568.795 | 569.410 | 569.810 | 569.810 | |
| HORIZONTAL GEOMETRY | R=40.00 8+121.16-8+104.50 | | R=60.00 8+122.24-8+198.07 | | | | | | | | | | | | | | R=600.00 8+218.40-8+267.22 | | | | R=200.00 8+267.22-8+297.20 | | | | R=200.00 8+297.20-8+334.51 | | | | R=18.00 8+365.83-8+389.39 | | | | | |
| VERTICAL GEOMETRY | V.C.L.=30.00 K=7.09 | | G=-10.80% | | V.C.L.=30.00 K=59.16 | | G=-10.29% | | V.C.L.=40.00 K=8.87 | | G=-5.78% | | V.C.L.=30.00 K=60.14 | | G=-6.28% | | V.C.L.=40.00 K=12.29 | | G=-9.54% | | V.C.L.=30.00 K=117.11 | | G=-9.79% | | | | V.C.L.=40.00 K=4.08 | | G=0.00% | | | | | |
| SUPERELEVATION | r=+2.5% | | r=-2.5% | | r=+2.5% | | r=-2.5% | | r=+2.5% | | r=-2.5% | | r=+2.5% | | r=-2.5% | | r=+2.5% | | r=-2.5% | | r=+2.5% | | r=-2.5% | | r=+2.5% | | r=-2.5% | | r=+2.5% | | r=-2.5% | | | |

LONGITUDINAL SECTION
SCALE: HORIZONTAL 1: 1000
VERTICAL 1: 200

CONSTRUCTION OF RAJA MAWATHA EXTENTION ROAD FROM KETAWALA TO MASPENNA SECTION FROM CH (7+500 - 9+300)Km

PROFILE - CH(8+100-8+400)Km SCALE: 1: 1000

| REV | DESCRIPTION | BY | DATE |
|-----|-------------|----|------|
| | | | |
| | | | |

DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS & TRANSPORT

SURVEYED & PLOTTED: K.A.S.B. KUMARA ARACHCHI

DESIGNED: K.A.S.B. KUMARA ARACHCHI

DRAWN: B.K. RANASINGHE

C.E. (DESIGN): K.A.S.B. KUMARA ARACHCHI


D.D. (DESIGN): L.V.S. WEERAKOON

CHECKED: R.I.P. SOMARATHNA

DATE: 2023-03-23

DRG.No.: DD/D/UVA/H/1267/1.2/2/03(06)

DESIGN OFFICE (C.P.), ROAD DEVELOPMENT AUTHORITY, 6B, GANNORUWA, PERADENIYA. TEL: 0812388997 FAX: 0812388997 email: docpkandy@gmail.com



| CHAINAGE | 8+400 8+410 8+420 8+430 8+440 8+450 8+460 8+470 8+480 8+490 8+500 8+510 8+520 8+530 8+540 8+550 8+560 8+570 8+580 8+590 8+600 8+610 8+620 8+630 8+640 8+650 8+660 8+670 8+680 8+690 8+700 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
|-----------------------|--|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|
| FINISHED GROUND LEVEL | 544.016 | 544.016 | 544.016 | 544.016 | 544.016 | 544.016 | 544.016 | 544.145 | 544.532 | 545.178 | 546.083 | 547.117 | 548.151 | 549.173 | 549.869 | 550.457 | 550.639 | 550.528 | 550.332 | 550.139 | 549.949 | 549.803 | 549.709 | 549.669 | 549.677 | 549.694 | 549.712 | 549.729 | 549.747 | 549.764 | 549.780 | 549.787 |
| EXISTING GROUND LEVEL | 538.410 | 536.784 | 536.049 | 535.182 | 537.784 | 540.234 | 542.254 | 543.689 | 545.164 | 546.577 | 547.854 | 548.456 | 549.111 | 549.881 | 550.549 | 551.776 | 550.747 | 551.418 | 550.059 | 550.084 | 548.808 | 548.600 | 549.684 | 549.937 | 550.862 | 548.750 | 548.006 | 550.785 | 548.424 | 548.453 | 548.547 | |
| HORIZONTAL GEOMETRY | <p>R=24.00 8+457.68-8+503.66</p> <p>R=400.00 8+526.82-8+586.16</p> <p>R=68.00 8+595.16-8+620.33</p> <p>R=90.00 8+620.33-8+645.58</p> <p>R=60.00 8+650.57-8+668.84</p> <p>R=60.00 8+691.70-8+731.82</p> | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| VERTICAL GEOMETRY | <p>G=0.00%</p> <p>V.C.L.=40.00 K=3.87</p> <p>G=10.34%</p> <p>V.C.L.=40.00 K=3.26</p> <p>G=-1.94%</p> <p>V.C.L.=40.00 K=18.93</p> <p>G=0.18%</p> <p>V.C.L.=40.00 K=440.43</p> | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| SUPERELEVATION | <p>l&r=-2.5%</p> <p>l=+2.5% r=-2.5%</p> <p>l=+2.5% r=-2.5%</p> <p>l=+2.5% r=-2.5%</p> <p>l=+2.5% r=-2.5%</p> <p>l=+2.5% r=-2.5%</p> | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |

LONGITUDINAL SECTION
 SCALE : HORIZONTAL 1: 1000
 VERTICAL 1: 200

CONSTRUCTION OF RAJA MAWATHA EXTENTION ROAD FROM KETAWALA TO MASPENNA SECTION FROM CH (7+500 - 9+300)Km

PROFILE - CH(8+400-8+700)Km SCALE -1:1000

| REV | DESCRIPTION | BY | DATE |
|-----|-------------|----|------|
| | | | |
| | | | |

DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
 MINISTRY OF HIGHWAYS & TRANSPORT

SURVEYED & PLOTTED : K.A.S.B. KUMARA ARACHCHI

DESIGNED : K.A.S.B. KUMARA ARACHCHI

DRAWN : B.K. RANASINGHE

C.E. (DESIGN) : K.A.S.B. KUMARA ARACHCHI


D.D. (DESIGN) : L.V.S. WEERAKOON

DESIGN OFFICE (C.P.),
 ROAD DEVELOPMENT AUTHORITY
 6B, GANNORUWA, PERADENIYA
 TEL : 0812388997 FAX : 0812388997 email : docpkandy@gmail.com

CHECKED : R.I.P. SOMARATHNA

DATE : 2023-03-23

DRG.No. : DD/D/UVA/JH/1267/1 2/2/04(06)



| CHAINAGE | 8+700 | 8+710 | 8+720 | 8+730 | 8+740 | 8+750 | 8+760 | 8+770 | 8+780 | 8+790 | 8+800 | 8+810 | 8+820 | 8+830 | 8+840 | 8+850 | 8+860 | 8+870 | 8+880 | 8+890 | 8+900 | 8+910 | 8+920 | 8+930 | 8+940 | 8+950 | 8+960 | 8+970 | 8+980 | 8+990 | 9+000 | | |
|-----------------------|------------------------------|---------|--------------------|-------------------------------|-------------------------|---------|------------------------------|---------|--------------------------|------------------------------|--------------------|---------|-------------------------------|---------|--------------------|-------------------------------|-------------------------|---------|------------------------------|---------|-------------------------|-------------------------------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|
| FINISHED GROUND LEVEL | 548.773 | 548.780 | 548.794 | 548.805 | 548.814 | 548.822 | 548.831 | 548.834 | 548.824 | 548.801 | 548.763 | 548.713 | 548.654 | 548.584 | 548.504 | 548.425 | 548.380 | 548.372 | 548.400 | 548.459 | 548.520 | 548.578 | 548.588 | 548.563 | 548.478 | 548.344 | 548.189 | 548.054 | 548.808 | 548.765 | 548.640 | 548.537 | 548.483 |
| EXISTING GROUND LEVEL | 548.547 | 548.512 | 548.445 | 548.717 | 548.319 | 551.122 | 548.520 | 548.634 | 548.634 | 548.572 | 550.855 | 548.972 | 548.802 | 550.298 | 548.321 | 548.373 | 548.672 | 550.028 | 548.092 | 548.648 | 548.951 | 548.546 | 548.146 | 549.868 | 549.311 | 548.428 | 550.012 | 548.241 | 549.073 | 548.683 | 548.468 | 548.249 | 548.483 |
| HORIZONTAL GEOMETRY | R=60.00 8+691.70-8+731.82 | | | R=121.15 8+770.84-8+790.75 | | | R=65.00 8+790.76-8+817.43 | | | R=38.00 8+838.53-8+869.81 | | | R=250.00 8+869.81-8+889.51 | | | R=120.00 8+928.08-8+969.79 | | | R=60.00 8+969.79-8+991.50 | | | R=200.00 8+991.50-9+015.49 | | | | | | | | | | | |
| VERTICAL GEOMETRY | V.C.L.=40.00 K=440.43 | | G=0.08% | | V.C.L.=40.00 K=72.88 | | G=-0.46% | | V.C.L.=40.00 K=100.04 | | G=-0.86% | | V.C.L.=40.00 K=27.15 | | G=0.61% | | V.C.L.=40.00 K=19.40 | | G=-1.45% | | V.C.L.=40.00 K=47.22 | | | | | | | | | | | | |
| SUPERELEVATION | i=+2.5% i=-2.5% | | i=+2.5% i=-2.5% | | i=+2.5% i=-2.5% | | i=+2.5% i=-2.5% | | i=+2.5% i=-2.5% | | i=+2.5% i=-2.5% | | i=+2.5% i=-2.5% | | i=+2.5% i=-2.5% | | i=+2.5% i=-2.5% | | i=+2.5% i=-2.5% | | i=+2.5% i=-2.5% | | | | | | | | | | | | |

LONGITUDINAL SECTION
SCALE: HORIZONTAL 1: 1000
VERTICAL 1: 200

CONSTRUCTION OF RAJA MAWATHA EXTENTION ROAD FROM KETAWALA TO MASPENNA SECTION FROM CH (7+500 - 9+300)Km

| REV | DESCRIPTION | BY | DATE |
|-----|-------------|----|------|
| | | | |

DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS & TRANSPORT


SURVEYED & PLOTTED :
DESIGNED : K.A.S.B. KUMARA ARACHCHI
DRAWN : B.K. RANASINGHE

C.E (DESIGN) : K.A.S.B. KUMARA ARACHCHI
D.D(DESIGN) : L.V.S. WEERAKOON

DESIGN OFFICE (C.P.),
ROAD DEVELOPMENT AUTHORITY
6B, GANNORUWA, PERADENIYA.
TEL : 0812388997 FAX : 0812388997 email : docpkandy@gmail.com

CHECKED : R.I.P. SOMARATHNA
DATE : 2023-03-23
DRG.No. : DD/D/UVA/H/1267/1.2/205(06)

PROFILE CH(8+700-9+000)Km SCALE -1 1000




| CHAINAGE | 9+000 | 9+010 | 9+020 | 9+030 | 9+040 | 9+050 | 9+060 | 9+070 | 9+080 | 9+090 | 9+100 | 9+110 | 9+120 | 9+130 | 9+140 | 9+150 | 9+160 | 9+170 | 9+180 | 9+190 | 9+200 | 9+210 | 9+220 | 9+230 | 9+240 | 9+250 | 9+260 | 9+270 | |
|-----------------------|--|---------|------------------------------|---------|---------|---------|------------------------------|---------|---------------------------------|---------|---------------------------------|---------|---------------------|-------------------------------|-------------------------|-------------------------------|---------------------|-------------------------------|-------------------------|---------|---------------------|---------|--------------------------|---------|---------|---------|---------|---------|---------|
| FINISHED GROUND LEVEL | 548.588 | 548.537 | 548.454 | 548.390 | 548.330 | 548.268 | 548.201 | 548.157 | 548.130 | 548.127 | 548.187 | 548.248 | 548.331 | 548.435 | 548.558 | 548.688 | 548.740 | 548.775 | 548.772 | 548.731 | 548.673 | 548.633 | 548.613 | 548.613 | 548.627 | 548.643 | 548.664 | 548.688 | 548.718 |
| EXISTING GROUND LEVEL | 548.248 | 548.188 | 548.257 | 548.239 | 548.448 | 548.288 | 548.011 | 547.880 | 547.688 | 547.874 | 548.046 | 548.283 | 548.535 | 548.804 | 549.295 | 549.742 | 549.111 | 550.257 | 548.485 | 548.428 | 548.234 | 548.408 | 548.605 | 552.120 | 549.933 | 548.845 | 548.341 | 548.685 | 548.688 |
| HORIZONTAL GEOMETRY | R=200.00 8+991.50-9+015.59 | | R=36.00 9+067.46-9+093.91 | | | | R=60.00 9+103.03-9+117.03 | | R=21.00 9+112.96-9+132.14 | | R=120.00 9+160.19-9+187.46 | | | R=280.00 9+201.46-9+226.42 | | R=250.00 9+226.42-9+257.48 | | R=450.00 9+276.61-9+305.30 | | | | | | | | | | | |
| VERTICAL GEOMETRY | V.C.L.=40.00 K=2.5 | | G=-0.61% | | | | V.C.L.=40.00 K=41.46 | | G=-0.36% | | V.C.L.=40.00 K=45.26 | | G=1.24% | | V.C.L.=50.00 K=26.51 | | G=-0.64% | | V.C.L.=40.00 K=50.92 | | G=0.14% | | V.C.L.=80.00 K=242.09 | | | | | | |
| SUPERELEVATION | LHS i=+2.5% 9+000.30 9+008.59 | | i=-2.5% 9+027.59 | | | | i=+4.0% 9+051.46 | | i=-4.0% 9+068.82 9+075.46 | | i=+2.5% 9+124.14 9+129.68 | | i=-2.5% 9+148.19 | | i=+2.5% 9+166.19 | | i=-2.5% 9+185.46 | | i=+2.5% 9+203.46 | | i=-2.5% 9+217.42 | | i=+2.5% 9+235.42 | | i=-2.5% | | | | |

LONGITUDINAL SECTION
SCALE : HORIZONTAL 1: 1000
VERTICAL 1: 200


CONSTRUCTION OF RAJA MAWATHA EXTENTION ROAD FROM KETAWALA TO MASPENNA SECTION FROM CH (7+500 - 9+300)Km

PROFILE - CH(9+000-9+300)Km SCALE -1:1000

| REV | DESCRIPTION | BY | DATE |
|-----|-------------|----|------|
| | | | |
| | | | |


DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS & TRANSPORT


SURVEYED & PLOTTED :
 DESIGNED : K.A.S.B. KUMARA ARACHCHI
 DRAWN : B.K. RANASINGHE
 C.E (DESIGN) : K.A.S.B. KUMARA ARACHCHI
 D.D(DESIGN) : L.V.S.WEERAKOON


 DESIGN OFFICE (C.P.),
 ROAD DEVELOPMENT AUTHORITY
 6B, GANNORUWA, PERADENIYA
 TEL : 0812388997 FAX : 0812388997 email : docpkandy@gmail.com

CHECKED : R.I.P. SOMARATHNA
 DATE : 2023-03-23
 DRG.No. : DD/DI/JVA/H/1267/11.2/2/06(06)

***CONSTRUCTION OF RAJA MAWATHA EXTENTION ROAD FROM
KETAWALA TO MASPANNA (CH 7+560- CH9+300km)
: GEOMETRIC DESIGN DRAWINGS ,
1.3 - TYPICAL ROAD CROSS SECTIONS***

- LEGEND:**
- C/L: New Centre Line
 - Asphalt Concrete
 - Dence Graded Aggregate Base Course
 - Sub base (CBR ≥ 30%)
 - Sub base (CBR ≥ 15%)
 - Shoulder Fill
 - Embankment type 1
 - Embankment type 11



TYPICAL CROSS SECTION

CONSTRUCTION OF RAJA MAWATHA EXTENSION ROAD FROM KETAWALA TO MASPANNA. (FROM CH7+560 TO 9+300 km)

TYPICAL CROSS SECTION

SCALC -

| REV | DESCRIPTION | BY | DATE |
|-----|-------------|----|------|
| | | | |
| | | | |
| | | | |
| | | | |



DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS AND TRANSPORT.



DESIGN OFFICE (C.P.),
ROAD DEVELOPMENT AUTHORITY
S.W.R.D. BANDARANAYAKE MAWATHA, KANDY
TEL : 0812234267 FAX : 0812234267 email : docpkandy@gmail.com

SURVEYED & PLOTTED :

DESIGNED :
K.A.S.B.KUMARA ARACHCHI

DRAWN :
S.M.S.T.THILAKARATHNA

CHECKED :
R.I.P.SOMARATHNA

C.E. (DESIGN):
K.A.S.B.KUMARAARACHCHI

D.D. (DESIGN):
L.V.S.WEERAKOON

DATE : 23-13-2023

DRG No. : DD/D/UVVA/H/TY.CS/1267/01/(01)

***CONSTRUCTION OF RAJA MAWATHA EXTENTION ROAD FROM
KETAWALA TO MASPANNA (CH 7+560- CH9+300km)
: GEOMETRIC DESIGN DRAWINGS,
1.4 - PAVEMENT DESIGN THICKNESSES***

CONSTRUCTION OF RAJA MAWATHA EXTENSION ROAD FROM KETAWALA TO MASPANNA.(FROM CH7+560 TO 9+000)km

| No | REGION | | DESIGN THICKNESS OF PAVEMENT LAYERS(mm) | | | |
|----|--------|-------|---|--------------------------------------|----------------------------------|-----------------------------------|
| | | | RECONSTRUCTIONS | | | |
| | FROM | TO | WEARING COURSE | DENSE GRADED AGGREGATE BASE(CBR>=80) | SOIL SUB BASE TYPE 1 (CBR ≥ 30) | SOIL SUB BASE TYPE 11 (CBR ≥ 15) |
| 1 | 7+560 | 9+300 | 50 | 200 | 200 | 225 |

**CONSTRUCTION OF RAJA MAWATHA EXTENSION ROAD FROM KETAWALA TO MASPANNA.
FROM (CH7+560 TO 9+300 km)**

PAVEMENT DESIGN THICKNESSES

SCALE -

| REV | DESCRIPTION | BY | DATE |
|-----|--------------------------|----|------------|
| R1 | VERTICAL PROFILE CHANGED | | 28-11-2011 |
| | | | |
| | | | |
| | | | |
| | | | |



DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS AND TRANSPORT.



DESIGN OFFICE (C.P.),
ROAD DEVELOPMENT AUTHORITY
6B, GANNORUWA, PERADENIYA.
TEL : 0812388997 FAX : 0812388997 email : docpkandy@gmail.com

SURVEYED & PLOTTED :

DESIGNED :
K.A.S.B.KUMARAARACHCHI

DRAWN :
S.M.S.T.THILAKARATHNA

CHECKED :
R.P.I.SOMARATHNA

C.E. (DESIGN) :
K.A.S.B.KUMARA ARACHCHI

D.D.(DESIGN):
L.V.S.WEERAKOON

DATE : 23 -03- 2023

DRG.No. : DD/D/UVVA/H/1267/1.6/01(01)

***CONSTRUCTION OF RAJA MAWATHA EXTENTION ROAD FROM
KETAWALA TO MASPANNA (CH 7+560- CH9+300km)
: GEOMETRIC DESIGN DRAWINGS,
1.5 - STRUCTURES***

| GABION WALL | | | |
|---------------|-----|-----|-----------------|
| CHAINAGE | LHS | RHS | TYPICAL SECTION |
| 8+036 - 8+081 | 45m | - | TYPE S.B -1 |
| 8+081 - 8+110 | 29m | - | TYPE S.B -2 |
| 8+140 - 8+230 | 90m | - | TYPE S.B -1 |
| 8+230 - 8+270 | 20m | - | TYPE S.B -2 |

| MASS CONCRETE RETAINING WALLS | | | |
|-------------------------------|-----|-----|-----------------|
| CHAINAGE | LHS | RHS | TYPICAL SECTION |
| 7+590 - 7+610 | 20m | - | M.C.R- 03 |
| 7+700 - 7+730 | 30m | - | M.C.R- 05 |
| 7+790 - 7+810 | 20m | - | M.C.R- 03 |
| 8+500 - 8+520 | 20m | - | M.C.R- 05 |
| 8+600 - 8+620 | 20m | - | M.C.R- 03 |
| 9+200 - 9+230 | 30m | - | M.C.R- 06 |

| BOX CULVERT TYPE | | |
|------------------|-----------|------------------------|
| CHAINAGE | SIZE | TYPICAL SECTION |
| 8+100 | 1.5 x 1.5 | BOX CULVERT/ M.C.R- 02 |
| 8+020 | 1.5 x 1.5 | BOX CULVERT/ M.C.R- 02 |

**CONSTRUCTION OF RAJAMAWATHA EXTENSION ROAD FROM KETAWALA TO MASPANNA.
(FROM CH 07+560 TO 09+300 km)**

DETAILS OF WALL AND CULVERT

SCALE - 1:50

| REV | DESCRIPTION | BY | DATE |
|-----|-------------|----|------|
| | | | |
| | | | |
| | | | |
| | | | |



DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS AND TRANSPORT



DESIGN OFFICE (C.P.),
ROAD DEVELOPMENT AUTHORITY
06B, SAMAGI NIWASA, GANNORUWA, PERADENIYA.
TEL : 0812234267 FAX : 0812234267 email : dacp@rda.gov.lk

SURVEYED & PLOTTED :

DESIGNED :
K.A.S.B.KUMARAARACHCI

DRAWN :
JAGATH C RAJAPAKSE


CHECKED :
R.I.P.SOMARATHNA

C.E. (DESIGN) :
K.A.S.B.KUMARAARACHCI

D.D.(DESIGN)
L.V.S.WEERAKOON

DATE : 23-03-2023

DRG.No. : DD/DCP/UVA/STR/1267/1.5/01-07



GENERAL NOTES

(a) ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE SPECIFIED

(b) ALL MATERIALS AND WORKMANSHIP ARE TO BE IN ACCORDANCE WITH REQUIREMENT OF THE SPECIFICATION

(c) POROUS BACKFILL TO BE PROVIDED ALONG THE ENTIRE LENGTH OF THE WALL AS INDICATED

(d) WEEP HOLES TO BE PROVIDED AT 1500mm C/C STRAGGERED USING 75mm DIA. PVC PIPES

(e) EXPANSION JOINT TO BE PROVIDED AT EVERY 5m INTERVAL USING THERMOFORM

CONCRETE

USE FOLLOWING CONCRETE GRADES FOR STRUCTURE OR PART OF A STRUCTURE MENTIONED BELOW WITH REQUIREMENT OF THE STANDARD SPECIFICATION

(a) SCREED - GR. 15/37.5

(b) FOUNDATION BASE - GR. 25/19

(c) SUB STRUCTURE - GR. 15/37.5

REINFORCEMENT

(a) ALL BARS MARKED "Y" SHALL BE HIGH YIELD DEFORMED BARS OF YIELD STRENGTH NOT LESS THAN 460N/mm²

(b) BARS OF CUT LENGTH LARGER THAN THE SUPPLIED LENGTH TO BE LAPPED WITH LENGTH OF 50Ø, WHERE Ø IS THE DIAMETER AND LAPPING SHOULD BE STRAGGERED

(c) REINFORCEMENT BARS SHALL BE BENT ACCORDANCE WITH STANDARD SPECIFICATIONS

(d) CLEAR CONCRETE COVER FOR ALL REINFORCEMENT TO BE 50mm

FORM WORK


(a) TYPE OF FORM WORK FOR FOUNDATION SLAB TO BE ROUGH FINISH.

(b) TYPE OF FORM WORK FOR SUB STRUCTURE TO BE SMOOTH FINISH.

SPECIAL NOTES

(a) ALLOWABLE BEARING CAPACITY OF THE GROUND AND THE PASSIVE EARTH HEIGHT SHALL BE CHECKED BY THE ENGINEER

(b) M.C.R = MASS CONCRETE RETAINING WALL.



| RETAINING WALL TYPE | HEIGHT OF THE WALL ABOVE THE GROUND LEVEL (m) | ALLOWABLE BEARING STRENGTH OF SOIL SHOULD NOT BE LESS THAN (KN/m ²) | PASSIVE EARTH HEIGHT |
|---------------------|---|---|----------------------|
| M.C.R-1 | 1.0 | 75.00 | 0.5 |
| M.C.R-2 | 1.5 | 100.00 | 0.6 |
| M.C.R-3 | 2.0 | 140.00 | 0.7 |
| M.C.R-4 | 2.5 | 145.00 | 0.9 |
| M.C.R-5 | 3.0 | 155.00 | 1.0 |
| M.C.R-6 | 3.5 | 175.00 | 1.1 |
| M.C.R-7 | 4.0 | 185.00 | 1.2 |
| M.C.R-8 | 4.5 | 190.00 | 1.2 |
| M.C.R-9 | 5.0 | 200.00 | 1.2 |

CONSTRUCTION OF RAJAMAWATHA EXTENSION ROAD FROM KETAWALA TO MASPANNA (FROM CH 07+560 TO 09+300 km)

TYPICAL SECTION OF MASS CONCRETE RETAINING WALLS AND HEAD WALLS


| REV. | DESCRIPTION | BY | DATE |
|------|-------------|----|------|
| | | | |

DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS AND TRANSPORT





SURVEYED & PLOTTED : DESIGNED : A.G. ARIYAWANSA DRAWN : J.C. RAJAPAKSHA CHECKED : A.G. ARIYAWANSA

C.E. (DESIGN) : A.G. ARIYAWANSA D.D. (DESIGN) : L.V.S. WEERAKOON DATE : 23.03.2023

DRG No. : DD/DCP/UA/TP/1267/1.5/02-07




- GENERAL NOTES**
1. ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE STATED.
 2. THIS DRAWINGS TO SUIT SITE CONDITIONS SHALL BE DECIDED BY THE ENGINEER AT CONSTRUCTION STAGE.
 3. CONCRETE GRADE SHALL BE GR. 30/19
 4. REINFORCEMENT SHALL BE HOT ROLLED HIGH YIELD STEEL TO BS 4469 WITH MIN fy = 460 N/SQMM
 5. CLEAR COVER TO REINFORCEMENT SHALL BE 50 MIN.
 6. MINIMUM RADIUS FOR SCHEDULING 3Ø
 7. LAP LENGTH 5ØØ
 8. ANCHORAGE LENGTH 5ØØ



- SPECIAL NOTES**
1. h - DROP WALL HEIGHT.
 2. W - WIDTH OF OPENING
 3. H - HEIGHT OF OPENING
 4. Ts - TOP SLAB THICKNESS
 5. Tb - BOTTOM SLAB THICKNESS
 6. Tw - SIDE WALL THICKNESS
 7. Ti - MID WALL THICKNESS
 8. Tww - WING WALL THICKNESS

| CULVERT TYPE | INTERNAL DIMENSION | | CULVERT I.D NO | EARTH COVER (m) | SLAB THICKNESS (TS) | BASE THICKNESS (TB) | WALL THICKNESS EXT (TW) | WALL THICKNESS INT (TI) | REINFORCEMENT DETAILS | | | | | | | | | | | | | | | | | | |
|--------------|--------------------|------|----------------|-----------------|---------------------|---------------------|-------------------------|-------------------------|-----------------------|---------|---------|---------|---------|---------|---------|----------|---------|---------|---------|---------|---------|--|--|--|--|--|--|
| | W(m) | H(m) | | | | | | | a | b | c | d | e | f | g | j1-j2-j3 | m | n | p | q | s | | | | | | |
| SINGLE CELL | 1.0 | 1.0 | SC - 1 | - | 200 | 200 | 200 | - | T12-200 | T12-200 | T16-200 | T16-200 | T12-200 | T16-200 | T12-200 | T12-250 | T12-250 | T12-200 | T12-200 | T16-200 | | | | | | | |
| | 1.5 | 1.0 | SC - 2 | - | 200 | 200 | 200 | - | T12-150 | T12-150 | T16-150 | T16-150 | T12-150 | T16-150 | T12-150 | T12-250 | T12-250 | T12-150 | T12-150 | T16-150 | | | | | | | |
| | 2.0 | 1.0 | SC - 3 | - | 250 | 250 | 200 | - | T16-175 | T12-175 | T20-175 | T16-175 | T12-175 | T20-175 | T12-175 | T12-250 | T12-250 | T12-175 | T12-175 | T16-175 | | | | | | | |
| | 2.5 | 1.0 | SC - 4 | - | 225 | 225 | 200 | - | T16-150 | T12-150 | T20-150 | T16-150 | T12-150 | T20-150 | T12-150 | T12-250 | T12-250 | T12-150 | T12-150 | T16-150 | | | | | | | |
| | 1.0 | 1.5 | SC - 5 | - | 225 | 225 | 225 | - | T12-200 | T12-200 | T16-200 | T16-200 | T12-200 | T20-150 | T12-150 | T12-250 | T12-250 | T12-150 | T12-150 | T16-150 | | | | | | | |
| | 1.5 | 1.5 | SC - 6 | - | 200 | 200 | 200 | - | T12-150 | T12-150 | T16-150 | T16-150 | T12-150 | T16-150 | T12-150 | T12-250 | T12-250 | T12-150 | T12-150 | T16-150 | | | | | | | |
| | 2.0 | 1.5 | SC - 7 | - | 225 | 225 | 225 | - | T16-175 | T12-175 | T20-175 | T16-175 | T12-175 | T20-175 | T12-175 | T12-250 | T12-250 | T12-150 | T12-150 | T16-150 | | | | | | | |
| | 2.5 | 1.5 | SC - 8 | - | 225 | 225 | 225 | - | T16-150 | T12-150 | T20-150 | T16-150 | T12-150 | T20-150 | T12-150 | T12-250 | T12-250 | T12-175 | T12-175 | T16-175 | | | | | | | |
| | 1.0 | 2.0 | SC - 9 | - | 200 | 200 | 200 | - | T12-200 | T20-200 | T16-200 | T16-200 | T20-200 | T16-200 | T20-200 | T12-250 | T12-250 | T12-200 | T12-200 | T16-200 | | | | | | | |
| | 1.5 | 2.0 | SC - 10 | - | 200 | 200 | 200 | - | T12-150 | T12-150 | T16-150 | T16-150 | T12-150 | T16-150 | T20-150 | T12-250 | T12-250 | T12-200 | T12-200 | T16-200 | | | | | | | |
| | 2.0 | 2.0 | SC - 11 | - | 225 | 225 | 225 | - | T16-175 | T12-175 | T20-175 | T16-175 | T12-175 | T20-175 | T12-175 | T12-250 | T12-250 | T12-175 | T12-175 | T16-175 | | | | | | | |
| | 2.5 | 2.0 | SC - 12 | - | 225 | 225 | 225 | - | T16-150 | T12-150 | T20-150 | T16-150 | T12-150 | T20-150 | T12-150 | T12-250 | T12-250 | T12-175 | T12-175 | T16-175 | | | | | | | |
| | 1.0 | 2.5 | SC - 13 | - | 200 | 200 | 200 | - | T12-200 | T20-200 | T16-200 | T16-200 | T20-200 | T16-200 | T20-200 | T12-250 | T12-250 | T12-150 | T12-150 | T16-150 | | | | | | | |
| | 1.5 | 2.5 | SC - 14 | - | 200 | 200 | 200 | - | T12-150 | T12-150 | T16-150 | T16-150 | T12-150 | T16-150 | T12-150 | T12-250 | T12-250 | T12-150 | T12-150 | T16-150 | | | | | | | |
| | 2.0 | 2.5 | SC - 15 | - | 225 | 225 | 225 | - | T16-175 | T12-175 | T20-175 | T16-175 | T12-175 | T20-175 | T12-175 | T12-250 | T12-250 | T12-150 | T12-150 | T16-150 | | | | | | | |
| | 2.5 | 2.5 | SC - 16 | - | 225 | 225 | 225 | - | T16-150 | T12-150 | T20-150 | T16-150 | T12-150 | T20-150 | T12-150 | T12-250 | T12-250 | T12-175 | T12-175 | T16-175 | | | | | | | |
| SINGLE CELL | 2.0 | 2.0 | SCE - 1 | 0 - 2 | 250 | 250 | 250 | - | T12-150 | T12-150 | T16-150 | T16-150 | T12-150 | T16-150 | T12-150 | T12-250 | T12-250 | T12-150 | T12-150 | T16-150 | | | | | | | |
| | | | SCE - 2 | 2 - 4 | 300 | 300 | 300 | - | T16-175 | T12-175 | T20-175 | T16-175 | T12-175 | T20-175 | T12-175 | T12-250 | T12-250 | T12-150 | T12-150 | T16-150 | | | | | | | |
| | | | SCE - 3 | 4 - 6 | 350 | 350 | 350 | - | T16-150 | T12-150 | T20-150 | T16-150 | T12-150 | T20-150 | T12-150 | T12-250 | T12-250 | T12-175 | T12-175 | T16-175 | | | | | | | |
| | 3.0 | 2.0 | SCE - 4 | 0 - 2 | 300 | 300 | 300 | - | T12-150 | T12-150 | T16-150 | T16-150 | T12-150 | T16-150 | T12-150 | T12-250 | T12-250 | T12-150 | T12-150 | T16-150 | | | | | | | |
| | | | SCE - 5 | 2 - 4 | 350 | 350 | 350 | - | T16-175 | T12-175 | T20-175 | T16-175 | T12-175 | T20-175 | T12-175 | T12-250 | T12-250 | T12-150 | T12-150 | T16-150 | | | | | | | |
| | | | SCE - 6 | 4 - 6 | 400 | 400 | 400 | - | T16-150 | T12-150 | T20-150 | T16-150 | T12-150 | T20-150 | T12-150 | T12-250 | T12-250 | T12-150 | T12-150 | T16-150 | | | | | | | |
| | 3.0 | 3.0 | SCE - 7 | 0 - 2 | 300 | 300 | 300 | - | T12-150 | T12-150 | T16-150 | T16-150 | T12-150 | T16-150 | T20-150 | T12-150 | T12-250 | T12-250 | T12-150 | T12-150 | T16-150 | | | | | | |
| | | | SCE - 8 | 2 - 4 | 350 | 350 | 350 | - | T16-175 | T12-175 | T20-175 | T16-175 | T12-175 | T20-175 | T12-175 | T12-250 | T12-250 | T12-150 | T12-150 | T16-150 | | | | | | | |
| | | | SCE - 9 | 4 - 6 | 450 | 450 | 450 | - | T16-150 | T12-150 | T20-150 | T16-150 | T12-150 | T20-150 | T12-150 | T12-250 | T12-250 | T12-150 | T12-150 | T16-150 | | | | | | | |
| TWIN CELL | 2.0 | 2.0 | TCE - 1 | 0 - 2 | 250 | 250 | 250 | 250 | T12-150 | T12-150 | T16-150 | T16-150 | T12-150 | T16-150 | T12-150 | T12-250 | T12-250 | T12-150 | T12-150 | T16-150 | | | | | | | |
| | | | TCE - 2 | 2 - 4 | 300 | 300 | 300 | 300 | T16-175 | T12-175 | T20-175 | T16-175 | T12-175 | T20-175 | T12-175 | T12-250 | T12-250 | T12-150 | T12-150 | T16-150 | | | | | | | |
| | | | TCE - 3 | 4 - 6 | 400 | 400 | 400 | 350 | T16-150 | T12-150 | T20-150 | T16-150 | T12-150 | T20-150 | T12-150 | T12-250 | T12-250 | T12-175 | T12-175 | T16-175 | | | | | | | |
| | 3.0 | 2.0 | TCE - 4 | 0 - 2 | 300 | 300 | 300 | 300 | T12-150 | T12-150 | T16-150 | T16-150 | T12-150 | T16-150 | T20-150 | T12-150 | T12-250 | T12-250 | T12-150 | T12-150 | T16-150 | | | | | | |
| | | | TCE - 5 | 2 - 4 | 400 | 400 | 400 | 350 | T16-175 | T12-175 | T20-175 | T16-175 | T12-175 | T20-175 | T12-175 | T12-250 | T12-250 | T12-150 | T12-150 | T16-150 | | | | | | | |
| | | | TCE - 6 | 4 - 6 | 500 | 500 | 500 | 400 | T16-150 | T12-150 | T20-150 | T16-150 | T12-150 | T20-150 | T12-150 | T12-250 | T12-250 | T12-175 | T12-175 | T16-175 | | | | | | | |
| | 3.0 | 3.0 | TCE - 7 | 0 - 2 | 350 | 350 | 350 | 350 | T12-150 | T12-150 | T16-150 | T16-150 | T12-150 | T16-150 | T20-150 | T12-150 | T12-250 | T12-250 | T12-150 | T12-150 | T16-150 | | | | | | |
| | | | TCE - 8 | 2 - 4 | 400 | 400 | 400 | 350 | T16-175 | T12-175 | T20-175 | T16-175 | T12-175 | T20-175 | T12-175 | T12-250 | T12-250 | T12-150 | T12-150 | T16-150 | | | | | | | |
| | | | TCE - 9 | 4 - 6 | 500 | 500 | 500 | 400 | T16-150 | T12-150 | T20-150 | T16-150 | T12-150 | T20-150 | T12-150 | T12-250 | T12-250 | T12-175 | T12-175 | T16-175 | | | | | | | |



CONSTRUCTION OF RAJAMAWATHA EXTENSION ROAD FROM KETAWALA TO MASPANNA ROAD, (FROM CH 07+560 TO 09+300 km)



DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS AND TRANSPORT

DESIGN OFFICE (C.P.), ROAD DEVELOPMENT AUTHORITY
06B SAMAGI NIWASA, GANNORUWA, PERADENIYA.
TEL : 0812234267 FAX : 0812234267 email : dacp@rda.gov.lk

TYPICAL BOX CULVERT AND WINGWALL DETAILS SCALE -

SURVEYED & PLOTTED : A.G. ARIYAWANSA
DESIGNED : A.G. ARIYAWANSA
DRAWN : J.C. RAJAPAKSHA
CHECKED : A.G. ARIYAWANSA

C.E (DESIGN) : A.G. ARIYAWANSA
D.D.(DESIGN) : L.V.S. WEERAKOON
DATE : 23.03.2023
DRG No. : DD/ID/CP/UVA/TP/1267/1.5/03-07






GENERAL NOTES

1. ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE STATED.
2. THIS DRAWINGS TO SUIT SITE CONDITIONS SHALL BE DECIDED BY THE ENGINEER AT CONSTRUCTION STAGE.
3. CONCRETE GRADE SHALL BE GR. 30/19
4. REINFORCEMENT SHALL BE HOT ROLLED HIGH YIELD STEEL TO BS 4469 WITH MIN $f_y = 460$ N/SQMM
5. CLEAR COVER TO REINFORCEMENT SHALL BE 50 MIN.
6. MINIMUM RADIUS FOR SCHEDULING 3Ø
7. LAP LENGTH 5Ø
8. ANCHORAGE LENGTH 5Ø

SPECIAL NOTES

1. h - DROP WALL HEIGHT.
2. W - WIDTH OF OPENING
3. H - HEIGHT OF OPENING
4. Ts - TOP SLAB THICKNESS
5. Tb - BOTTOM SLAB THICKNESS
6. Tw - SIDE WALL THICKNESS
7. Tl - MID WALL THICKNESS
8. Tww - WING WALL THICKNESS



| CULVERT TYPE | INTERNAL DIMENSION | | WING WALL THICKNESS | REINFORCEMENT DETAILS | | | | | | |
|--------------|--------------------|------|---------------------|-----------------------|---------|----------|---------|--------|---------|---------|
| | W(m) | H(m) | | t1-t2-t3 | v1 | u1-u2-u3 | v2 | y | w | x |
| SINGLE CELL | 1.0 | 1.0 | 250 | T12-250 | T10-250 | T10-300 | T10-300 | 2 T 25 | T12-250 | T12-250 |
| | 1.5 | 1.0 | 250 | T12-250 | T10-250 | T10-300 | T10-300 | 2 T 25 | T12-250 | T12-250 |
| | 2.0 | 1.0 | 250 | T12-250 | T10-250 | T10-300 | T10-300 | 2 T 25 | T12-250 | T12-250 |
| | 2.5 | 1.0 | 250 | T12-250 | T10-250 | T10-300 | T10-300 | 2 T 25 | T12-250 | T12-250 |
| | 1.0 | 1.5 | 250 | T20-250 | T10-250 | T10-300 | T10-300 | 2 T 25 | T12-250 | T12-250 |
| | 1.5 | 1.5 | 250 | T20-250 | T10-250 | T10-300 | T10-300 | 2 T 25 | T12-250 | T12-250 |
| | 2.0 | 1.5 | 250 | T20-250 | T10-250 | T10-300 | T10-300 | 2 T 25 | T12-250 | T12-250 |
| | 2.5 | 1.5 | 250 | T20-250 | T10-250 | T10-300 | T10-300 | 2 T 25 | T12-250 | T12-250 |
| | 1.0 | 2.0 | 300 | T16-125 | T12-250 | T10-250 | T10-250 | 3 T 25 | T12-250 | T12-250 |
| | 1.5 | 2.0 | 300 | T16-125 | T12-250 | T10-250 | T10-250 | 3 T 25 | T12-250 | T12-250 |
| | 2.0 | 2.0 | 300 | T16-125 | T12-250 | T10-250 | T10-250 | 3 T 25 | T12-250 | T12-250 |
| | 2.5 | 2.0 | 300 | T25-125 | T12-250 | T10-250 | T10-250 | 3 T 25 | T12-250 | T12-250 |
| | 1.0 | 2.5 | 300 | T25-125 | T12-250 | T10-250 | T10-250 | 3 T 25 | T12-250 | T12-250 |
| | 1.5 | 2.5 | 300 | T25-125 | T12-250 | T10-250 | T10-250 | 3 T 25 | T12-250 | T12-250 |
| | 2.0 | 2.5 | 300 | T25-125 | T12-250 | T10-250 | T10-250 | 3 T 25 | T12-250 | T12-250 |
| | 2.5 | 2.5 | 300 | T25-125 | T12-250 | T10-250 | T10-250 | 3 T 25 | T12-250 | T12-250 |

CONSTRUCTION OF RAJAMAWATHA EXTENSION ROAD FROM KETAWALA TO MASPANNA ROAD, (FROM CH 07+560 TO 09+300 km)

TYPICAL BOX CULVERT AND WINGWALL DETAILS




SCALE -

| REV | DESCRIPTION | BY | DATE |
|-----|-------------|----|------|
| | | | |
| | | | |
| | | | |

DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS AND TRANSPORT

SURVEYED & PLOTTED :
DESIGNED : A.G.ARIYAWANSA
DRAWN : J.C. RAJAPAKSHA
CHECKED : A.G.ARIYAWANSA

C.E. (DESIGN) : A.G.ARIYAWANSA
D.D.(DESIGN) : L.V.S.WEERAKOON
DATE : 23-03-2023
DRG.No. : DD/ID/CP/UVA/TP/1267/1.5/04-07



GENERAL NOTE:

1. ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE SPECIFIED.
2. ALL MATERIALS AND WORKMANSHIP ARE TO BE IN ACCORDANCE WITH OF THE SPECIFICATION.
3. TYPE & NUMBERS OF COVER SLAB SHALL BE INSTRUCTED BY THE ENGINEER.

CONCRETE:

1. EXPOSED SHARP EDGES OF CONCRETE SHALL BE CHAMFERED.
2. APPROPRIATE PROVISIONS TO BE MADE TO FACILITATE HANDLING OF SLAB.
3. CONCRETE GRADE SHALL BE USED AS FOLLOWS:
 - (a) PRECAST RCC: GRADE 25/19
 - (b) DRAIN BASE: GRADE 20/19

REINFORCEMENT:

1. ALL BARS MARKED "R" SHALL BE HOT ROLLED MILD STEEL PLAIN BARS OF YIELD STRENGTH NOT LESS THAN 250 N/mm.
2. ALL BARS MARKED "T" SHALL BE HIGH YIELD DEFORMED BARS OF YIELD STRENGTH NOT LESS THAN 460 N/mm.
3. REINFORCEMENT BARS SHALL BE BENT ACCORDANCE WITH STANDARD SPECIFICATIONS.
4. CLEAR COVER FOR ALL REINFORCEMENT SHALL BE 20 mm MINIMUM.

WEEP HOLE:

1. WEEP HOLE TO BE PROVIDED AT 2000mm C/C STRAGGERED USING 75mm DIA. PVC PIPES.
2. AT THE PAVEMENT EDGE, THE WEEP HOLES TO BE PROVIDE AT THE BOTTOM OF ABC. IF THE DEPTH OF CONCRETE DRAIN IS LESS THAN BOTTOM LEVEL OF ABC, THE WEEP HOLE AT THE PAVEMENT EDGE SHALL BE PROVIDE HIGHER THAN THE BOTTOM SLAB OF CONCRETE DRAIN 100 mm OR AS INSTRUTED BY THE ENGINEER.
3. WEEP HOLES SHALL BE PLACE 45 DEGREES HORIZONTAL ANGLE TO MATCH WATER FLOW DIRECTION OF CONCRETE "U" DRAIN.

SPECIAL NOTE

DRAIN TYPE AND THE HEIGHT OF THE DRAIN TO BE DECIDED TO SUITE SITE CONDITION AS DIRECTED BY THE ENGINEER.

CONSTRUCTION OF RAJAMAWATHA EXTENSION ROAD FROM KETAWALA TO MASPANNA (FROM CH 07+560 TO 09+300 km)

TYPICAL DETAILS OF "U" DRAIN AND COVER SLAB

SCALE -

| REV | DESCRIPTION | BY | DATE |
|-----|-------------|----|------|
| | | | |
| | | | |
| | | | |



DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS AND TRANSPORT



DESIGN OFFICE (C.P.),
ROAD DEVELOPMENT AUTHORITY
06B SAMAGI NIWASA, GANNORUWA, PERADENIYA.
TEL : 0812234267 FAX : 0812234267 email : dacp@rda.gov.lk

SURVEYED & PLOTTED :

DESIGNED :
A.G.ARIYAWANSA

DRAWN :
J.C.RAJAPAKSHA





CHECKED :
A.G.ARIYAWANSA

C.E (DESIGN) :
A.G.ARIYAWANSA

D.D (DESIGN)
L.V.S.WEERAKOON

DATE : 23-03-2023

DRG No. : DD/D/CP/UVA/TP/1267/1.5/06-07



| GABION WALL TYPE | HEIGHT OF THE WALL ABOVE THE GROUND LEVEL (m) | PASSIVE EARTH HEIGHT |
|------------------|---|----------------------|
| C.B.G - 1 | 2.00 | 0.5 |
| C.B.G - 2 | 3.00 | 0.6 |
| C.B.G - 3 | 4.00 | 0.7 |
| C.B.G - 4 | 5.00 | 0.8 |
| C.B.G - 5 | 6.00 | 0.9 |

SPECIFICATION

(1) Galvanization and Plastic Coating :

All the wire used in the manufacture of gabion system units, and that used for connecting them together, (which requires wire with diameter not less than 2.2mm) complies with the strictest international standards.

-BS 1052/80

-ASTM-A641-82 Class 3

The steel wire is heavily zinc coated for protection against corrosion.

-ASTM A641-82

- BS 443-82

The galvanization is coated with a PVC sheath of a nominal thickness of 0.50mm.

The main values for the PVC material are as follows.

-Colour : Gray - ASTM D1482-57T

-Specific weight : between 1.30 & 1.35 dN/dm³ -ASTM D792-91

-Hardness: between 50 & 60 -ASTM D2240-91

-Tensile strength : not less than 210dN/cm² - ASTM D412-92

-Elongation : between 200% & 280% - ASTM D412-92

-Weight loss : less than 5% after 24hrs. at 105c -ASTM D2287-92

-Residual ashes : less than 2% - ASTM D2124-62T

-Abrasion resistance: loss in volume less than 0.30cm³ ASTM D1242-56(75) Test method A

CONSTRUCTION OF RAJAMAWATHA EXTENSION ROAD FROM KETAWALA TO MASPANNA (FROM CH 07+560 TO 09+300 km)

TYPICAL GABION WALL SECTION WITH CONCRETE BASE

SCALE -

| REV | DESCRIPTION | BY | DATE |
|-----|-------------|----|------|
| | | | |
| | | | |
| | | | |



DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS AND TRANSPORT



DESIGN OFFICE (C.P.),
ROAD DEVELOPMENT AUTHORITY
06B, SAMAGI NIWASA, GANNORUWA, PERADENIYA.
TEL : 0812234267 FAX : 0812234267 email : dacp@rda.gov.lk

SURVEYED & PLOTTED :

DESIGNED :
A.G. ARIYAWANSA

DRAWN :
J.C. RAJAPAKSHA






CHECKED :
A.G. ARIYAWANSA

C.E. (DESIGN) :
A.G. ARIYAWANSA

D.D. (DESIGN)
L.V.S. WEERAKOON

DATE : 23-03-2023

DRG No. : DD/D/CP/UVA/TP/1267/1.5/05-07



SPECIFICATION

(1) Galvanization and Plastic Coating :

All the wire used in the manufacture of gabion system units, and that used for connecting them together, (which requires wire with diameter not less than 2.2mm) complies with the strictest international standards.

- BS 1052/80
- ASTM-A641-82 Class 3

The steel wire is heavily zinc coated for protection against corrosion.

- ASTM a641-82
- BS 443-82

The galvanization is coated with a PVC sheath of a nominal thickness of 0.50mm. The main values for the PVC material are as follows.

- Colour : Gray - ASTM D1482-57T
- Specific weight : between 1.30 & 1.35 dN/dm³ -ASTM D792-91
- Hardness: between 50 & 60 -ASTM D2240-91
- Tensile strength : not less than 210dN/cm² -ASTM D412-92
- Elongation : between 200% & 280% -ASTM D412-92
- Weight loss : less than 5% after 24hrs. at 105c -ASTM D2287-92
- Residual ashes : less than 2% -ASTM D2124-62T
- Abrasion resistance: loss in volume less than 0.30cm³ ASTM D1242-56(75) Test method A

| GABION WALL TYPE | HEIGHT OF THE WALL ABOVE THE GROUND LEVEL (m) | PASSIVE EARTH HEIGHT |
|------------------|---|----------------------|
| S.B - 1 | 1.90 | 0.5 |
| S.B - 2 | 2.85 | 0.6 |
| S.B - 3 | 3.80 | 0.7 |
| S.B - 4 | 4.75 | 0.8 |
| S.G - 5 | 5.70 | 0.9 |

CONSTRUCTION OF RAJAWATHA EXTENSION ROAD FROM KETAWALA TO MASPANNA (FROM CH 07+560 TO 09+300 km)

| REV | DESCRIPTION | BY | DATE |
|-----|-------------|----|------|
| | | | |
| | | | |
| | | | |

DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS AND TRANSPORT

| | | | |
|----------------------------------|---------------------------------|----------------------------|--|
| SURVEYED & PLOTTED : | DESIGNED : A.G.ARIYAWANSA | DRAWN : J.C. RAJAPAKSHA | CHECKED : A.G.ARIYAWANSA |
| C.E (DESIGN) : A.G.ARIYAWANSA | D.D (DESIGN) L.V.S.WEERAKOON | DATE : 23-03-2023 | DRG No. : DD/DI/CP/IVA/TP/1267/1.5/07-07 |

TYPICAL GABION WALL SECTION WITH ROCK BASE SCALE -